PLAQUEMINES

PLAQUEMINES EXPANSION, LLC
AND VENTURE GLOBAL PLAQUEMINES LNG, LLC

PLAQUEMINES EXPANSION PROJECT

Draft
Resource Report 1

General Project Description

Docket No.
PF25-7-000

Prepared by
Burns & McDonnell Engineering Company, Inc

August 2025

PLAQUEMINES EXPANSION, LLC AND VENTURE GLOBAL PLAQUEMINES LNG, LLC

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1 – GENERAL PROJECT DESCRIPTION

Resource Report 1 – General Project Description	
Full Filing Requirements	
Information	**Report Section Reference**
This report is required for all applications. It will describe facilities associated with the project, special construction and operation procedures, construction timetables, future plans for related construction, compliance with regulations and codes, and permits that must be obtained. Resource Report 1 must:	
☐ 1. Describe and provide location maps of all jurisdictional facilities, including all aboveground facilities associated with the project (such as: meter stations, pig launchers/receivers, valves), to be constructed, modified, abandoned, replaced, or removed, including related construction and operational support activities and areas such as maintenance bases, staging areas, communications towers, power lines, and new access roads (roads to be built or modified). As relevant, the report must describe the length and diameter of the pipeline, the types of aboveground facilities that would be installed, and associated land requirements. It must also identify other companies that must construct jurisdictional facilities related to the project, where the facilities would be located, and where they are in the Commission's approval process.	1.3, appendix 1A
☐ 2. Identify and describe all nonjurisdictional facilities, including auxiliary facilities, that will be built in association with the project, including facilities to be built by other companies. (i) Provide the following information: (A) A brief description of each facility, including as appropriate: Ownership, land requirements, gas consumption, megawatt size, construction status, and an update of the latest status of federal, state, and local permits/approvals; (B) The length and diameter of any interconnecting pipeline; (C) Current 1:24,000/1:25,000 scale topographic maps showing the location of the facilities; (D) Correspondence with the appropriate State Historic Preservation Officer (SHPO) or duly authorized Tribal Historic Preservation Officer (THPO) for tribal lands regarding whether properties eligible for listing on the National Register of Historic Places (NRHP) would be affected; (E) Correspondence with the U.S. Fish and Wildlife Service (and National Marine Fisheries Service, if appropriate) regarding potential impacts of the proposed facility on federally listed threatened and endangered species; and (F) For facilities within a designated coastal zone management area, a consistency determination or evidence that the owner has requested a consistency determination from the state's coastal zone management program. (ii) Address each of the following factors and indicate which ones, if any, appear to indicate the need for the Commission to do an environmental review of project-related nonjurisdictional facilities. (A) Whether or not the regulated activity comprises “merely a link” in a corridor type project (e.g., a transportation or utility transmission project). (B) Whether there are aspects of the nonjurisdictional facility in the immediate vicinity of the regulated activity which uniquely determine the location and configuration of the regulated activity. (C) The extent to which the entire project will be within the Commission's jurisdiction. (D) The extent of cumulative federal control and responsibility.	1.8 and 1.10, appendix 1A
☐ 3. Provide the following maps and photos: (i) Current, original United States Geological Survey 7.5-minute series topographic maps or maps of equivalent detail, covering at least a 0.5-mile-wide corridor centered on the pipeline, with integer mileposts identified, showing the location of rights-of-way, new access roads, other linear construction areas, compressor stations, and pipe storage areas. Show nonlinear construction areas on maps at a scale of 1:3,600 or larger keyed graphically and by milepost to the right-of-way maps. (ii) Original aerial images or photographs or photo-based alignment sheets based on these sources, not more than 1 year old (unless older ones accurately depict current land use and	Appendix 1A

Resource Report 1 – General Project Description	
Full Filing Requirements	
Information	**Report Section Reference**
development) and with a scale of 1:6,000 or larger, showing the proposed pipeline route and location of major aboveground facilities, covering at least a 0.5 mile- wide corridor, and including mileposts. Older images/photographs/alignment sheets should be modified to show any residences not depicted in the original. Alternative formats (e.g., blue-line prints of acceptable resolution) need prior approval by the environmental staff of the Office of Energy Projects. (iii) In addition to the copy required under §157.6(a)(2) of this chapter, applicant should send two additional copies of topographic maps and aerial images/photographs directly to the environmental staff of the Office of Energy Projects.	
☐ 4. When new or additional compression is proposed, include large scale (1:3,600 or greater) plot plans of each compressor station. The plot plan should reference a readily identifiable point(s) on the U.S. Geological Survey maps required in paragraph (c)(3) of this section. The maps and plot plans must identify the location of the nearest noise-sensitive areas (schools, hospitals, or residences) within 1 mile of the compressor station, existing and proposed compressor and auxiliary buildings, access roads, and the limits of areas that would be permanently disturbed.	Not Applicable
☐ 5. (i) Identify facilities to be abandoned, and state how they would be abandoned, how the site would be restored, who would own the site or right-of-way after abandonment, and who would be responsible for any facilities abandoned in place. (ii) When the right-of-way or the easement would be abandoned, identify whether landowners were given the opportunity to request that the facilities on their property, including foundations and below ground components, be removed. Identify any landowners whose preferences the company does not intend to honor, and the reasons therefore.	Not Applicable
☐ 6. Describe and identify by milepost, proposed construction and restoration methods to be used in areas of rugged topography, residential areas, active croplands, sites where the pipeline would be located parallel to and under roads, and sites where explosives are likely to be used.	1.5
☐ 7. Unless provided in response to Resource Report 5, describe estimated workforce requirements, including the number of pipeline construction spreads, average workforce requirements for each construction spread and meter or compressor station, estimated duration of construction from initial clearing to final restoration, and number of personnel to be hired to operate the proposed project.	1.5 and Resource Report 5
☐ 8. Describe reasonably foreseeable plans for future expansion of facilities, including additional land requirements and the compatibility of those plans with the current proposal.	1.7
☐ 9. Describe all authorizations required to complete the proposed action and the status of applications for such authorizations. Identify environmental mitigation requirements specified in any permit or proposed in any permit application to the extent not specified elsewhere in this section.	1.9, table 1.9-1 in appendix 1B
☐ 10. Provide the names and mailing addresses of all affected landowners specified in §157.6(d) and certify that all affected landowners will be notified as required in §157.6(d).	Appendix 1F

Federal Energy Regulatory Commission Comments dated June 23, 2025 on the Preliminary Draft of Resource Report 1		
Number	**Comment**	**Response/Report Section Reference**
1	Sections 1.1 and 1.8 reference a new non-jurisdictional intrastate natural gas pipeline proposed to be built to supply natural gas to the Project, as well as new utility service connections to a local electric power system, water supply, and fiber optic telecommunications. Provide the following information, as applicable, related to the new non-jurisdictional facilities: (A) A brief description of each facility, including as appropriate: ownership, land requirements, gas consumption, megawatt size, construction status, and an update of the latest status of federal, state, and local permits/approvals; (B) The length and diameter of any interconnecting pipeline; (C) Current 1:24,000/1:25,000 scale topographic maps showing the location of the facilities; (D) Correspondence with the appropriate State Historic Preservation Office and duly authorized Tribal Historic Preservation Office (for tribal lands) regarding whether properties eligible for listing on the National Register of Historic Places would be affected; (E) Correspondence with the U.S. Fish and Wildlife Service (and National Marine Fisheries Service, if appropriate) regarding potential impacts of the proposed facility on federally listed threatened and endangered species; and (F) For facilities within a designated coastal zone management area, a consistency determination or evidence that the owner has requested a consistency determination from the state's coastal zone management program.	This is addressed in section 1.8.
2	As described in section 1.3, the liquified natural gas (LNG) for the Project would be stored in previously authorized containment tanks associated with the existing Plaquemines LNG Terminal. Provide additional details regarding the piping that would be constructed to transport LNG from the Project to the existing LNG storage tanks at the Plaquemines LNG Terminal, including the number and size of pipes to be constructed, construction equipment, and location of the pipes.	Section 1.3.1 has been revised to incorporate this information.
3	As referenced in section 1.3, provide additional information regarding the stormwater piping system and outfalls for the Project, including the size and location of the piping to be used to transport the stormwater to the adjacent existing Plaquemines LNG Terminal site, and the location of the proposed outfall structure.	Section 1.3 has been revised to incorporate this information.
4	As described in Resource Report 1, Plaquemines Expansion, LLC and Venture Global Plaquemines LNG, LLC are proposing to construct one new marine berth associated with the Project. Describe if and how the existing Plaquemines LNG marine berths would be used to support the Project, including the estimated number of ships that would be loaded at the new marine berth versus the existing marine berths, and the ability of the existing marine berths to accommodate the additional ship traffic to be generated by the Project.	The four marine berths are evaluated as a unified system to allow for more accurate assessment of operational needs. Additional discussion has been added to section 1.3.3 to clarify this.
5	Provide an updated version of section 1.3.1 that indicates approximately how long an arriving LNG carrier is expected to remain at the marine loading berth before departing.	Section 1.3.3 (previously section 1.3.1) has been revised to incorporate this information.
6	Section 1.9 states that initial consultation with permitting agencies is anticipated to commence in May 2025. Provide copies of all correspondence with permitting and resource management agencies, and as applicable, provide an updated version of table 1.9-1 that reflects the consultation and permitting efforts.	Updates provided in table 1.9-1 and appendix 1B.
7	Provide an updated version of section 1.11 that identifies potential projects located within the identified resource-specific geographic regions for cumulative impact assessment identified in table 1.11-1 and an assessment of potential cumulative impacts associated with construction and/or operation of the Project as it relates to each potential environmental resource.	Table 1.11-1 has been revised to incorporate this information.

Federal Energy Regulatory Commission Comments dated June 23, 2025 on the Preliminary Draft of Resource Report 1		
Number	**Comment**	**Response/Report Section Reference**
8	Provide a table that identifies past, present, and reasonably foreseeable future projects within the resource-specific geographic scopes identified in the table below. This table should also include the following information: a. project name and sponsor/proponent; b. a description of the project; c. location (city/county); d. approximate distance and direction of the project from the (Project Name) facilities; e. the milepost location where it crosses the proposed facilities or the nearest proposed project facility milepost; f. the resource-specific geographic scope the project falls within (specify the name of the HUC-12 watershed, where applicable); g. footprint/layout and quantitative impacts on specific resources, if available (acres of land/resource [wetlands, vegetation, habitat, etc.] affected); h. any known permits/authorizations or environmental review required; and i. the current status and schedule of the project. j. Also, include qualitative and quantitative descriptions of cumulative and/or overlapping impacts these projects and the FERC Project would have on each environmental resource. Lastly, include a map showing the identified projects in relation to the Project.	Table 1.11-2 in appendix 1B has been included.
9	Provide an updated version of section 1.2 that discloses which overseas markets the Project is expecting to export LNG to, as well as provides a brief summary as to why the existing facility cannot meet the projected increase in export volumes.	Section 1.2 has been revised to incorporate clarification for this information.
10	Provide an updated version of section 1.5.1 that includes a detailed construction work schedule.	A Gantt chart indicating the project schedule for the full completion and commissioning of the project is included in appendix 13.A.5 of Resource Report 13.
11	Indicate the anticipated height of the new pipe trestle system above State Highway 23.	Section 1.3 has been revised to detail this information. The new pipe trestle system height will be similar with the existing Authorized Facilities design.
12	Provide additional details regarding the proposed flaring system, including the type of flares to be constructed, height and configuration of flares (if ground flares are not used), anticipated number of flare events monthly/annually, as well as the anticipated duration of flare events.	See section 1.3, with additional details in Resource Report 9.
13	Provide additional information regarding the temporary power generators and temporary utility line that would be used during construction. This additional information should include the number and size of generators, anticipated schedule of generator use, the location and size of utility lines, and the existing energy grid/system that the utility lines would interconnect with.	See section 1.3.3, with additional details in Resource Report 9.
14	Provide an estimate of the percentage of the workforce (construction and operational) that would consist of local residents, and the percentage of the workforce that would need to temporarily or permanently relocate to the area.	Section 1.5.1 has been revised to provide this information. See also Resource Report 5.
15	Indicate if any worker (construction and operational) transportation/commuting measures are proposed to mitigate the effects on local traffic levels from the increase in workers commuting to the area (e.g., ride sharing, busing services, development of off-site commuter lots, etc.).	At this time, no offsite commuter lots have been identified, however, use of park and rides lots are being considered. See section 1.5.4 for transportation discussion.
16	Provide the estimated number of marine deliveries of construction materials, including the frequency of the deliveries.	Section 1.5.4 has been revised to provide this information.

PLAQUEMINES EXPANSION, LLC AND VENTURE GLOBAL PLAQUEMINES LNG, LLC

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1 – GENERAL PROJECT DESCRIPTION

TABLE OF CONTENTS

1.0 RESOURCE REPORT 1 – GENERAL PROJECT DESCRIPTION 1-1
1.1 INTRODUCTION 1-1
1.2 PURPOSE AND NEED 1-3
1.3 PROJECT FACILITIES 1-4
1.3.1 Expansion Facilities 1-4
1.3.2 Marine Berth 1-7
1.3.3 Facility Operational Design 1-9
1.4 LAND REQUIREMENTS 1-13
1.4.1 Expansion Facilities 1-13
1.4.2 Contractor Yards 1-13
1.4.3 Access Roads 1-14
1.5 CONSTRUCTION SCHEDULE AND PROCEDURES 1-14
1.5.1 Construction Schedule and Workforce 1-14
1.5.2 Construction Procedures 1-14
1.5.3 Expansion Facilities 1-16
1.5.4 Site Access and Traffic 1-20
1.6 OPERATION AND MAINTENANCE 1-20
1.6.1 Operation 1-20
1.6.2 Maintenance 1-21
1.7 FUTURE EXPANSION AND ABANDONMENT PLANS 1-21
1.8 NON-JURISDICTIONAL FACILITIES 1-21
1.8.1 Intrastate Natural Gas Pipeline 1-21
1.8.2 Utility Service Connections 1-23
1.9 PERMITS AND APPROVALS 1-23
1.10 AGENCY, PUBLIC, AND OTHER STAKEHOLDER COMMUNICATIONS 1-23
1.11 CUMULATIVE IMPACTS AND INDIRECT EFFECTS 1-26
1.11.1 Projects and Other Reasonably Foreseeable Future Actions Considered in the Cumulative Impacts Analysis 1-28
1.11.2 Potential Cumulative Impacts by Resource 1-30
1.12 REFERENCES 1-39

LIST OF TABLES

Table 1.4-1 Summary of Land Requirements at the Expansion Facilities 1-13
Table 1.8-1 Summary of Required Permits for Proposed Non-Jurisdictional Pipeline 1-22
Table 1.10-1 Summary of Plaquemines Expansion Open Houses 1-25
Table 1.11-1 Resource-Specific Geographic Regions for the Cumulative Impact Assessment 1-26

LIST OF APPENDICES

Appendix 1A Project Maps and Figures

Figure 1.1-1	Regional Location of Proposed Project (Topographic Map)
Figure 1.1-2	Regional Location of Proposed Project (Aerial Map)
Figure 1.1-3	Proposed Expansion Facilities (layout)
Figure 1.3-1	Proposed Expansion Facilities (Aerial Map) (*filed under separate cover as Controlled Unclassified Information (CUI)//Critical Energy Infrastructure Information (CEII)*)
Figure 1.3-2	Proposed Expansion Facilities (Topographic Map) (*Filed under separate cover as CUI//CEII*)
Figure 1.11-1	Projects Considered in Cumulative Impact Analysis

Appendix 1B Appendix Tables

Table 1.9-1	Permits, Approvals, and Consultations
Table 1.11-2	Projects and Reasonably Foreseeable Future Actions with Potential to Contribute to Cumulative Impacts

Appendix 1C Upland Erosion Control, Revegetation and Maintenance Plan

Appendix 1D Wetland and Waterbody Construction Mitigation Procedures

Appendix 1E Project Correspondence to Landowners and Stakeholders (to-date)

Appendix 1F Landowner List (*filed under separate cover as CUI//Privileged and Confidential (PRIV)*)

Appendix 1G Stakeholder List (*filed under separate cover as CUI//PRIV)*

ACRONYMS AND ABBREVIATIONS

Applicants	Plaquemines Expansion, LLC and Venture Global Plaquemines LNG, LLC
Application	The application to the Federal Energy Regulatory Commission of the Applicants for authorization to site, construct, and operate natural gas liquefaction and export facilities.
Authorized Facilities	The permanent land- and marine-based Plaquemines LNG natural gas liquefaction, storage, and export facilities
Bcfd	billion cubic feet per day
CCTV	closed-circuit television system
CEII	Critical Energy Infrastructure Information
CFR	Code of Federal Regulations
CO_2	carbon dioxide
Commission	Federal Energy Regulatory Commission
CPRA	Coastal Protection and Restoration Authority
CUI	Controlled Unclassified Information
CWA	Clean Water Act
DOE	U.S. Department of Energy
DOT	U.S. Department of Transportation
DOTD	Louisiana Department of Transportation and Development
EI	Environmental Inspector
EIA	U.S. Energy Information Administration
ESD	emergency shutdown
Expansion Facilities	permanent land- and marine-based Plaquemines Expansion natural gas liquefaction, storage, and export facilities
FERC	Federal Energy Regulatory Commission
GDP	gross domestic product
H_2S	hydrogen sulfide
HDPE	high density polyethylene
LDENR	Louisiana Department of Energy and Natural Resources
LDEQ	Louisiana Department of Environmental Quality
LNG	liquefied natural gas
LPDES	Louisiana Pollution Discharge Elimination System
m^3	cubic meters
m^3/hr	cubic meters per hour
MOF	material offloading facility
MTPA	million tonnes per annum
NGA	Natural Gas Act
NFPA	National Fire Protection Association
PHMSA	Pipeline and Hazardous Materials Safety Administration
Plan	FERC Upland Erosion Control, Revegetation, and Maintenance Plan
Plaquemines Expansion	Plaquemines Expansion, LLC
Plaquemines LNG	Venture Global Plaquemines LNG, LLC
ppmv	parts per million by volume

Procedures	FERC Wetland and Waterbody Construction and Mitigation Procedures
Project	Plaquemines Expansion Project
SH	State Highway
SMR	single mixed refrigerant
SWPPP	Stormwater Pollution Prevention Plan
USACE	U.S. Army Corps of Engineers
USCG	U.S. Coast Guard
Venture Global	Venture Global LNG, Inc.

PLAQUEMINES EXPANSION, LLC AND VENTURE GLOBAL PLAQUEMINES LNG, LLC

PLAQUEMINES EXPANSION PROJECT

1.0 RESOURCE REPORT 1 – GENERAL PROJECT DESCRIPTION

1.1 INTRODUCTION

Resource Reports 1 through 13 collectively make up the Environmental Report submitted to the Federal Energy Regulatory Commission ("FERC" or "Commission") as part of the application (the "Application") of Plaquemines Expansion, LLC ("Plaquemines Expansion") and Venture Global Plaquemines LNG, LLC ("Plaquemines LNG"), together referred to as the "Applicants" and both wholly owned subsidiaries of Venture Global LNG, Inc. ("Venture Global"), for the proposed expansion ("Project") of the Plaquemines LNG Terminal that is currently under construction in Plaquemines Parish, Louisiana. The Application is submitted pursuant to section 3 of the Natural Gas Act ("NGA"), and the Environmental Report is submitted in accordance with Title 18 of the Code of Federal Regulations ("CFR") Section 380.12.

On September 30, 2019, the Commission authorized Plaquemines LNG to site, construct and operate a new liquefied natural gas ("LNG") export terminal and associated facilities along the Mississippi River in Plaquemines Parish, Louisiana.[1] The Authorized Facilities at the Plaquemines LNG export terminal include: (a) one natural gas gate station; (b) six pretreatment facilities; (c) 18 liquefaction blocks; (d) four full containment above ground storage tanks; (e) boil-off, flash, and gas relief systems; (f) three LNG loading berths; (g) two 710-megawatt electric power generation plants; (h) one warm flare, one cold flare, one spare flare, one low pressure flare, and one marine flare; (i) safety and security systems; and (j) other appurtenant facilities. The Authorized Facilities are under construction and Plaquemines LNG has commenced the export of commissioning cargos.[2]

As part of this Project, Plaquemines Expansion proposes to build, own, and operate additional liquefaction facilities capable of producing peak capacity of approximately 24.8 million metric tonnes per annum ("MTPA") and other facilities detailed below. The Project will be situated on an approximately 462-acre permanent site immediately adjacent to the approximately 632-acre site on which the Authorized Facilities are located. An additional 562 acres adjacent to the permanent Project site will be used during construction and approximately 77 acres of existing workspace from the Authorized Facilities will be utilized during construction. The marine facilities and associated workspace will be located on approximately 62 acres.

The Project facilities will include (a) one natural gas gate station; (b) five pretreatment facilities; (c) 16 liquefaction blocks capable of producing approximately 24.8 MTPA; (d) seven LNG expanders; (e) boil-off, flash, and gas relief systems; (f) one LNG loading berth for ocean-

[1] Venture Global Plaquemines LNG, LLC and Venture Global Gator Express, LLC, 168 FERC ¶ 61,204 (2019) ("2019 Order"). The LNG terminal facilities authorized by the 2019 Order are collectively referred to herein as "Authorized Facilities." The 2019 Order also authorized Venture Global Gator Express, LLC to construct and operate a new natural gas pipeline system within Plaquemines Parish. The Commission recently authorized the increase in the maximum liquefaction capacity of the Authorized Facilities without any new facilities, construction activities, or facility modifications. Venture Global Plaquemines LNG, LLC, 190 FERC ¶ 61,113 (2025).

[2] The Commission approved Plaquemines LNG's request to load the first LNG export cargo on December 20, 2024. Accession No. 20241220-3027, Delegated Order issued in Docket No. CP17-66-000. Plaquemines LNG files both monthly construction reports and weekly commissioning reports with the Commission in that docket.

going vessels; (g) one warm flare, one cold flare, one spare flare, and one marine flare; (h) two 710-megawatt natural gas-fired combined cycle electric generation facilities; (i) safety and security systems; and (j) other appurtenant facilities. The Applicants expect to begin construction of the Project upon receipt of all required regulatory approvals, as detailed below. The Project will be interconnected with the Plaquemines LNG terminal and will share in the utilization of certain Authorized Facilities, including treated gas, utilities, LNG storage tanks, low pressure flare, LNG loading berths, marine flare, electrical power generation, and other appurtenant facilities. The Project will not include any new FERC-jurisdictional interstate pipeline facilities: rather, feed gas for the Project will be delivered by a non-jurisdictional intrastate natural gas transmission pipeline system that will be constructed by an affiliate of the Applicants that will connect the Project to the existing natural gas pipeline network in northern Louisiana, and will provide feed gas to the liquefaction and power generation facilities. This pipeline is further described in section 1.8.[3]

The Applicants will work with the Commission and other interested federal, state, and local agencies to obtain all necessary permits and approvals for the Project. Following the receipt of Commission authorization and other necessary approvals, the Applicants plan to begin construction of the Project by early 2027.

In accordance with the pre-filing review process, the Applicants are committed to conducting an engaged review of the Project with stakeholders and will work to address their concerns where feasible. The Applicants will submit in this docket periodic updates of any changes to the Project.

The Project will initiate construction upon receipt of regulatory approvals to begin construction. The entire construction period is expected to be approximately four years. The Project facilities are illustrated in the series of figures contained in appendix 1A, as described below.

- Figures 1.1-1, 1.1-2 and 1.1-3 show the regional location of the Project facilities on an aerial map and U.S. Geological Survey topographic map, respectively.

- Figures 1.3-1 and 1.3-2 (filed under separate cover as Controlled Unclassified Information/Critical Energy Infrastructure Information [“CUI/CEII”]) provide a detailed layout of the Expansion Facilities on aerial and topographic maps, respectively.

The Project will be sited, constructed and operated pursuant to Section 3 of the NGA. The Applicants intend to own the natural gas and the LNG that passes through the Project facilities prior to the sale of LNG to third parties, and/or to act as agent for third parties under tolling arrangements pursuant to long-term off-take agreements. The Applicants will construct, own, and operate the Project facilities and will bear responsibility for related costs.

On March 6, 2025, the Applicants requested that FERC initiate the pre-filing process for reviewing the Project under the National Environmental Policy Act. This request was approved by the Director of the Office of Energy Projects on April 4, 2025, in FERC Docket Number PF25-7-000.

[3] The new intrastate natural gas pipeline is expected to consist of approximately 300 miles of 48-inch-diameter pipeline, with firm transportation capacity of approximately 4.5 billion cubic feet per day.

The Applicants plan to apply under Section 3 of the Natural Gas Act to the Department of Energy/Office of Fossil Energy during FERC's pre-filing review process to export up to 24.8 MTPA of LNG to Free Trade Agreement and non-Free Trade Agreement nations.

Resource Report 1 describes the Project and its purpose and need from a local, regional, national, and global perspective. In accordance with CFR, Title 18, § 380.12, this report discusses facility layout and design, construction schedule, land requirements, operation and maintenance procedures, non-jurisdictional facilities, applicable regulatory approvals, and agency coordination.

1.2 PURPOSE AND NEED

The Project's objective is to convert domestically produced natural gas to LNG for storage and export to overseas markets, which will encourage the development of new domestic resources, and promote a liberalized global natural gas trade and greater diversification of global supplies. The specific markets will depend on global demand dynamics and commercial arrangements in place at the time of export, subject to authorization from the U.S. Department of Energy ("DOE"). The Commission has authorized the Plaquemines LNG facility to produce up to a total of 27.2 MTPA of LNG for export; therefore, the Applicants are developing the Project to enable the production of up to 24.8 MTPA of additional LNG for export. Once complete, together, the Authorized Facilities and Expansion Facilities will enable the combined production of 52 MTPA of LNG for export.[4]

Based on data from the Potential Gas Committee's biennial reports combined with U.S. Energy Information Administration ("EIA") data from the 2021 Annual Energy Outlook, the "total U.S. future supply of natural gas stands at an all-time record 3,863 Tcf [trillion cubic feet], which is well in excess of 100 years of supply at current consumption levels." This outlook is further supported by the DOE *Energy, Economic, and Environmental Assessment of U.S. LNG Exports* study which found that modeled U.S. domestic natural gas supply is sufficient to meet the modeled global demand for U.S. LNG exports while continuing to meet domestic demand (DOE, 2024).

According to the EIA, U.S. LNG exports are anticipated to increase by 3.3 billion cubic feet per day ("Bcfd") in 2025 and are expected to grow by 1.2 Bcfd in 2026 (EIA, 2025). Others forecast that the global demand for this abundant and clean form of energy will double by 2040. Customers in markets around the world are importing more U.S. LNG to provide their citizens with a cleaner alternative to coal and other higher carbon intensity forms of energy. American LNG also provides security and diversity of supply to countries who wish to increase their own national security. The DOE has consistently recognized that LNG exports have macroeconomic benefits and are consistent with the public interest. The U.S. LNG industry contributed more than $400 billion dollars to the U.S. gross domestic product ("GDP") and supported hundreds of thousands of jobs since 2016 (S&P Global, 2024). The public interest in the export of LNG by The Applicants will be further detailed in its export application to be filed with the DOE Office of Fossil Energy. Additional discussion regarding the natural gas market is provided in Resource Report 13, section 13.1.4.

[4] FERC previously authorized the Plaquemines LNG facility to produce up to 24.0 MTPA of LNG under the 2019 Order. FERC issued an order approving an uprate amendment application on February 19, 2025, to 27.2 MTPA. Pursuant to orders issued on July 21, 2016 and June 13, 2022, the DOE Office of Fossil Energy authorized Plaquemines LNG to export up to 1,405.33 billion cubic feet per year of domestically produced LNG from the Authorized Facilities to free trade agreement countries. Pursuant to an order issued October 16, 2019, DOE has also authorized Plaquemines LNG to export up to 1,240 billion cubic feet per year of domestically produced LNG from the Authorized Facilities to non-free trade agreement countries. Plaquemines LNG's application to amend its non-free trade agreement authorization to increase the export capacity to 1,405.33 billion cubic feet per year is pending before DOE.

1.3 PROJECT FACILITIES

Once complete, the Project will consist of 16 LNG blocks, capable of producing a peak capacity of approximately 24.8 MTPA of LNG under optimal conditions. The LNG will be stored in the previously authorized full containment LNG storage tanks and loaded onto LNG carriers for export. The Project facilities are described in the following sections.

1.3.1 Expansion Facilities

1.3.1.1 Gas Gate Station

The Project will receive natural gas from a non-jurisdictional intrastate natural gas transmission pipeline consisting of two parallel segments at the Project's gas gate station to be constructed onsite near the southwest boundary of the existing Plaquemines LNG facility. The gas gate station will contain non-jurisdictional intrastate pipeline equipment, including a filter/separator(s), custody transfer meter(s), emergency shut down ("ESD") valves, and gas analyzer located at the gas gate station. The Project's equipment that will interconnect with the pipeline at the gas gate station will include a tie-in to the inlet flange of the Project's custody meter, pig receiving facilities, ESD valves, and a gas analyzer. The gas gate station will be within an approximately 700-foot by 450-foot fenced area that will be located within the Project footprint.

1.3.1.2 Pretreatment Systems

The Project will have five pretreatment systems, each including an amine gas-sweetening unit to remove carbon dioxide ("CO_2") and a hybrid dehydration and heavy hydrocarbon removal unit to remove water and heavy hydrocarbons. Feed gas will be processed in the pretreatment systems before being directed to the LNG blocks as described below.

1.3.1.3 LNG Processing, Liquefaction Blocks and Refrigerant Storage

Sixteen liquefaction blocks, powered by electric motors, will contain the following liquefaction equipment:

- two single mixed refrigerant ("SMR") process units, including:
    - a two-stage mixed refrigerant centrifugal compressor with electric motor driver;
    - mixed refrigerant vapor and liquid separator vessels;
    - a cold box;
    - air cooled exchangers; and
    - a suction scrubber
- A refrigerant make-up system;
- A refrigerant storage site; and
- Distribution piping between the refrigerant storage site and the liquefaction blocks.

After liquefaction, LNG will be transferred from the Expansion Facility's liquefaction blocks to the LNG expanders, and subsequently to the LNG storage tanks at the Plaquemines LNG Terminal via aboveground piping interconnects. Pipe sections will be fabricated offsite and constructed by cranes once delivered. Plot plans which show the proposed piping within the Authorized Facilities are provided in appendix 13.E.6 filed as CUI/CEII as part of Resource Report 13.

1.3.1.4 Flare System

Two separate flare structures will be installed at the Expansion Facilities:

- a warm/cold/spare flare structure containing two separate flare headers to handle cold relief fluids and wet/warm relief fluids about 280 feet in height; and
- a low-pressure marine flare structure for low-velocity vapors from LNG carrier gas-up/cooldown operations about 100 feet in height.

The Expansion Facilities' flare system will be designed to safely and reliably dispose of vapor streams that may need to be vented during plant emergency conditions. The design of the flare system will be based on segregation of wet, dry, and low-pressure streams. As such, two separate systems, warm (wet) and cold (dry), will be provided for the Project. Additionally, the Project will also contain a common spare flare stack. Low-pressure relief/vents from the Project's boil-off gas compressors will be sent to the Authorized Facilities' low-pressure flare. Additional details regarding flare system details, including heights and diameters are provided with Resource Report 13. The expected frequency and duration of flaring events will be discussed in a subsequent filing of Resource Report 9.

1.3.1.5 Boil-off, Flash, and Gas Relief Systems

The boil-off, flash, and gas relief systems will include the following components:

- multiple electric-driven, boil-off gas compressors for recovering vapors generated from tank and pipeline heat leak, displaced gas from ship filling, and liquefaction flash gas (the recovered boil-off gases will be used as fuel by the Project's power generation facilities); and
- flares and associated piping for venting purge gas during plant startup and venting/flaring of gas during emergency operational situations.

1.3.1.6 Buildings

The Project will include a new control room adjacent to the Authorized Facilities existing control room. The Project anticipates using the Authorized facilities existing workshop, warehouse, electrical equipment, and other support structures.

1.3.1.7 Stormwater Piping System and Outfall

Stormwater from the Expansion Facilities will be routed back into the adjacent Plaquemines LNG Terminal Site and discharged through two outfalls at the perimeter outfalls associated with the Plaquemines LNG Terminal and from there will be discharged to the area surrounding the Plaquemines LNG Terminal Site. The outfalls will be regulated by the LDEQ under the Louisiana Pollutant Discharge Elimination System ("LPDES") program. The location

and footprint of the outfalls are depicted on Figure 1.1-1. The proposed outfalls will likely be 48 inches in diameter depending on final design.

1.3.1.8 Power Supply

Power for the Project operation is expected to be generated by two natural gas-fired combined cycle power plants, each with a generating capacity of 710 megawatts, designed to provide electrical power for the pretreatment and liquefaction systems, LNG loading pumps, boil-off gas compressors, site lighting, building loads, and other equipment that comprise the Project. Emergency power will be provided by diesel generators. Control and security systems will be powered through an uninterruptible power supply system with battery back-up.

The Expansion Facilities will also connect to a proposed 230 kilovolt interconnect substation located within the Project. This substation will connect the power plants at the Authorized Facilities to the power plants at the Expansion Facilities. The Expansion Facilities will also have access to up to 60 megawatts of supplemental power from Entergy Louisiana, LLC via the proposed substation at the Authorized Facilities. The utility connection will provide an alternate supplemental power source for the Authorized Facilities and the Expansion Facilities to enhance system reliability during peak operations and outages. Plaquemines LNG will seek a variance from FERC in docket no. CP17-66 for the additional electrical connection once the design is complete.

1.3.1.9 Water Supply

The Applicants' process service water requirements are expected to be sourced from the Mississippi River and processed by new facilities to be developed on the Project site. The Expansion Facilities' potable water needs will be provided from one or multiple connections to the local utility potable water system. The Project's liquefaction blocks will be air-cooled, significantly reducing the Project's operational process water requirements. The Project's power plants also will be air-cooled.

1.3.1.10 Communication System

The communication systems at the Expansion Facilities will include a telephone exchange, a public address and general alarm system, a ship-to-shore radio system, a computer network and email system, a plant telecommunication network, a telemetry system for data transfer to/from the Authorized Facilities, and a closed-circuit television system ("CCTV").

1.3.1.11 Project Safety

The Project will meet the applicable requirements of the regulations of the U.S. Coast Guard ("USCG") set forth in 33 CFR Part 127, the requirements of the U.S. Department of Transportation's ("DOT) Pipeline and Hazardous Materials Safety Administration ("PHMSA") in 49 CFR Part 193, and all other standards for safety and fire protection applicable to LNG terminals. These requirements and standards include the following technical safety measures:

- angular/linear displacement meters and alarms (jetty arms);
- quick connect/disconnect couplings (jetty arms);
- emergency system ship-to-shore interface point (jetty arms);

- impoundment basins for LNG spillages;
- fire, gas, and LNG spill detectors;
- emergency shutdown systems;
- firefighting systems (water deluge, foam generator, and dry powder);
- hazardous area classifications;
- depressurization and flare systems; and
- terminal security devices.

1.3.1.12 Project Security

The Project will be subject to USCG facility security regulations under the Marine Transportation Security Act (33 CFR Part 105) and will have a facility security plan approved by the USCG. The Project will meet the necessary security measures required under those regulations, including security fencing, lighting, access control, and a CCTV system.

1.3.2 Marine Berth

1.3.2.1 LNG Vessel Loading

The Project will include one new LNG loading berth, designed to accommodate LNG vessels ranging from 120,000 cubic meters ("m^3") to 210,000 m^3 of carrying capacity. Dredging is not required for the LNG vessels to access the new LNG loading berth from the Mississippi River given that the existing river water depths (i.e., 45 feet or greater) provide ample depth.

The new marine berth associated with the Project is summarized below and described in further detail in the subsequent paragraphs:

- aboveground cryogenic piping between the tanks' LNG pumps and the LNG loading berth;
- one trestle pipe system carrying LNG transfer piping and spill containment system, boil-off gas piping, and fire water piping between the Plaquemines LNG Terminal plant and the LNG loading berth; and
- one marine flare structure about 100 feet in height for LNG carrier gas-up/cool-down operations; and
- one jetty substation, providing electrical power to other marine facilities.

1.3.2.2 LNG Carrier Berthing Area

The LNG carrier berthing area will consist of one new LNG carrier loading berth designed to accommodate LNG carriers ranging from 120,000 m^3 to 210,000 m^3 of cargo capacity and that will include:

- one jetty;

- one loading platform;
- one LNG spill collection sump;
- four berthing dolphins;
- three bow mooring dolphins; and
- three stern mooring dolphins.

The new LNG loading berth will be constructed in the Mississippi River along the northern edge of the Authorized Facilities and will include a 19.6-acre operational footprint (12-acre land footprint and 7.6-acre water footprint). The LNG loading berth will be on the Mississippi River between river mile markers 54 and 55 and located south of the three existing LNG loading berths and the Material Offloading Facility ("MOF"). LNG carriers will access the berth via designated shipping routes.

The LNG loading berth will feature a 135-foot-long by 110-foot-wide concrete platform with a hydraulic gangway, lighting, control buildings, cathodic protection, and an LNG trough leading to a separate platform-mounted spill-sump. The loading berth will include one jetty, one loading platform, one LNG spill collection sump, four berthing dolphins, three bow mooring dolphins, and three stern mooring dolphins. The berth will also include a separate platform for a service water pumps and intake. The berth will have breasting dolphins on the interior and mooring dolphins on the outer sides. The berth platform, spill-sump platform, service water pump platform, breasting dolphins, and mooring dolphins will be supported on steel piles of various diameters. A staircase at either end of the berth will provide access between the walkway and the river shoreline.

The LNG loading platform will include three 16-inch-diameter LNG loading arms, and one 16-inch-diameter vapor return arm. Each loading arm will be equipped with the following:

- a hydraulic quick connect/disconnect coupler;
- a hydraulic double-ball, valve-powered emergency release coupler;
- swivel joints with nitrogen purge;
- a mechanical locking device for arm stowing;
- nitrogen purge and drain connections; and
- breasting and mooring dolphins.

The loading arms will be fully balanced in the empty condition by a counterweight system and maneuvered by hydraulic cylinder drives. Each loading and vapor return arm will have a powered emergency release coupling.

LNG will be pumped from the Plaquemines LNG Terminal's LNG storage tanks to ocean-going carriers for export. The design pumping rate from the tanks will be 12,000 m^3 per hour ("m^3/hr"). At the LNG loading berth, transfer to carriers will be achieved through the three loading arms. The vapor return arm is provided to route displaced/flash gas back to the storage tanks.

1.3.2.3 Pipe Trestle System

The Expansion Facilities' design includes a trestle crossing of State Highway ("SH") 23 by the cryogenic pipeline that will transport LNG from the LNG storage tanks to the LNG loading berth for marine export. In addition to the cryogenic piping and spill containment system, the trestle system will be used to carry utility connections to the LNG loading berth, crossing the Mississippi River levee as well as SH 23. The LNG loading berth will be connected directly with the liquefaction and storage facilities on the south side of SH 23 through a trestle system carrying LNG transfer piping, boil-off gas piping, fire water piping, and various auxiliary umbilicals. The pipe trestle will have a design similar to the pipe trestle associated with the Authorized Facilities and will cross over the storm surge wall in the northeast sector of the Project Site and run perpendicularly over SH 23 and the federal levee to the LNG loading berth. The pipe trestle will be around 35 feet tall and have more than 22 feet of clearance over both lanes of SH 23. Outside the Expansion Facilities' storm surge wall, the overall pipe trestle system length between the Expansion Facilities and LNG loading berth will be about 1,000 feet long.

The pipe trestle will consist of a horizontal steel lattice-work structure set on multiple vertical supports consisting of cross-braced steel pipe pilings. The pilings are 24-, 36-, 48-, or 54-inch-diameter, depending on location. The vertical clearance of the trestle above the federal levee will be 19 feet. The trestle width will be approximately 30 or 32 feet, depending on location. The pipelines and umbilicals will be set in tiers on the trestle, with the larger diameter structures, including the cryogenic LNG transfer piping, associated spill containment system, and vapor return piping, occupying the lower tiers.

1.3.2.4 Roadway

The LNG loading berth will have vehicular access by a roadway and a separate accessway to be constructed over the highway for pedestrian and non-highway vehicle access. The section of the roadway over and riverward of the federal levee will be supported on vertical steel pipe piling structures. The elevated roadway will be either 14 feet or 19 feet wide, depending on location, and will be flanked by guardrails. The roadway will originate on the north side of SH 23.

A separate accessway will be constructed to provide access for pedestrians and non-highway vehicles during operation of the Project. This accessway will originate within the storm surge wall and cross over the highway. The accessway will have more than 22 feet of clearance over both lanes of SH 23. This elevated accessway will not be utilized for construction traffic.

1.3.3 Facility Operational Design

The Applicants will build liquefaction infrastructure at the Expansion Facilities to provide an export capacity of 24.8 MTPA of LNG. Pipeline-quality natural gas from the existing market hubs and pipeline networks in northern Louisiana will be delivered to the Expansion Facilities through a non-jurisdictional intrastate natural gas pipeline, as described in section 1.8.

The Applicants estimate that the production volumes from the Expansion Facilities will be able to accommodate LNG vessels ranging from 120,000 m^3 to 210,000 m^3 of carrying capacity. The additional marine berth from the Expansion Facilities is required to accommodate the increased vessel traffic to support the total terminal capacity. The Applicants anticipate that the combined Project and Authorized Facilities will result in approximately 875 vessel arrivals annually, assuming an average vessel capacity of 120,000 m^3, four total LNG loading berths, and the additional proposed LNG production (i.e., 24.8 MTPA) for a combined production of 52 MTPA

of LNG for export. A fourth berth will ensure efficient turnaround times, operational flexibility, and reduced scheduling bottlenecks.

Upon arrival at the Expansion Facilities, the feed gas will enter the gas gate station where the gas will be split into two streams, one for process feed to the liquefaction plant and the other for the fuel gas supply[5] to the electric power generation system. The pipeline-quality gas delivered to the Expansion Facilities will be composed primarily of methane but also will contain ethane, propane, butane, and other heavy-end hydrocarbons (between 2 and 3 percent) in addition to small quantities of nitrogen, oxygen, CO_2, and water.

To ensure that the liquefaction plant can function properly, the pretreatment units will remove CO_2, water, and heavy hydrocarbons from process feed gas. The trace amounts of CO_2 present in natural gas would freeze in the cryogenic liquefaction process and block the cryogenic exchangers if not removed beforehand. Hydrogen sulfide (H_2S) is also removed to reduce the sulfur dioxide emissions. The pretreated gas will enter each block to be liquefied in the two SMR units in each liquefaction block, after which the LNG will be piped into storage.

LNG will be pumped from the Plaquemines LNG storage tanks to ocean-going carriers for export. To achieve the proposed maximum loading rate for LNG vessels (12,000 m^3/hr), the main cryogenic LNG line from the LNG storage tanks to the loading platform will be nominally sized at 42 inches in diameter. Based on this loading rate, LNG loading times for vessels will range from approximately 10 to 18.5 hours depending on vessel size and capacity. This estimate excludes vessel berthing, mooring, and unmooring/departure time. The LNG loading platform will support three 16-inch-diameter LNG loading arms, and one 16-inch-diameter vapor return arm. The loading arm will be equipped with the following:

- A hydraulic quick connect/disconnect coupler;
- A hydraulic double-ball, valve-powered emergency release coupler;
- Swivel joints with nitrogen purge;
- A mechanical locking device for arm stowing;
- Nitrogen purge and drain connections; and
- Breasting and mooring dolphins.

Arriving and departing LNG carriers will spend an average of nine hours in transit through state waters.

Electrical power will be generated at the Expansion Facilities by natural gas-fired combined cycle electric generation facilities, sized to reliably meet the Expansion Facilities' design requirements. The main power load at the Expansion Facilities will be consumed by compressor electric motor drivers in the liquefaction plant (one driver for each of the two liquefaction trains in each of the 16 liquefaction blocks). Other Project loads will include LNG pumps, boil-off gas and booster compressors, and the multiple fan motors that will be used for air cooling during the liquefaction process. The electric generation facilities will supply their own auxiliary electric loads, including fans in the air-cooled steam condenser, and will have multiple generators for black start

[5] Natural gas feed for power generation will be supplemented with boil-off gas and other fuel gas streams generated in the liquefaction plant.

capability. During construction, the Expansion Facilities will be powered by temporary power generators and a temporary utility line until the power plant is operational. The 230 kV interconnect substation may also be used during construction and commissioning.

The Expansion Facilities will use the local utility potable water line for the potable water needs for the Expansion Facilities.

Service water (fresh water) will be generated using an intake located along the Mississippi River, treated in the Project's freshwater treatment system and stored in a combined fresh water and fire water tank. Service water will be used for commissioning and operation of the Expansion Facilities. The fire water system will include four pumps (two electric-powered and two diesel-powered) each with a rated capacity of 5,000 gallons per minute. The Applicants will place water intakes above the channel bed to avoid or minimize sediment disturbance.

The sanitary waste system used for Expansion Facilities operations will include a sanitary wastewater treatment package plant which will discharge effluent to a LPDES permitted outfall. The system will also have a holding tank which will be pumped out as necessary and the waste disposed of at licensed facilities.

1.3.3.1 Pretreatment Process Description

After passing through the gas gate station at the Expansion Facilities site, the feed gas will be sent to the pretreatment facilities. The pretreatment plant contains a hydrogen sulfide ("H_2S") removal unit, an acid gas removal unit, and a hybrid dehydration and heavy hydrocarbon removal unit that will remove trace components of CO_2, H_2S, water, and heavy hydrocarbons. The trace amounts of CO_2, water, and heavy hydrocarbons present in natural gas will freeze in the cryogenic liquefaction process and block the cryogenic exchangers if it is not removed beforehand. Hydrogen sulfide is removed to meet LNG specifications and to lower sulfur dioxide emissions. After passing through the gas gate station, the feed gas will enter the H_2S removal unit and then the acid gas removal unit, which will be designed to treat feed gas containing levels of CO_2 up to 2 percent mole. The amines collected in the solvent drain tank during maintenance will be filtered and transferred to the solvent storage tank.

The feed gas pressure will be boosted as necessary by electric motor-driven compressors to achieve a minimum of 1,080 pounds per square inch gauge after pretreatment and before the feed gas enters the liquefaction system. Air-cooled heat exchangers will cool the feed gas to near-ambient temperature to remove the heat of compression. The feed gas leaving the booster compressors will be split into streams to feed each of the 16 liquefaction blocks.

1.3.3.2 Hydrogen Sulfide Removal Unit

The H_2S removal unit will be downstream of the acid gas removal unit. Acid gas from the acid gas removal units, containing up to 300 parts per million by volume ("ppmv") H_2S, will be fed to the non-regenerative H_2S removal beds to remove H_2S to lower sulfur dioxide emissions. Potential carryover of absorbent particles will be removed in the H_2S absorber after-filters.

1.3.3.3 Acid Gas Removal Unit

The acid gas removal unit is designed to treat feed gas containing up to 2 percent mole CO_2. Treated feed gas must contain no more than 50 ppmv CO_2 and no more than 1 ppmv H_2S. Activated methyl diethanolamine technology will be used, primarily due to its ability to remove CO_2 to very low levels, to reduce corrosion issues, and because of its lower foaming tendencies.

Five acid gas removal units will be installed. Antifoam injection will be provided, as well as amine and water storage and make-up facilities. The low-pressure CO_2-rich acid gas stream with some H_2S and residual hydrocarbons content will be sent to the H_2S removal units, as described in the previous section, and then to the thermal oxidizers for destruction.

1.3.3.4 Hybrid Dehydration and Heavy Hydrocarbon Removal Unit

The hybrid dehydration and heavy hydrocarbon removal unit will be downstream of the acid gas removal unit and is designed to remove water and heavy hydrocarbons from the feed gas leaving the amine tower after acid gases have been removed. Water and heavy hydrocarbons would freeze during natural gas liquefaction if not removed beforehand. The hybrid system will consist of five molecular sieve vessels; the process flow is routed through a valve system to two of the vessels while the other vessel's sieve material is regenerated with a small flow of dry hot gas.

At any given time, three molecular sieve beds will be in adsorption mode, while the other two will be in regeneration mode. The regeneration gas is heated by a hot oil system. The dried treated gas is filtered downstream of the molecular sieve vessel. The water content of the gas is reduced to about 0.5 ppmv.

1.3.3.5 Liquefaction Process Description

Each of the 32 liquefaction trains (two in each of the 16 liquefaction blocks) will use the SMR process to produce up to 1.55 MTPA of LNG per block (collectively, 24.8 MTPA). When the pretreated gas enters the liquefaction train, it will be de-superheated, condensed to liquid, then sub-cooled to near -260 degrees Fahrenheit in aluminum plate-fin heat exchangers, which will be enclosed and insulated with perlite powder in steel cold-boxes. Refrigeration for this process will be produced by a specially designed single loop mixed refrigerant system. The refrigerant, a mixture of nitrogen and hydrocarbon gases (e.g., methane, ethylene, propane, butane, and pentane), will be pressurized by a multi-stage electric motor-driven compressor and then partially condensed in air-cooled heat exchangers. The resultant cooled and pressurized vapors and liquids are separated into various streams and continue to be condensed and sub-cooled in the cold-box plate-fin heat exchangers. The cooling source for these mixed refrigerant streams and the natural gas liquefaction stream will be created by flashing cold mixed refrigerant to lower pressures then passing those colder mixed refrigerant streams in counter current to the streams to be cooled in the plate-fin heat exchangers. The lower pressure mixed refrigerant will be warmed to near ambient and returned to the suction of the compressors to complete the cycle.

Each liquefaction train will contain a refrigerant make-up system with gas analyzers and controls that maintain the refrigerant components in proper proportion. The refrigerant make-up system will be also designed to recover refrigerant during equipment shutdown. Distribution piping will connect vessels in the common refrigerant storage area to each liquefaction train. Except for certain safety systems, one distributed control system in the liquefaction plant control building, with multiple equipment redundancies, will be used for all process and power control.

When the LNG exits the cold-box, it will be depressurized in the LNG expanders and delivered at near ambient pressure to the LNG storage tanks. From the LNG storage tanks, the LNG will be pumped through cryogenic transfer piping onto ocean-going LNG carriers at the berthing dock.

1.4 LAND REQUIREMENTS

As discussed previously and as illustrated in figures 1.1-1 and 1.1-2, the Project Site consists of the land-based Expansion Facilities and the marine-based LNG loading berth. Land requirements are addressed in sections 1.4.1 and 1.4.2 for the Expansion Facilities.

1.4.1 Expansion Facilities

The Expansion Facilities will be constructed within an approximately 462-acre property and 62-acre marine facility workspace that has been contractually secured by an affiliate of the Applicants through agreements with the Louisiana Gateway Port. These contracts grant the right to lease the property for up to 70 years. Additionally, an adjacent 562-acre property which will be used for construction workspace was secured through the same agreements. The LNG loading berth will be constructed in the Mississippi River along the northern edge of the Expansion Facilities and includes a 20.3-acre operational footprint. Table 1.4-1 shows the Project land requirements.

TABLE 1.4-1

Plaquemines Expansion Project
Summary of Land Requirements at the Expansion Facilities

Facilities	Land Impacted by Construction (acres)	Land Impacted by Operation (acres)
Expansion Facilities		
Expansion Site	462.0	462.0
Marine Berth (Land-Based)	20.3	20.3
Marine Berth (Water-Based)	43.0	0.0
Adjacent Workspace		
Parking/Laydown (Permanent)	104.8	104.8
Parking/Laydown (Temporary)	449.4	0.0
Utility/Drainage	7.5	0.0
Existing Workspace [a]	77.6	0.0
Total [b]	**1,164.1**	**586.6**

[a] Existing workspace has been previously approved from the Authorized Facilities, and the Applicants will utilize this space during construction.

[b] Totals may not match the sum of addends due to rounding.

1.4.2 Contractor Yards

Contractor yards are needed for various uses, such as pipe fabricating, concrete coating operations, and fabricating piping assemblies, staging construction operations, storing construction materials, parking equipment, and maintaining temporary construction offices. The Applicants anticipate using the Venice Yard, a contractor yard that was approved for use for the Plaquemines LNG terminal (see Accession No. 20220603-3003), and the existing 2.2-acre overnight truck parking lot located about 2.7 miles west of the facility that was also used by the Plaquemines LNG terminal (see Accession No. 20230531-5413).

The Expansion Facilities will also likely utilize existing offsite parking areas in the Belle Chasse community as park and ride lots during construction to reduce congestion on roads and reduce the need for parking space within the Expansion Facilities. The number and location of

park and ride lots will be determined during construction and will fluctuate depending on the phase of construction.

1.4.3 Access Roads

Access roads are used to transport construction workers, equipment, and materials to the construction work area from public interstate, state, county, and local highways/roads. Early construction access to the Expansion Facilities will be via the existing Plaquemines LNG Terminal Site driveways. Four new connections to SH 23 and one new connection from an unimproved road along the eastern side of the Expansion Facilities will be constructed for ingress and egress to the Expansion Facilities.

1.5 CONSTRUCTION SCHEDULE AND PROCEDURES

1.5.1 Construction Schedule and Workforce

The Applicants anticipate that FERC authorization to site, construct, and operate the Project will be issued in the second half of 2026. Construction of the Project is anticipated to commence by early 2027, with first production of LNG targeted during of 2029.

During the construction peak, an estimated 9,000 on-site direct workers will be required; however, the number of workers present at different stages of construction will vary significantly. As Expansion Facilities construction activities increase, the workforce will average approximately 4,000 workers over 47 months. The Applicants estimate approximately 30 percent of the workforce will consist of residents therefore, approximately 70 percent of the workforce would need to temporarily or permanently relocate to the area. About 250 permanent workers will be employed at the Expansion Facilities of which the Applicants expect that about 25 percent would likely relocate to the area.

Construction will occur on a 24-hours-per-day, 7-days-per-week (24/7) basis. Hammer or vibratory pile driving will be limited to the hours of 7 AM to 7 PM and will not occur on Sundays. Landowners, local officials, and emergency responders will be notified about the construction schedule as discussed in section 1.10. A Project schedule for the full completion and commissioning is included in appendix 13.A.5 of Resource Report 13.

1.5.2 Construction Procedures

The Applicants will adhere to numerous construction and operation plans, including but not limited to:

- FERC *Upland Erosion Control, Revegetation, and Maintenance Plan* (“Plan”) (appendix 1C);
- FERC *Wetland and Waterbody Construction and Mitigation Procedures* (“Procedures”) (appendix 1D);
- Spill Prevention, Control, and Countermeasure Plan (to be filed prior to construction);
- Stormwater Pollution Prevention Plan (“SWPPP”) (to be filed prior to construction):

- Plan for Unanticipated Discovery of Cultural Resources or Human Remains During Construction (appendix 4E);
- Traffic Study and Management Plan (to be filed when available with subsequent version of Resource Report 8);
- Nighttime Construction Noise Mitigation Plan (to be filed prior to construction);
- Expansion Facilities Lighting Plan (appendix 8B);
- Fugitive Dust Plan (appendix 9F); and
- Emergency Response Plan (appendix 11B).

All facilities will be designed, installed, tested, operated, and maintained in accordance with applicable laws, regulations, and standards intended to prevent facility accidents and failures, ensure public safety, and protect the environment. These standards and regulations include the DOT's *Federal Safety Standards for Liquefied Natural Gas Facilities* (49 CFR 193; DOT, 2006), the National Fire Protection Association ("NFPA") *Standard for the Production, Storage, and Handling of LNG* (Standard 59A), the National Electrical Code (NFPA 70) (NFPA, 2017, 2019), and applicable sections of the USCG's regulations for Waterfront Facilities Handling Liquefied Natural Gas and Hazardous Gas (33 CFR 127 and Executive Order 10173; USCG, 1988).

The Project will comply with FERC's Plan and Procedures as applicable to LNG terminal construction (see appendices 1C and 1D). Implementation of the Plan and Procedures during construction and post-construction monitoring will help ensure that ground disturbance and restoration activities are implemented in an environmentally appropriate manner.

Public roads utilized in the Project vicinity during construction will be monitored daily and maintained as necessary to ensure that any deterioration in condition noted at the end of construction reflects typical traffic usage and is not directly attributable to higher-than-average traffic volumes associated with the Project. Existing roads that are damaged or modified as a direct result of construction will be repaired or restored to previous condition. Public roads will be monitored during construction to assess damage and repairs and help detect and prevent unwanted dirt and debris migrating off-site from the Project's workspaces.

During construction, some potential exists for spills of hazardous materials, such as hydraulic fluid and diesel fuel for equipment and vehicles. In addition, stormwater runoff from the construction workspace could carry unconfined debris or materials. To address these concerns, the Applicants will develop and adhere to a Spill Prevention and Response Procedures Plan and a SWPPP, in line with applicable regulations and permit requirements.

The Applicants will review Project-specific environmental conditions with prospective contractors during pre-bid meetings and incorporate such conditions into construction bid documents. The Applicants will require that all contractors develop and train their construction workers in spill prevention and clean-up, waste management, and incident management and reporting to support environmental compliance during construction. Contractors will be contractually obligated to comply with all environmental conditions. As soon as any non-compliance during construction is discovered, the contractor will be directed to comply. Additional corrective actions may be taken as necessary, including the issuance of stop-work orders.

For purposes of quality assurance and to support regulatory compliance, the Project will be represented by one chief inspector at the Expansion Facilities, and one for the gas gate station inside the Plaquemines LNG terminal. Craft inspectors and environmental inspectors ("EIs") will assist each chief inspector. In addition, craft inspectors will be used for inspection services at manufacturing and fabrication facilities handling process modules, equipment, and piping prior to delivery to the Project. All inspectors will have access to the compliance specifications and other relevant material contained in the construction contracts.

The primary role of the EIs is to ensure that the environmental conditions associated with permits and other authorizations are satisfied. The EIs will have authority to stop work or require other corrective actions to achieve environmental compliance. In addition to monitoring compliance, the EIs will assist with environmental training for Project personnel and report compliance status on a daily, weekly, and biweekly basis. The environmental training program will be designed to ensure that all individuals receive training tailored to their role before beginning on-site work, adequate training records are maintained, and refresher training is provided as needed.

1.5.3 Expansion Facilities

1.5.3.1 Site Preparation and Temporary Construction Facilities

The Expansion Facilities site will require area-wide improvements, including clearing, grubbing, grading, soil stabilization, and filling to increase ground elevation, some of which must be performed ahead of foundation development and plant construction. The full scope of these activities will be partly dependent on the results of geotechnical studies for the Expansion Facilities, which will be used to evaluate geotechnical soil properties (e.g., bearing capacity, deformability, liquefaction potential, moisture content, compaction, and slope stability). The geotechnical studies for the Expansion Facilities will be provided when available.

Construction of the Expansion Facilities will utilize the existing MOF associated with the Authorized Facilities to deliver permanent plant components, steel and concrete piles, and certain bulk materials during construction. The Applicants intend to utilize the MOF to the extent possible to minimize deliveries to the construction site by truck. The Applicants estimate that the MOF will accommodate about 630 vessel deliveries or about one delivery from barge or other vessel type every other day for the first 42 months of construction.

The Expansion Facilities' site ground elevations will be raised through grading and potential importing of fill materials. The source of additional fill material has not been confirmed. The Applicants are considering using commercially available aggregate materials, including gravel, oyster shell, and crushed stone. The Applicants will construct a storm surge wall to protect the facilities from storm surge during construction and operation.

The existing soil at the Expansion Facilities site may require improvement and stabilization to provide a load-bearing surface during construction. Commonly used stabilizers include Portland cement and hydrated lime. Soil consolidation may also be achieved using other methods, such as the installation of wick drains and stone columns. Soil improvement requirements will be established after analysis of the geotechnical report and the seismic investigations are completed. Aggregate materials (e.g., gravel, oyster shells, and/or crushed stone) and geotextile layers will be used to level and finish temporary workspace and operational areas, as necessary. Aggregate materials will be delivered to the Expansion Facilities by truck or by barge to the existing MOF.

At the outset of construction, the Applicants will install temporary facility areas within the laydown area to support construction. These additional areas will be required for developing "preliminary works," which include initial site preparation and construction of new site access roads. The temporary facility areas may house sanitary facilities, a parking area, and a laydown area for material storage. As site preparation proceeds, this temporary facility area will be expanded, and additional temporary facilities will be added as necessary to support construction. These areas will include offices, a canteen, a warehouse, sanitary facilities, concrete batch plants, and parking areas. Construction workspace preparation across the Expansion Facilities will involve cutting and filling to rough grade and soil stabilization and improvement as referenced above, followed by temporary fencing installation to isolate construction activities from peripheral areas. Construction access roads will be installed at this time. In addition to the plant roads, electrical, communications, and water systems needed during construction will be installed at this time.

As part of site preparation, the Applicants will install a temporary water intake(s) within the Mississippi River to supply water for construction and commissioning needs such as dust suppression, hydrostatic testing, concrete production and water needs for commissioning. The temporary water intake will be located within the footprint of the proposed marine facility. The temporary water intake design will likely consist of a 30-inch-diameter high density polyethylene ("HDPE") waterline at grade within the river and batture. The water line will contain two electric pumps with a power supply located landward of the levee. The intake will have slots only on the top of the HDPE pipe to screen the intake and prevent uptake of sediment. The pumps will be screened and elevated in accordance with permit requirements. Pumping capacity will likely range between 500 and 1,000 gallons per minute.

The Expansion Facilities' site preparation activities will be designed to ensure efficient and environmentally protective stormwater drainage. The Expansion Facilities site will be designed to direct discharges through a system of ditches and trenches into the Plaquemines LNG Terminal Site and, if necessary, holding basins and filtration devices during construction, allowing sufficient retention time to preclude high sediment loads from reaching receiving waters. Stormwater controls (including placement of gravel or other suitable material to provide a stable, well-drained surface) will be installed. Throughout construction, the Applicants will follow the erosion and sedimentation control procedures described in the SWPPP and the Plan and Procedures.

1.5.3.2 Liquefaction Plant Facilities

At the current stage of project design, detailed site-specific construction procedures for the Expansion Facilities remain under development. However, the general construction procedures described below for the liquefaction plant are generally applicable to the other major site facilities requiring pile foundations and involving the transportation of large equipment units by truck and/or barge. For ancillary site facilities, such as utility storage areas, and warehouses, construction would also commence with foundation preparation, which may require the installation of piles.

The liquefaction plant will consist of 16 liquefaction blocks occupying a rectangular footprint in the north central sector of the Expansion Facilities. Following site grading, soil stabilization, and plant road installation (see description of Site Preparation and Temporary Construction Facilities above), foundation construction will commence with installation of piles to provide a firm base for the structures supporting the liquefaction blocks. Pile specifications will be based on guidance in FERC's most recent draft seismic guidelines (FERC, 2007) and Section 7.2.2 of NFPA Standard 59A (NFPA, 2019). After the piles have been positioned using pre-drilled

holes and/or pile-driving, caps will be installed and the concrete pad poured. Helical piles may also be used for some applications. After the piles have been positioned using predrilled holes and/or pile-driving, caps will be installed and the concrete pad poured.

The liquefaction blocks will be interconnected with the gas gate station at the Project and the LNG storage tanks at the Authorized Facilities by buried and aboveground piping interconnects, the latter on steel-framed support racks. Pipe spool fabrication will be undertaken mainly off site. Spools fabricated off site will be delivered by truck and barge. Where possible, pipe racks will be modularized to minimize site work. Pipe sections will be painted, coated, or insulated, as necessary, after welds have been tested according to applicable codes.

Certain larger equipment units, such as pretreatment systems, liquefaction cold-boxes and refrigerant compressors, will be assembled as modules in several offsite prefabrication yards. This offsite modular approach allows equipment assembly in a more controlled environment than that encountered under the onsite “stick-built” approach. Equipment units necessary for the Expansion Facilities will be constructed at existing commercial facilities within existing previously permitted or disturbed areas. Following the assembly, these large modular units will be transported to the MOF located on the Mississippi River, off-loaded, and transported to their respective foundations. Other equipment will be shipped to the Expansion Facilities site by truck. Equipment will undergo quality assurance/quality control inspection and testing at its place of origin and upon installation at the Expansion Facilities.

Once foundations have been set, work on the liquefaction blocks, piping interconnects, and associated utility systems can occur within the same general timeframe but will be coordinated such that various inter-dependent systems (e.g., electrical and instrumentation) can be installed and tested according to an appropriately sequenced schedule. After the equipment and piping has been set in place, cable systems will be installed. Ultimately, road paving, final site grading, seeding, and cleanup will be completed. Temporary construction facilities will be disassembled and removed on a progressive basis when they are no longer needed.

Pipe sections will be either hydrostatically or pneumatically tested (additional details will be provided in Resource Report 2) depending on the type and intended function of the pipe. Water for hydrostatic testing of plant piping will be obtained from a local municipal supply or the Mississippi River. Pipeline test segments will be capped and filled with water. The pipe test section will then be pressurized and hydrostatically tested. Any loss of pressure that cannot be attributed to specific factors such as temperature changes will be investigated. Any leaks detected will be repaired and the test section retested.

Hydrostatic test water will be obtained in compliance with Louisiana regulations. The Applicants will screen hydrostatic test water intake to minimize adverse impacts on aquatic organisms. Water used for hydrostatic testing will be reused in subsequent tests to the extent practical. Test water will be discharged through energy dissipating devices (e.g., straw bale filter structure) in accordance with the requirements of a LPDES hydrostatic discharge permit using methods described in the Procedures. Test water will contact only new pipe, and no chemicals will be added. Once a pipe segment has been successfully tested, the test cap and manifold will be removed, and the pipe will be tied into the remainder of the pipeline for drying operations. The Applicants do not anticipate that any chemical agents will be added to the test water. Additional details will be provided in Resource Report 2 regarding source, uptake and discharge rates, discharge location and estimated volume of water needed for the hydrostatic testing of facility components.

When the construction of the Expansion Facilities is nearly 70-percent complete, the focus will shift from construction by area to completion of specific systems. At this point, civil and structural work will be substantially complete, and equipment and piping set in place. The main schedule drivers will be mechanical completion and pre-commissioning requirements. A turnover coordinator will prepare system completion and turnover packages, which will include the following items:

- marked-up drawings to show the limit of each system and blind flanges locations;
- line list by system with pressure testing documentation;
- equipment list including motors with data sheets and inspection reports;
- marked-up single line diagrams with inspection/test reports for electrical equipment;
- cable reports;
- instrument index with data sheets and calibration sheets;
- loop diagrams;
- vendor documentation/drawings;
- turnover exceptions lists;
- detailed punch-list of items requiring correction; and
- operation and maintenance manuals.

Dredging Requirements

The Applicants do not anticipate that dredging or excavation will be required for the LNG carriers to access the LNG loading berth. The location of the LNG carrier berthing area in the Mississippi River will be reviewed under the U.S. Army Corps of Engineers ("USACE") Section 404 and 408 programs, the LDEQ Section 401 program, and the Louisiana Department of Energy and Natural Resources ("LDENR") Office of Coastal Management.

Interconnecting Trestle Construction/Fabrication

The Applicants will construct an approximately 1,000-foot-long aboveground trestle that will support one new 42-inch diameter cryogenic LNG transfer lines and connect the Expansion Facilities with the proposed LNG loading berth. More detailed information about trestle construction/fabrication will be provided in the Application.

Drainage of the Finished Site

The Expansion Facilities site will be graded such that stormwater flow from process areas will enter a peripheral system of shallowly sloped swales that will collect and carry the runoff to perimeter outfall locations within the Plaquemines LNG Terminal. Before arriving at the outfalls, the stormwater will pass through surficial containment sump devices designed to remove oil and

sediments from the stormwater. Areas that do not have the potential for contamination will be carried directly to outfalls. Portions of the site where the topography remains unchanged will retain their natural drainage. A detailed stormwater conveyance plan will be provided prior to construction.

The design and operation of all stormwater discharge and treatment facilities will be in accordance with applicable regulations and permits, including LPDES regulations under the Clean Water Act ("CWA").

1.5.4 Site Access and Traffic

The Applicants will prepare a Traffic Study and Management Plan to address worker and materials/equipment transportation for the Project construction areas. The plan will comply with state and local regulatory requirements and will contain specific routing information and delivery timelines. The Expansion Facilities site can be accessed by road from Belle Chase, Louisiana, heading southeast about 20 miles via SH 23 along the Mississippi River (see figures 1.3-1 and 1.3-2 in appendix 1A [filed under separate cover as CUI/CEII]). The Applicants anticipate that, during construction, major material supplies and equipment will be delivered by barge via the MOF on the Mississippi River at the Plaquemines LNG Terminal, or via truck by SH 23.

The Applicants anticipate 332 vessels (ships and barges combined) over the first 42 months of construction to be unloaded at the MOF for permanent plant equipment that cannot be delivered by road. Additional information regarding frequency and impacts associated with truck trips, as well as worker transportation and commuting measures will be provided in the Traffic Management Plan. The overall intent of the plan will be to minimize construction-related disruption to local traffic and local use of the waterways, and to ensure that such local use proceeds in a safe and efficient manner.

1.6 OPERATION AND MAINTENANCE

1.6.1 Operation

All facilities will be operated and maintained in accordance with applicable government safety standards and regulations intended to ensure adequate protection of the public and to prevent facility accidents and failures. These standards and regulations include, as applicable, the DOT Federal Safety Standards for Liquefied Natural Gas Facilities (49 CFR Part 193), NFPA Standard 59A, and applicable sections of the USCG's regulations for Waterfront Facilities Handling Liquefied Natural Gas and Hazardous Gas (33 CFR Part 127 and Executive Order 10173).

Operating procedures will be prepared for the Project after the final design is completed. The procedures will address safe startup, shutdown, cool down, purging, as well as routine operation and monitoring. Comprehensive training will be provided to ensure that all facility personnel are familiar with, and adhere to, properly documented and recognized safety procedures. The potential hazards of cryogenic LNG operations and proper equipment operation will be two areas of focus. Operators will meet the applicable training requirements of the DOT, USCG, and other regulatory entities.

The Applicants will update the existing Emergency Response Plan for the Authorized Facilities to include the Project facilities and will address safety procedures during weather events, including storm surges and hurricanes for the Expansion Facilities (this updated plan will be

provided during detailed design). Efforts will be made to coordinate with and involve appropriate local officials to ensure effective integration with local communication and emergency response systems.

1.6.2 Maintenance

Maintenance of the Expansion Facilities will be conducted in accordance with the provisions of 49 CFR 193, Subpart G and applicable laws and regulations, and through procedures and programs developed by the Applicants. Full-time staff will conduct routine maintenance and minor repairs, whereas major overhauls and non-routine maintenance will be handled by specialty contractors. Both scheduled and unscheduled maintenance will be entered into a computerized maintenance management system and disseminated to the appropriate personnel for follow-up. All operations and maintenance personnel will be trained in the use of the computerized maintenance management system. Scheduled preventive and predictive routine maintenance will include equipment rotation and inspection of safety equipment, environmental equipment, and instrumentation. All maintenance activities will be performed by trained maintenance technicians reporting to a maintenance supervisor.

1.7 FUTURE EXPANSION AND ABANDONMENT PLANS

Beyond the Project, the Applicants have not identified any future expansions, or abandonment plans for the Expansion Facilities, which is projected to have a minimum design life of 30 years.

1.8 NON-JURISDICTIONAL FACILITIES

Under certain circumstances, non-jurisdictional facilities may be subject to the Commission's review. In determining whether to assert jurisdiction, the Commission considers the following four factors:

- whether or not the regulated activity comprises "merely a link" in a corridor-type project (e.g., a transportation or utility transmission project);
- whether there are aspects of the non-jurisdictional facility in the immediate vicinity of the regulated activity that uniquely determine the location and configuration of the related activity;
- the extent to which the entire project will be within the Commission's jurisdiction; and
- the extent of cumulative federal control and responsibility.

The Applicants have identified all the proposed facilities at the Project site as jurisdictional and subject to FERC authorization. Non-jurisdictional facilities, which will be authorized and regulated by Louisiana state agencies, will include construction of an intrastate natural gas pipeline to provide natural gas supply to the Project and new utility service connections to a local electric power system, water supply, and fiber optic telecommunications.

1.8.1 Intrastate Natural Gas Pipeline

The Project will receive natural gas via a non-jurisdictional intrastate natural gas pipeline, the Cloud Connector Pipeline. The natural gas is required to supply the Plaquemines Expansion

with gas for power generation facilities and liquefaction. The intrastate pipeline will be in-service on a phased schedule, with final in-service date projected for February 2029. Additional information about the interconnect facility for this pipeline to the Expansion Facilities is provided in section 1.3.1.1 and additional information regarding capacity and pressure is provided in Resource Report 13, section 13.1.1.5.

A summary of the required permits for the Cloud Connector Pipeline is provided in table 1.8-1, which reflects information available to the Applicants.

TABLE 1.8-1

Plaquemines Expansion Project
Summary of Required Permits for Proposed Non-Jurisdictional Pipeline

Agency	Permit/Approval
FEDERAL AGENCY	
COE – Vicksburg and New Orleans Districts	Clean Water Act (CWA) Section 404 Permit for impacts on Waters of the United States, including wetlands (33 USC § 1344)
	Rivers and Harbors Act (RHA) Section 10 Permit for construction and operation of structures in and across federally navigable waters (33 USC § 403)
	33 USC § 408 (5 Federal Levee Crossings)
National Marine Fisheries Service – Southeast Region (NMFS)	Endangered Species Act (ESA) Section 7 Consultation (16 USC § 1856 et seq.)
	Essential Fish Habitat Consultation (50 CFR Part 600)
	Fish and Wildlife Coordination Act Consultation (16 USC § 661 et seq.)
U.S. Fish and Wildlife Service (FWS)	ESA Section 7 Consultation (16 USC § 1536)
	Migratory Bird Treaty Act (16 USC § 703 et seq.)
	Fish and Wildlife Coordination Act Consultation (16 USC § 661 et seq.)
STATE AGENCY	
Louisiana Department of Environmental Quality (LDEQ) – Air Permits Division	Title V and Prevention of Significant Deterioration (PSD) Air Permits (40 CFR Part 70)
Louisiana Department of Environmental Quali😊ty (LDEQ) – Water Permits Division	Section 401 Water Quality Certification (33 USC § 1341)
	Louisiana Pollutant Discharge Elimination System - Hydrostatic Test Water Discharge General Permit (LA R.S. 30:2001 et seq.)
	Louisiana Pollutant Discharge Elimination System - Construction Stormwater Discharge Permit (LA R.S. 30:2001 et seq.)
	Louisiana Pollutant Discharge Elimination System – Industrial Wastewater Discharge Permit (LA R.S. 30:2001 et seq.)
Louisiana Department of Energy and Natural Resources (LDENR), Pipeline Division	Notice of Construction
Louisiana Department of Energy and Natural Resources (LDENR) – Office of Coastal Management (OCM)	Coastal Use Permit (CUP), a Joint Permit Application with the COE (R.S. 49:214.25)
	Water Use Agreement
Louisiana Department of Wildlife and Fisheries (LDWF)	State-Listed Species Clearance
	Letter of Authorization – Grassy Lake Wildlife Management Area (WMA) and Richard K Yancey WMA
Louisiana Office of State Lands	Pipeline Right-of-Way Grant

TABLE 1.8-1

Plaquemines Expansion Project
Summary of Required Permits for Proposed Non-Jurisdictional Pipeline

Agency	Permit/Approval
Louisiana Department of Culture, Recreation and Tourism, Division of Archaeology	Consultation under Section 106 of the National Historic Preservation Act (NHPA) (36 CFR Part 800)
LOCAL LEVEE DISTRICTS	
Levee Districts (North Lafourche Levee District, Terrebonne Levee and Conservation District, Plaquemines Levee District)	Individual Authorizations from each Levee District; 10 levee systems crossed
TRIBAL OUTREACH	
15-20 Federally Recognized Tribes	Consultation under Section 106 of the NHPA (36 CFR Part 800)

1.8.2 Utility Service Connections

In addition to onsite utility systems currently existing for the Plaquemines LNG Terminal, the Project will require new utility service connections to support operation. The connections will include tie-ins to the electric power grid from Entergy, potable water service from a local utility provider, and fiber optic telecommunications. The utility interconnections will be developed in coordination with the appropriate service providers and will be designed to meet the operational demands of the Project, and constructed and operated in compliance with applicable regulations. All utility service connections are expected to be located immediately adjacent to the Expansion Facilities along SH 23 within the utility/drainage workspace illustrated in figures 1.1-1 and 1.1-2.

1.9 PERMITS AND APPROVALS

The Applicants will ensure that all necessary permits, clearances, and licenses for Project construction and operation are obtained by the time they are required. Table 1.9-1 in appendix 1B provides a list of required authorizations and identifies the applicable federal, state, or local agency or other authority in each case. Initial consultation with permitting agencies commenced in May 2025. Copies of the initial correspondence with agencies are appended to the appropriate resource reports.

1.10 AGENCY, PUBLIC, AND OTHER STAKEHOLDER COMMUNICATIONS

In the NGA, Congress instructed FERC to issue approvals of proposed LNG export terminals unless FERC finds the proposed project will not be consistent with the public interest. On March 6, 2025, the Applicants requested that FERC initiate the pre-filing process for National Environmental Policy Act review of the Project. This request was approved on April 4, 2025, and the Project was assigned pre-filing docket number PF25-7-000.

One of the objectives of the pre-filing process is to identify interested stakeholders and provide opportunities for involvement early in the Project planning process to identify and resolve issues, where possible, prior to the filing of a formal application. The Applicants began discussions with potential stakeholders in May 2025 and will continue these efforts throughout the life of the Project. The Applicants believe that public engagement provides a valuable opportunity for stakeholder input. Thus, the Applicants are committed to communicating with landowners and other stakeholders and will continue to refine the Project, where feasible, in

response to input received from landowners, the public, agencies (including FERC environmental staff), and other stakeholders.

The Applicants will continue to meet with various groups and individuals regarding the Project, as outlined in the Public Participation Plan included as an attachment to in the Project pre-filing request letter dated March 6, 2025. The Applicants will work in good faith with stakeholders to identify and address issues early and proactively. The public consultation team, with the support of the constituent departments of our Project team (e.g., engineering, construction, legal, external affairs, and environmental compliance) will collaborate to implement the Public Participation Plan, which includes the following key program elements:

- Identify and meet with local associations, affected public groups and other non-governmental organizations about the Project and any potential impacts on the community or stakeholder's interests on an ongoing basis.

- Designate a single point of contact for the public to direct comments and questions.

  - Mr. AJ Walker is the point of contact.

- Establish a website presence, a Project e-mail address, a toll-free Project phone number, and a Project mailing address:

  Website: http://www.ventureglobal.com/
  Toll-free number: 1 (800) 514-0833
  Email address: landowner@ventureglobalIng.com

  Mailing address:
  1401 McKinney Street, Suite 2600
  Houston, Texas 77010

- Conduct consultation meetings with community leaders and elected officials on a regular basis.

- Host open house meetings for communities, elected officials, landowners and other stakeholders.

- Produce and distribute informational materials regarding the Project, including letters to affected landowners notifying them of the start of construction.

- Support on-going public outreach throughout the life of the Project.

- Document and respond to questions and issues raised through this iterative engagement process.

As part of the public participation process, the Applicants held three open houses on May 19, 20, and 21, 2025. Table 1.10-1 identifies the public open houses dates and locations that the Applicants held. In total, about 100 people attended the three open houses. Landowners and other stakeholders were notified of the open houses in May 2025 informational letters. The Applicants also notified the public of the open houses by posting a social media flyer on several local Facebook Groups. The social media flyer was shared by Louisiana Gateway Port, Plaquemines Parish Council Member from District 8 Mitch Jurisich and Plaquemines Parish

Council Member from District 3 Chris Schultz. Additionally, Oil & Gas Water and the FERC Office of Public Participation also posted their own notifications about the open house meetings, not using the social media flyer created by the Applicants.

TABLE 1.10-1

Plaquemines Expansion Project
Summary of Plaquemines Expansion Open Houses

Date	City	Location	Number of Attendees
May 19, 2025	Belle Chasse	Belle Chasse Auditorium 8398 Highway 23 Belle Chasse, LA 70037	50
May 20, 2025	Port Sulphur	Port Sulphur YMCA 278 Civic Drive Port Sulphur, LA 70083	28
May 21, 2025	Braithwaite	Rev. Percy M. Griffin Community Center 15577 Highway 15 Braithwaite, LA 70040	25

Landowners the open houses were primarily interested in increased traffic caused by the Project, improvements to road conditions, and in Port Sulphur specifically, the evacuation procedure. Other topics raised by attendees included air pollutant byproducts, noise from ship traffic, safety concerns, infrastructure improvements to the local community, impacts on the Parish water system, fugitive dust, wetland mitigation credits and restoration, stormwater discharges, and permanent jobs.

On July 14, 2025, the Applicants filed with FERC a letter for the Project (see Accession No. 20250714-5201). The letter notified FERC that the Applicants increased the number of liquefaction blocks to be permitted from 12 to 16, and because of this modification, the proposed production capacity of the Project increased from 18.6 MTPA to about 24.8 MTPA. Additionally, based on traffic congestion during construction feedback received during the open houses described above, the Applicants identified the need for additional workspace to alleviate and address traffic concerns. The Applicants determined that a larger laydown area that is contiguous to the Project site would reduce the number of vehicle and truck trips necessary during construction. Therefore, the proposed Project footprint was increased to include an additional 562 acres east of the previously submitted Project footprint.

On July 18, 2025, the Applicants notified additional landowners within 0.5 mile of the increased footprint of the Project and notified the previously notified landowners and stakeholders of the modification. Examples of these mailings are provided in appendix 1E.

The Applicants, FERC staff, and interested agencies have engaged in biweekly pre-filing Project calls to discuss the application and permitting processes, the minutes of which have been posted to the FERC docket. FERC staff held public scoping sessions on August 12 and 13, 2025, at the Belle Chasse Auditorium in Belle Chasse, LA, and at the Port Sulphur YMCA in Port Sulphur, LA. Notice of the scoping meetings was published on July 29, 2025 (see Accession No. 20250729-3029).

Comments received during the public scoping sessions included concerns over traffic congestion during construction, support for the Project due to job creation and greater tax revenue and benefits for community businesses. Additionally, at the August 13, 2025, meeting in Port Sulphur, Plaquemines Parish President Keith Hinkley acknowledged that water issues

experienced within the parish during the recent construction of the Authorized Facilities were attributed to the parish infrastructure itself and were not caused by construction of the Authorized Facilities.

In accordance with 18 CFR § 157.6(d)(2), the Applicants will send formal written notification to all landowners within 0.5 mile of the proposed Project location within three business days following the date the Commission issues a Notice of Application. Additionally, the Notice of the Application will be published in newspapers of record in the local area and copies of the public version of the Project's Application will be placed in one or more local public libraries to facilitate review by members of the community who do not have access to the other methods provided above.

An example of Project correspondence to landowners and stakeholders to-date is provided in appendix 1E. A copy of the Project landowner mailing list is included in appendix 1F and a copy of the Project stakeholder mailing list is included in appendix 1G (filed under separate cover as CUI/CEII).

1.11 CUMULATIVE IMPACTS AND INDIRECT EFFECTS

Pursuant to former 40 CFR § 1508.7, a "cumulative impact is the impact on the environment which results from the incremental impact of the action when added to other past, present, and reasonably foreseeable future actions regardless of what agency (federal or non-federal) or person undertakes such other actions. Cumulative impacts can result from individually minor but collectively significant actions taking place over a period of time."

To adequately address and accomplish the purpose of this analysis, an action must first meet the following criteria:

- The action causes impacts on a resource that would be affected by the proposed Project.
- The action causes impacts within all or part of the geographic scope of the proposed Project.
- The action causes impacts within all or part of the temporal scope of the proposed Project.

Table 1.11-1 outlines the resource-specific geographic regions considered for cumulative impact assessment.

TABLE 1.11-1

Plaquemines Expansion Project
Resource-Specific Geographic Regions for the Cumulative Impact Assessment

Environmental Resource	Geographic Scope for Cumulative Impacts	Justification for Geographic Scope
Groundwater, surface water, canals, and wetlands	Hydrologic Unit Code (HUC)-12 sub-watershed • HUC-030104040809 - Planters Canal • HUC-080901000101 - Mississippi River-Bonnet Carre Spillway	Impacts on groundwater and surface water resources could reasonably extend throughout a HUC-12 sub-watershed (i.e., a detailed hydrologic unit that can accept surface water directly from upstream drainage areas, and indirectly from associated surface areas such as remnant, noncontributing, and diversions to form a drainage area with single or multiple outlet points), as could the related impacts on aquatic resources and fisheries. See Resource Report 2.

TABLE 1.11-1

Plaquemines Expansion Project
Resource-Specific Geographic Regions for the Cumulative Impact Assessment

Environmental Resource	Geographic Scope for Cumulative Impacts	Justification for Geographic Scope
Vegetation and wildlife	HUC-12 sub-watershed • HUC-030104040809 - Planters Canal • HUC-080901000101 - Mississippi River-Bonnet Carre Spillway	Consideration of impacts within a HUC-12 sub-watershed sufficiently accounts for impacts on vegetation and wildlife that would be directly affected by construction activities and for indirect impacts such as changes in habitat availability and displacement of transient species. See Resource Report 3.
Cultural resources	Overlapping impacts within the Area of Potential Effects	The Area of Potential Effects for direct effects (physical) includes areas subject to ground disturbance, while the Area of Potential Effects for indirect effects (visual or audible) includes aboveground ancillary facilities or other Project elements visible from historic properties in which the setting contributes to their National Register of Historic Places eligibility. See Resource Report 4.
Socioeconomics	Affected parishes	Affected parishes would experience the greatest impacts associated with employment, housing, public services, transportation, traffic, property values, and economy and taxes. See Resource Report 5.
Marine transportation	Mississippi River	Affected navigable waterways would experience the greatest impact downstream from the LNG facility. See Resource Report 5.
Soils and surficial geology	Construction workspaces	Impacts on soils and surficial geology would be highly localized and would not be expected to extend beyond the area of direct disturbance associated with the Project. See Resource Reports 6 and 7.
Land use	0.25 mile	Impacts on general land uses would be restricted to the construction workspaces and the immediate surrounding vicinity; therefore, the geographic scope for land use and recreation is 0.25-mile from the proposed Project. See Resource Report 8.
Visual	The distance that the tallest feature at the planned facility would be visible from neighboring communities	Assessing the impact based on the viewshed allows for the impact to be considered with any other feature that could have an effect on visual resources. See Resource Report 8.
Noise – operation	1.0 mile	Noise from the proposed Project's permanent facilities is not anticipated to have an impact beyond 1.0 mile. See Resource Report 9.
Noise – construction	0.25 mile	Areas in the immediate proximity of aboveground facility construction activities (within 0.25 mile) would have the potential to be affected by construction noise. See Resource Report 9.
Air quality – operation	31.1 miles (50.0 kilometers)	Impacts on air quality beyond 50 kilometers (31.1 miles) would be *de minimis*. See Resource Report 9.
Air quality – construction	0.25 mile	Air emissions during construction would be limited to vehicle and construction equipment emissions and dust and localized to the proposed Project's construction area. See Resource Report 9.

Construction is anticipated to commence by early 2027, with first production of LNG targeted during of 2029. Table 1.11-2 in appendix 1B lists the projects that, in conjunction with the Plaquemines Expansion Project, could cause or contribute to potential cumulative impacts on environmental resources in the study area. The locations of these projects are depicted in figure 1.11-1 in appendix 1A. A brief description of each of the projects and an analysis of potential cumulative impacts by resource are provided below.

1.11.1 Projects and Other Reasonably Foreseeable Future Actions Considered in the Cumulative Impacts Analysis

1.11.1.1 Industrial Developments

The NOLA Terminal is a multi-use terminal with storage and export docks at mile marker 59 on the west bank of the Mississippi River. It will be the first terminal in the region capable of accommodating New-Panamax class vessels. The project is situated approximately one mile north of the Expansion Facilities. Phase one involved construction of the wharves and docks which was completed in 2022. Phase two construction for the land-side storage facilities and transport has not yet started (NOLA Terminal, 2025).

The Plaquemines LNG Terminal is an LNG export facility currently under phased construction by Plaquemines LNG; it is located adjacent to the Expansion Facilities and was approved by FERC in 2019 under FERC Docket No. CP17-66-000. Construction activities began in 2021 and continue to be underway. The facility includes liquefaction trains, natural gas pre-treatment trains, three ship loading berths, two combined cycle gas turbine power plants, a material offloading facility on the Mississippi River, and two pipelines that connect to existing interstate natural gas pipelines (Venture Global, 2025).

Louisiana Gateway Container Terminal, located on the west bank of the Mississippi River at mile marker 51, is a planned port facility designed to accommodate growing containerized cargo demand. The terminal will include three ship berths equipped with six ship-to-shore cranes, an intermodal rail yard, and is expected to handle up to 1 million twenty-foot equivalent units annually. The project will initially be situated on a 200-acre site under a 30-year lease agreement, with the potential for future expansion up to 900 acres. It will include an intermodal yard to streamline the transfer of containers. The project is supported in part by the issuance of infrastructure bonds (Bujanda & Allen, 2024).

The Venture Global CCS Plaquemines carbon capture and sequestration ("CCS") project that will sequester CO_2 produced at the Authorized Facilities and the Expansion Facilities. CO_2 emissions will be captured from the acid gas removal unit and transported via pipeline to state-managed subsurface saline aquifers beneath Barataria Bay. The CO_2 will be compressed into a dense phase, pumped into the ground, and permanently stored. In September 2022, the Louisiana State Mineral and Energy Board approved an operating agreement for pore space located in Plaquemines Parish (Louisiana State Mineral and Energy Board, 2022).

The former Alliance Refinery, now Belle Chasse Terminal, in Belle Chasse, Louisiana refined crude oil into petroleum products and petrochemicals. Damage from Hurricane Ida caused the refinery to shut down in 2021. Subsequently, the refinery was turned into a crude oil terminal. Phillips 66 sold this terminal to Harvest Midstream, and it now operates as a crude storage and transfer facility with approximately 1 million barrels of storage and two docks on Mississippi River. It no longer performs any refining activities (Oil & Gas Watch, 2025; Harvest Midstream, 2022).

The Gulfstream LNG project is a proposed LNG export terminal six miles southeast of the Expansion Facilities. It is currently in pre-filing with FERC under Docket No. PF24-5-000 and has not started construction. If constructed, the facility would involve two feed gas processing trains, three LNG liquefaction trains, one LNG storage tank and tank protection system, two marine berths, and an on-site generation plant (FERC, 2025).

1.11.1.2 Other Developments

The Mississippi River Ship Channel, Gulf to Baton Rouge project is a USACE project in coordination with the non-federal sponsor, the Louisiana Department of Transportation and Development ("LADOTD"). The project aims to deepen the Mississippi River channel through dredging operations and modifications to river infrastructure to allow ships a 50-foot draft for approximately 256 miles from the Gulf of America[6] to Baton Rouge, Louisiana. Construction activities are ongoing, following the USACE's issuance of the Final Environmental Impact Statement in 2018 (USACE, 2018). The Mississippi River in front of the Expansion Facilities is naturally greater than 55 feet and does not require construction or operation and maintenance to provide deep draft access. Therefore, this USACE project will not occur directly in front of or in the areas directly surrounding the Expansion Facilities.

The Bayou Grande Cheniere Ridge Marsh Creation project, managed by the Louisiana Coastal Protection Restoration Authority ("CPRA"), restored marsh habitat and established a ridge of woody species on the western edge of the Mississippi approximately six miles southeast of the Expansion Facilities (CPRA, 2024). This project has been completed.

The Alliance Booster Station and New Water Line to Port Sulphur involve construction of a water booster station in Alliance, Louisiana and the installation of a transmission line to deliverable potable water from the station to Port Sulphur, collectively referred to as the parish water line. The Booster station is approximately seven miles northwest of the Expansion Facilities; however, the water line will cross the Plaquemines LNG Terminal and Expansion Facilities property because it runs along SH 23. The booster station and Phase 1 which is located between the Alliance Booster Station and Hermitage Road is complete, while Phase 2 that is located between Heritage Road and Port Sulphur Water Treatment Plant is under construction and likely to be completed in 2025. The Port Sulphur Water Treatment Plant and Water Intake involves an abandonment project by the Plaquemines Parish Water Department to convert the facility into a booster station as part of parish-wide infrastructure upgrades. The water treatment plant includes reverse osmosis technology to mitigate the impact from the Mississippi River saltwater intrusion. Construction has been completed; therefore, the cumulative impacts associated with the water treatment plant are limited to water resources.

The Cloud Connector Project is a proposed approximately 300-mile intrastate natural gas pipeline that will provide natural gas to the Authorized Facilities and associated Expansion Facilities. The project is anticipated to have an in-service date of February 2029.

As part of ongoing redevelopment associated with the Louisiana Gateway Port, two existing port tenants, Port Ship Service, Inc. and Belle Chasse Marine, are planned to be relocated approximately 1 mile downstream of their current locations adjacent to the Project just north of SH 23. They will serve the same operational functions and will require reconstruction of associated marine infrastructure at the new sites. Existing facilities and structures are currently planned to remain in place and are not proposed for removal.

Two borrow pit locations are located near the Project, which provide essential fill material for other projects. The Plaquemines Dirt & Clay Company owns approximately 600 acres of land that is divided into a north pit and a south pit with a large Parish-maintained levee along a manmade drainage canal (Steeg Law, 2021). The Woodland Borrow Pit is split into north and south areas directly east of the Plaquemines Dirt & Clay Company borrow pits. The Woodland

[6] On January 20, 2025, President Trump issued Executive Order renaming the Gulf of Mexico as the Gulf of America.

North Borrow Pit has supplied levee-grade soils for USACE flood protection initiative projects, including the New Orleans to Venice Hurricane Protection efforts (USACE, 2021).

The Mid-Barataria Sediment Diversion was a coastal restoration project led by the CPRA which aimed to reconnect the Mississippi River to the Barataria Basin by diverting sediment-rich water to rebuild marshland. On July 17, 2025, CPRA canceled the project due to high construction and mitigation costs, public opposition, and ecological risks (RESTORE, 2025).

The LADOTD is planning road extension and bridge projects to support the transportation network in Jefferson and Plaquemines Parishes. These projects include the proposed extension of Peters Road across the Gulf Intracoastal Waterway via a new high-level bridge, which would improve vehicular and freight connectivity between SH 3017 and SH 23. As part of the project, the road centerline and right-of-way would relocate approximately 1.8 miles south to accommodate the right of way for the Peters Road rail corridor realignment project (Bujanda & Allen, 2024, LADOTD, 2025). The Peters Road relocation construction is ongoing. The Gulf Intercoastal Waterway bridge is in the planning stage and construction has not started.

1.11.2 Potential Cumulative Impacts by Resource

1.11.2.1 Groundwater

Direct and indirect impacts on groundwater from the Expansion Facilities will be minor and localized as discussed in Resource Report 2. Due to the high salinity of localized groundwater resources in Plaquemines Parish, groundwater is not a significant source of industrial or potable water in the parish. However, cumulative groundwater withdrawals could have the potential to increase drawdown and exacerbate salinity conditions in the Gramercy aquifer and Coastal Lowlands aquifer system.

No project in table 1.11-2 has the potential to contribute cumulative impacts on groundwater near the Expansion Facilities. The Expansion Facilities are located within two HUC-12 sub-watersheds: HUC-030104040809 (Planters Canal) and HUC-080901000101 (Mississippi River–Bonnet Carré Spillway). Of these, HUC-030104040809 is the smaller, more localized watershed, directly encompassing the Project site. The only other project within this watershed is the Plaquemines LNG Terminal, which is already under construction. Although other projects in table 1.11-2 may overlap with the HUC-080901000101 watershed along the Mississippi River, the marine berth of the Expansion Facilities is limited in its reach and will not perform dredging. Therefore, the Expansion Facilities will not contribute to cumulative impacts on groundwater resources in the vicinity.

Groundwater disruption may occur outside of the HUC-12 sub-watersheds associated with the Project. There are borrow pits directly adjacent to the Expansion Facilities, which may alter groundwater flow in the area and contribute to drawdown in the overall aquifer system.

To minimize potential impacts on groundwater resources from the Expansion Facilities construction and potential spills or leak of hazardous liquids, the Applicants will implement the measures in the Plan and Procedures, SWPPP, and SPCC Plan. Additionally, the Applicants will adhere to the LPDES permits for water discharges during construction and operation. For these reasons, potential cumulative impacts on groundwater associated with the construction and/or operation of the Expansion Facilities will not be significant.

1.11.2.2 Surface Waters, Canals, and Wetlands

Construction and operation of the Expansion Facilities will affect surface waters, and result in the permanent loss of wetland acreage. Some portions of the construction area required for the Expansion Facilities will overlap with previously developed areas of the Plaquemines LNG Terminal; however, new impacts will occur outside of the Plaquemines LNG Terminal to accommodate the Expansion Facilities. Grading activities, fill activities, and spills or leaks of hazardous materials could affect surface water resources. Construction and operation impacts will primarily impact man-made drainage ditches at the Site, which will be filled to support construction of the facilities. No dredging will occur within the Mississippi River.

Any projects involving dredge and fill or obstructing the navigable capacity within waters of the United States would require a Section 10 of the Rivers and Harbors Act and/or Section 404 CWA authorizations from the USACE and corresponding Section 401 CWA Water Quality Certifications. These authorizations require implementation of spill prevention plans during construction and operations. Although a spill or leak from any of the proposed projects could be significant, it is unlikely that multiple actions would result in spills or leaks in the same relative timeframe to produce a significant cumulative effect given the regulatory environment regarding spill prevention. Thus, the cumulatively increased risk associated with spills or leaks of hazardous materials would be minor.

Several regional projects could contribute to cumulative impacts on water resources. The NOLA Terminal is located upstream of the Expansion Facilities and involves construction of riverfront export docks. Construction activities may result in limited wetland impacts and potential sedimentation or stormwater runoff. The Plaquemines LNG Terminal is under construction but has already undergone grading and wetland fill and is not expected to have overlapping construction with the Expansion Facilities.

The Louisiana Gateway Container Terminal is downstream of the Expansion Facilities and will involve work within the Mississippi River. The Cloud Connector Project, which will tie into the Plaquemines LNG Terminal, will cross numerous surface waters and wetlands, where construction would involve trenching, hydrostatic test discharges, and wetland disturbances. If constructed concurrently with the Expansion Facilities, localized increase in sedimentation or accidental discharges would contribute to cumulative effects on the regional water quality. The Gulfstream LNG project would involve filling wetlands and reconfiguring surface drainage systems, and therefore could have cumulative impacts on regional hydrology, especially if construction phases overlap. The Alliance Booster Station is upstream of the Expansion Facilities and the water line will cross the Terminal and Expansion Facilities properties as it is located with SH 23 right-of-way. If constructed concurrently with Expansion Facilities, increased sedimentation would contribute to regional water quality impacts. Construction on the Medium Diversion at Myrtle Grove has not yet been planned, but could potentially affect sedimentation levels and water levels, which would both affect the regional water quality near the Expansion Facilities. water used for

During dry periods and low river flow, the water within the Mississippi River at this location may become too saline for human consumption which places pressure on regional water supplies that may need to be trucked or barged in to offset municipal intakes within the river located downstream. The Expansion Facilities water treatment facility will be designed to remove chlorides from the river to allow the facility to operate during periods of low flow and reduce pressure on regional water supplies that may be needed to offset potable water needs within the community.

The borrow pits near the site may cumulatively impact water resources through potential runoff, however, if the Project requires fill from these facilities, it will eliminate the need to transport in fill from further away, reducing overall stress on transportation and air emissions.

Projects located directly on the Mississippi near the Expansion Facilities have the potential to contribute to cumulative impacts on water resources and Mississippi River conditions. The planned relocation of the Port Ship Service and Belle Chasse Marine to approximately one mile downstream will involve reconstruction of those facilities, which may involve in-water activities such as pile driving and shoreline stabilization.

The projects mentioned above are anticipated to follow best management practices, implement site-specific SWPPPs, plans and seek authorization under the CWA. The Applicants will follow the Procedures to avoid or minimize effects on wetlands, as well as implement mitigation measures to reduce the potential for hazardous spills. Additionally, the Applicants will be required to mitigate unavoidable impacts on wetlands through the USACE and LDENR permitting process. Therefore, although Project construction and operation will result in unavoidable permanent wetland loss and other long-term impacts, these impacts will be offset with appropriate compensatory mitigation.

1.11.2.3 Cultural Resources

Cumulative impacts on cultural resources would only occur if other past, present, or reasonably foreseeable actions affect the same historic properties as the Project. The Area of Potential Effect for direct impacts on historic properties is limited to areas where ground or offshore disturbance will or could take place, which involve the Expansion Facilities including the marine berth. The Project's indirect Area of Potential Effect includes the area of direct effects plus the surrounding areas within view of the new construction, identified as a 1.0-mile-wide buffer from the Expansion Facilities' boundary.

Where direct impacts on significant cultural resources are unavoidable, mitigation will occur before construction (e.g., recovery of data and curation of materials). Projects requiring federal actions, like the Project and other projects listed in table 1.11-2, are required to comply with Section 106 of the National Historic Preservation Act, which requires federal agencies to identify, assess, and mitigate adverse effects, including cumulative effects, on historic properties within the Area of Potential Effect. The Applicants have completed background research on past surveys that have identified sensitive cultural resources and historic properties that could be affected by the Project and have developed a plan to address unanticipated discoveries of cultural resources and human remains during construction. Other federal projects would implement similar plans and measures. For these reasons, cumulative impacts on cultural resources, if any, would not be significant.

1.11.2.4 Fisheries, Wildlife, Endangered and Threatened Species

During construction of the Expansion Facilities, impacts on fisheries and other aquatic resources will result from the excavation, inadvertent release of hazardous materials, pile driving, traffic in the Mississippi River, construction-related stormwater runoff, and hydrostatic testing of storage tanks. However, these impacts will be short term and localized, and adherence to construction best management practices and mitigation measures, permit conditions, and Project-specific construction and operation plans will minimize impacts on local aquatic resources that may be present near the Expansion Facilities. Because the LNG loading berth platforms will increase habitat diversity in the Mississippi River, the platforms may contribute to a long-term

beneficial impact on fisheries resources present in the Mississippi River. While artificial nighttime lighting can create undesirable effects on aquatic resources during Project operations, the Expansion Facilities lighting will be consistent with similar industrial lighting at facilities located along the Mississippi River, including the Plaquemines LNG terminal, and will implement mitigation measures in its Project-specific Facility Lighting Plan. Therefore, the effect on aquatic resources is expected to be negligible because aquatic species in the area are accustomed to lighting from the existing nearby operating industrial facilities.

As described in Resource Report 3, underwater noise levels generated by pile driving can affect aquatic species. Potential noise impacts from construction activities could contribute to a short-term effect on aquatic wildlife; however, impacts from noise on marine species due to the Project are not anticipated to be significant, and the potential for vessel strikes due to increased vessel traffic are unlikely where established, well-traveled, deepwater shipping lanes are used. Additionally, pile driving will not impede wildlife movement along the river long-term.

As shown in table 1.11-2, multiple projects are occurring along the Mississippi River, including the NOLA Terminal and the relocation of Port Ship Service, Inc. and Belle Chasse Marine, will require in-water work such as pile driving. However, cumulative impacts associated with construction and operation of the marine berth on fisheries and aquatic resources are expected to be minimal to nonexistent due to the distance between the sites. Construction of the Plaquemines LNG Terminal marine berths has been completed; therefore, no cumulative impacts on fisheries or aquatic resources will occur.

Construction and operation at the Expansion Facilities will affect wildlife resources and habitat primarily because of vegetation clearing and permanent displacement of species at permanent facility locations. However, wildlife will have the opportunity to leave and inhabit nearby, similar habitats. Aside from the Plaquemines LNG Terminal that is immediately adjacent and the Cloud Connector Project which will tie into the Authorized Facilities, no other projects are geographically nearby that would inhibit wildlife from leaving the area to nearby, similar habitats that are not already developed.

The Project and any projects listed in table 1.11-2 that involve a federal action and have the potential to affect a federally listed threatened or endangered species would be required to comply with Section 7 of the Endangered Species Act, which requires all federal agencies to use their authorities to conserve endangered and threatened species in consultation with the U.S. Fish and Wildlife Service. Pursuant to the regulatory requirement to consult with the U.S. Fish and Wildlife Service regarding project impacts on protected species and habitats, the Service found that the Project is not likely to adversely affect the federally listed species; therefore, it is unlikely that the Project, in combination with the impacts from other projects, would contribute to a significant cumulative effect on threatened and endangered species.

1.11.2.5 Vegetation

Impacts to vegetation will be permanent. The Applicants are evaluating the anticipated permanent conversion and loss impacts associated with the Project and will coordinate with the LDENR and USACE with input from state and federal stakeholder to adequately mitigate impacts. Although other projects within the vicinity, including the relocation of Port Ship Service, Inc. and Belle Chasse Marine, will involve vegetation removal for development, there are not expected to be significant cumulative effects on vegetation.

1.11.2.6 Socioeconomics

As described in Resource Report 5, the Project study area includes Plaquemines Parish, the location of the Project, as well as the adjacent parishes of Jefferson, Orleans, and St. Bernard in Louisiana. For the purposes of this evaluation, there are five resources that could be potentially affected by cumulative impacts due to competition associated with the presence of the construction workforce:

- Employment/Workforce: The analysis considered how the listed projects could affect the availability of a local workforce and the impact the construction and operation of the projects may have on local unemployment.
- Housing: The analysis considered the impact on available housing from the temporary construction workers and permanent workers.
- Economy and Tax Revenues: The analysis considered the impact of the listed projects on the economy and tax revenues.
- Public Services: The analysis considered the impact of the listed projects on public services offered, specifically, water/sewer, electric, public safety, and health care services.
- Transportation: The analysis considered the impacts of the listed projects on roads and marine transportation corridors.

The greatest level of impact on socioeconomic resources that could potentially be affected by cumulative impacts due to competition associated with the presence of the Project construction workforce will occur during the Project construction phase when transient workers reside in the study area and will temporarily affect housing, road transportation, and public services. As the collective construction phase of the projects listed in table 1.11-2 subsides and the projects become operational, the cumulative economic effects in the study area will be positive. Employment will be the largest benefit of the Project and the study area will see an increase in the availability of jobs, many of which will pay higher wages than many current jobs in the study area. Additionally, investment in the study area by way of real property will result in long-term increase in property tax revenue, which can be used to improve local education and public services.

Employment/Workforce

The cumulative impacts on employment and the workforce will create short-term and long-term effects that would derive from a demand for employment in the study area, particularly in the New Orleans-Metairie-Kenner Metropolitan Statistical Area, which is the largest in the state. The short-term effects will include the need for temporary construction workers to build the Expansion Facilities, as well as the workers needed for other projects considered in the cumulative analysis. Long-term employment impacts would derive from permanent jobs created within this area. The short-term and the long-term impacts will be beneficial and may counteract the population decline that has been occurring in portions of the study area in recent years. The increase in jobs will help the local parishes by providing prospective and local populations the ability to work and live in the parishes.

Housing

The anticipated increase in temporary and permanent workers will have an impact on the local housing inventory. Short-term cumulative impacts on housing from the increased workforce could include higher occupancy and increased room rates for hotels and motels, and less availability at recreational vehicle parks, longer commutes for workers living outside the study area, and higher rental costs associated with the increased demand for accommodation. Long-term cumulative impacts will be significantly diminished when compared to the short-term effects. Few workers will become permanent residents in the area and, therefore, these additional residents will be easily accommodated within the current housing inventory available in the study area.

Economy and Tax Revenues

In Louisiana, the energy sector, which includes oil, gas, and LNG, accounts for roughly 25 percent of Louisiana's gross domestic product and approximately 15 percent of statewide employment, with total earnings reaching $25.5 billion (Louisiana Mid-Continent Oil and Gas Association, 2025). Plaquemines Parish ranks second in oil production within the state and 22nd in gas production (Shale XP, 2024). The global COVID-19 pandemic paused economic growth, and Louisiana has yet to recover to pre-pandemic employment numbers as of 2024. The New Orleans-Metairie area remains four percent less than its pre-pandemic employment (Louisiana Illuminator, 2024).

Although the influx of construction workers may cause a temporary burden on public services and temporary housing supply, the socioeconomic benefits of jobs and increased revenues will compensate for adverse effects. The investment in construction, startup costs, and subsequent annual operating expenditures will inject substantial additional income into the regional economy, including economic benefits stemming from purchases of construction materials, construction contracts, and local spending by workers.

Beneficial short-term and long-term cumulative impacts are likely to develop about the economy and tax revenues. These positive impacts include the billions of dollars proposed for investment in the study area over a short amount of time. This investment will lead to economic benefits to the study area and will have a positive effect on adjacent population areas. Long-term and short-term benefits will also include decreased unemployment, population increase in the study area seeking population recovery, and higher tax revenues on a state and local level.

Public Services

The Project will not affect the capability of law enforcement or fire departments to provide consistent levels of service in the study area. Short-term construction impacts may result in increased demand for emergency medical services; however, medical services will typically expand and meet the needs of permanent population growth.

The nearest school system to the Expansion Facilities is the Plaquemines Parish school system. Based on the available capacity within the two nearest school systems, the study area appears to have sufficient educational resources to accommodate school-age children accompanying non-local workers bringing families during their temporary relocation. Additional children will have minor to moderate, short-term effects on the public school system during construction, and minor and permanent impacts during operation.

Road Transportation

When considered alongside other major infrastructure and industrial projects in the region, the Walker Road-Peter Road project could contribute cumulatively to increased traffic volumes and changes to the transportation network. While the bridge and roadway extension would enhance long-term access, emergency response routes, and hurricane evacuation options, providing a net benefit to the region, short-term impacts such as construction-related traffic delays would occur. These effects would be compounded if construction schedules overlap.

The project construction may result in temporary impacts on the ground transportation network in the study area through the movement of workers to and from construction areas and the delivery of construction material. The construction workforce will generate new traffic around the Expansion Facilities. The construction of the Plaquemines LNG Terminal will not overlap with the Expansion Facilities' construction. To reduce potential traffic-related impacts along SH 23, the Applicants have developed a Traffic Study and Management Plan, which identifies anticipated construction traffic volumes and describes plans for safely and effectively managing the traffic volumes throughout the construction of the Expansion Facilities. More information about the traffic management approach is included in the Expansion Facilities Traffic Management Plan in appendix 5B of Resource Report 5.

Marine Transportation

Marine transportation is also expected to contribute to marine traffic along the Mississippi River. Projects including the NOLA Terminal, Louisiana Gateway Container terminal, Gulfstream LNG, relocation of the Port Ship Service, Inc and Belle Chasse Marine, and the Port Support Boat complex could contribute to vessel density dependent on construction schedules. Developments on the Mississippi are coordinated by the Louisiana Gateway Port and vessel transits are coordinated by the Cresent River Port Pilots' Association.

To minimize potential impacts on marine transportation associated with the additional berth associated with the Expansion Facilities, the Applicants developed a Waterway Suitability Assessment for the Project (see Resource Report 13 in the final Application). Any other LNG projects on the Mississippi River would also be required to develop a similar Waterway Suitability Assessment to reduce potential impacts on marine transportation, thus reducing the potential for cumulative impacts.

1.11.2.7 Soil and Geological Resources

The geographic area considered for cumulative impacts related to soils and geology generally consists of projects that overlap with the Project's construction footprint. These Projects include the Plaquemines LNG Terminal which has overlapping workspace with the Project, the Cloud Connector Pipeline which will tie into the Plaquemines LNG Terminal, and the Alliance Booster Station's associated water line which crosses under the Terminal and Expansion Facilities site property as it parallels adjacent to SH 23. The Plaquemines LNG Terminal has completed grading and will not have any additional impacts to soil and geological resources. The Cloud Connector Pipeline will complete restoration and revegetation within the associated workspace, thereby making soil impacts minor and temporary.

The rationale for limiting scope of cumulative impact analysis to the construction footprint for these resources is that, through implementation of best management practices outlined in the Plan, the anticipated impacts on soil and geological resources will be localized in nature and

should not significantly extend beyond the Project footprint. Blasting will not be required and no impacts to geologically sensitive resources, such as kart terrain, are proposed. Overall, the risk of landslides is low. With implementation of the best management practices outlined in the Plan, any potential cumulative impacts on soils and geological resources are anticipated to be minimal.

1.11.2.8 Land Use, Recreation, and Aesthetics

Direct and indirect impacts on land use from the Expansion Facilities will be minor and impacts on recreation near the Expansion Facilities will be minor and short term, as discussed in Resource Report 8. While the Expansion Facilities will be constructed within a floodplain, The Applicants will apply for and obtain the necessary permits for this construction. Visual impacts from the Expansion Facilities will be permanent but minor. Construction of the Expansion Facilities will create temporary visual impacts associated with construction activities; however, these changes will be consistent with the existing industrial land use in the area and the adjacent Plaquemines LNG Terminal.

The relocation of the Port Ship Service, Inc. and Belle Chasse Marine will maintain their existing marine-industrial land use function but contribute to a net increase in port-support activities along the Mississippi River during construction. They may contribute to cumulative visual change along the river corridor but are generally consistent with existing individual characteristics in the area.

The Expansion Facilities will be screened with the storm surge wall that will limit the visual impact on those traveling on nearby roads, and the impact will be relatively minor due to existing industrial facilities surrounding the Expansion Facilities. Because of this wall, the cumulative effect on these developments on aesthetics is not expected to be significant.

1.11.2.9 Air Quality

The Project will result in combustion-related operational emissions associated with the Expansion Facilities, fugitive dust from land clearing, and vehicles traveling to and from the Project. The cumulative impacts of greenhouse and non-greenhouse gas pollutants are discussed in section 9.4 of resource report 9.

Construction Emissions

Air quality impacts associated with the Project construction will generally be temporary and localized. To limit emissions of fugitive dust, the Applicants will maintain construction equipment in accordance with manufacturers' recommendations, and engine idling time will be minimized. Additionally, the Applicants will employ construction practices such as water sprays to control fugitive dust emissions during construction. Due to these factors and the intermittent and short-term characteristics of the emissions, construction is not expected to cause or substantially contribute to a violation of applicable ambient air quality standards or degradation of air quality.

Of the projects listed in table 1.11-2, the NOLA Terminal, Plaquemines LNG Terminal, Belle Chasse Terminal, and Gulfstream LNG would overlap geographically and temporally, potentially resulting in cumulative air quality impacts during Project construction. Each of these terminals would be required to meet the standards for mobile sources established by the EPA non-road source emissions regulations and LDEQ air quality standards. Each project would also

be expected to control fugitive dust emissions during construction. Therefore, construction air emissions are not expected to substantially affect long-term air quality in the region.

Additional construction emissions will be described in the final Application, and the cumulative impact analysis will be updated accordingly.

Operational Emissions

The air quality impacts associated with the Project's operation will be long-term. Venture Global CCS Plaquemines, LLC's carbon capture and sequestration project will reduce the CO_2 emissions from the Authorized Facilities and the Expansion Facilities and will lower the contribution to regional and cumulative air quality impacts. The operational emissions from the Project will be described in the final Application, and the cumulative impact analysis will be updated accordingly.

1.11.2.10 Noise

Construction and operational noise will be generated from the Project and the projects in the area. The Project is required to perform noise modeling and follow the noise guidelines required by FERC. It is anticipated that current cumulative impacts to noise may occur with nearby projects during construction, including the Plaquemines LNG Terminal. The final Application will include Project noise estimates, and the cumulative impact analysis will be updated accordingly at that time.

1.12 REFERENCES

Bujanda & Allen. 2024. Plaquemines: The Louisiana Gateway Port – 2024 Master Plan. Available online at: https://louisianagatewayport.com/port-master-plan/. Accessed July 2025.

Coastal Protection and Restoration Authority of Louisiana (CPRA). 2024. Fiscal Year 2025 Annual Plan. Available online at: https://coastal.la.gov/wp-content/uploads/2024/02/FINAL-CPRA_FY25-AP_20240228_print-compressed.pdf. Accessed July 2025.

Federal Energy Regulatory Commission (FERC). 2007. Draft Seismic Design Guidelines and Data Submittal Requirements for LNG Facilities. Issued January 23, 2007. Available online at www.ferc.gov/industries/gas/indus-act/lng/lng-seis-guide.pdf. Accessed April 2025.

Federal Energy Regulatory Commission (FERC). 2025. Gulfstream LNG Terminal Project. Available online at: https://www.ferc.gov/gulfstream-lng-terminal-project. Accessed July 2025.

Harvest Midstream. 2022. Harvest Midstream Announced an Agreement with Phillips 66 to Purchase the Belle Chasse Terminal. Available online at: https://www.harvestmidstream.com/news/harvest-midstream-announced-an-agreement-with-phillips-66-to-purchase-the-belle-chasse-terminal/. Accessed July 2025.

Louisiana Department of Energy and Natural Resources (LDENR). 2007. LAC, Title 43, Natural Resources, Part XIII. Office of Conservation – Pipeline Safety, Louisiana Pipeline Safety Gas Regulations. March 2007.

Louisiana Department of Transportation and Development (LADOTD). 2025. Peters Road Bridge & Extension (Phase 3). Contract No. 4400029384. Available online at: https://dotd.la.gov/media/d33jdgfd/contract-no-4400031920-hardesty-hanover.pdf. Accessed July 2025.

Louisiana Illuminator. 2024. Louisiana still hasn't recovered all the jobs it lost during the pandemic. Available online at: https://lailluminator.com/2024/07/17/louisiana-still-hasnt-recovered-all-the-jobs-it-lost-during-the-pandemic/. Accessed July 2025.

Louisiana Mid-Continent Oil and Gas Association. 2025. 2025 Study: Energy industry generates 25% of Louisiana's economy. Available online at: https://www.lmoga.com/news/2025-study-energy-industry-generates-25-of-louisianas-economy. Accessed July 2025.

Louisiana State Mineral and Energy Board. 2022. Carbon Dioxide Storage Agreement. Available online at: https://www.dnr.louisiana.gov/assets/OMR/media/forms_pubs/CS003.pdf. Accessed July 2025.

National Fire Protection Association (NFPA). 2017. NFPA 70: Standard for Electric Code. Available online at https://www.nfpa.org/codes-and-standards/all-codes-and-standards/list-of-codes-and-standards/detail?code=70. Accessed April 2025.

National Fire Protection Association (NFPA). 2019. NFPA 59A: Standard for the Production, Storage, and Handling of Liquefied Natural Gas. Available online at https://www.nfpa.org/codes-and-standards/all-codes-and-standards/list-of-codes-and-standards/detail?code=59A. Accessed April 2025.

NOLA Terminal. 2025. Available online at https://nolaterminal.com/. Accessed July 2025.

Oil & Gas Watch. 2025. Belle Chasse Terminal (former Alliance Refinery). Available online at: https://oilandgaswatch.org/facility/4653. Accessed July 2025.

RESTORE. 2025. Louisiana Cancels Landmark Restoration Project, Undermining Decades of Coastal Progress. Available online at: https://mississippiriverdelta.org/louisiana-cancels-landmark-restoration-project-undermining-decades-of-coastal-progress/. Accessed July 2025.

S&P Global. 2024. *Major New U.S. Industry at a Crossroads: A U.S. LNG Impact Study – Phase 1.* December 2024.

Shale XP. 2024. Oil and Gas Activity in Plaquemines Parish, LA. Available online at: https://www.shalexp.com/louisiana/plaquemines-parish. Accessed July 2025.

Steeg Law. 2021. Expanding a Servitude to Create an Expeditious Way to Access Property for Hurricane Protection. Available online at: https://www.steeglaw.com/expanding-a-servitude-to-create-an-expeditious-way-to-access-property-for-hurricane-protection/. Accessed August 2025.

U.S. Army Corps of Engineers (USACE). 2018. Mississippi River Ship Channel. Available online at: https://www.mvn.usace.army.mil/About/Mississippi-River-Ship-Channel/. Accessed July 2025.

U.S. Army Corps of Engineers (USACE). 2021. Environmental Assessment #586. Available online at: https://www.mvn.usace.army.mil/Portals/56/Users/194/42/2242/EA_586_Draft Document.pdf . Accessed August 2025.

U.S. Coast Guard (USCG). 1988. 33 CFR 127-- Waterfront Facilities Handling Liquefied Natural Gas and Hazardous Gas. February 7, 1988.

U.S. Department of Energy (DOE). 2024. *Energy, Economic, and Environmental Assessment of U.S. LNG Exports.* December 2024.

U.S. Department of Transportation (DOT). 2006. 49 CFR 193—Liquefied Natural Gas Facilities: Federal Safety Standards. 71 Fed. Reg. 33408 (June 9, 2006).

U.S. Energy Information Administration (EIA). 2025. Short-Term Energy Outlook. Available online at https://www.eia.gov/outlooks/steo/report/natgas.php. Accessed August 2025.

Venture Global LNG, Inc. 2025. Plaquemines LNG Terminal. Available online at: https://ventureglobal.com/venture-global-plaquemines/plaquemines-facility/. Accessed August 2025.

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1
APPENDIX 1A

Figures

Public Version

Figure 1.1-1 Regional Location of Proposed Project (Topographic Map)
Figure 1.1-2 Regional Location of Proposed Project (Aerial Map)
Figure 1.1-3 Proposed Expansion Facilities (layout)
Figure 1.11-1 Projects Considered in Cumulative Impact Analysis

Service Layer Credits: USA_Topo_Maps: Copyright:© 2013 National Geographic Society, i-cubed




Figure 1.1-1
Regional Location of Proposed Project
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 7/14/2025

Service Layer Credits: USA NAIP Imagery: Natural Color: Esri, USDA Farm Service Agency




Figure 1.1-2
Regional Location of Proposed Project
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 7/14/2025

Service Layer Credits: World Imagery: Maxar





Storm Wall
Phase I/II Facilities
Expansion Facilities
Proposed Marine Facility
Marine Workspace

Parking/Laydown (Permanent)
Parking/Laydown (Existing)

Parking/Laydown (Temporary)
Utility/Drainage Workspace

Scale: 1:22,000

NORTH

1,000 0 1,000
Feet

PLAQUEMINES

BURNS McDONNELL℠

Figure 1.1-3
Proposed Expansion Facilities (layout)
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 7/11/2025





Figure 1.8-1
Location of Cloud Connector Project
Plaquemines Expansion
Louisiana

Sources: Esri, Garmin International, Inc., Source: U.S. Census Bureau, Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, © OpenStreetMap contributors, and the GIS User Community, Randy McGregor (Original Publisher), Burns & McDonnell

Source: Burns & McDonnell

Issued: 8/15/2025

Service Layer Credits: Cloud Connector Centerline : Randy McGregor (Original Publisher), Burns & McDonnell, ENS



Project Number	Project Name
1	NOLA Oil Terminal
2	Plaquemines LNG
3	Louisiana Gateway Container Terminal
4	Plaquemines CCS
5	Bell Chasse Terminal
6	Gulfstream LNG Project
7	Mississippi River Dredging Project
8	Bayou Grande Cheniere Ridge Marsh Creation
9	Parish Water Line
10	Cloud Connector Project
11	Port Ship Service, Inc.
12	Belle Chasse Marine
13	Plaquemines Dirt & Clay Borrow Pit
14	Woodland Borrow Pits
15	Medium Diversion at Myrtle Grove
16	Walker Road - Peters Road Extension and Bridge Projects
17	Port Support Boat Complex
18	On-Site Concrete



Phase I/II Facilities

Expansion Facilities

Non-linear Project

Linear Project

Scale: 1:270,000

NORTH

4 0 4

Miles

PLAQUEMINES

BURNS McDONNELL

Figure 1.11-1
Projects Considered in Cumulative Impact Analysis
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 8/18/2025

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1
APPENDIX 1A

Figures

(Filed Under Separate Cover as Controlled Unclassified Information/Critical Energy Infrastructure Information [CUI/CEII])

Figure 1.3-1 Proposed Expansion Facilities (Aerial Map) (*filed under separate cover as Controlled Unclassified Information (CUI)//Critical Energy Infrastructure Information (CEII)*)

Figure 1.3-2 Proposed Expansion Facilities (Topographic Map) (*Filed under separate cover as CUI//CEII*)

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1
APPENDIX 1B

TABLES

Table 1.9-1 Permits, Approvals, and Consultations

Table 1.11-2 Projects and Reasonably Foreseeable Future Actions with Potential to Contribute to Cumulative Impacts

Table 1.9-1

Plaquemines Expansion Project
Permits, Approvals, and Consultations

Agency / Contact Name	Permit/Approval/ Regulatory Scope	Correspondence Type	Status
Federal			
Federal Energy Regulatory Commission (FERC) Terry Turpin, Director, Office of Energy Projects	Authorization to Construct and Operate Facilities under section 3(a) of the Natural Gas Act	Pre-filing Participation Request Letter Lead federal agency	Pre-filing letter sent: March 6, 2025. Updated informational letter sent: July 18, 2025. Application to be submitted October 2025
U.S. Department of Energy, Office of Fossil Energy (DOE/FE) Amy Sweeney, Director, Office of Regulation, Analysis, and Engagement	Authorization to export LNG by LNG carrier to Free Trade Agreement (FTA) and non-FTA nations	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Application will be submitted in the fourth quarter of 2025.
U.S. Department of Homeland Security – U.S. Coast Guard Waterway Management Division, 8th District, Sector New Orleans Captain Kelly K. Denning Sector Commander	Waterfront Facilities Handling Liquefied Natural Gas and Liquefied Hazardous Gas (33 Code of Federal Regulations [CFR] 127), which includes Letter of Intent submission (33 CFR 127.007), Waterway Suitability Assessment (WSA) consultation (including Preliminary WSA and Follow-on WSA), and Letter of Recommendation from the U.S. Coast Guard (18 CFR 157.21)	Preliminary WSA and Letter of Intent	Preliminary WSA and Letter of Intent sent March 5, 2025 Follow-On WSA Workshop with stakeholders completed July 31, 2025. Final WSA to be complete in August 2025.
U.S. Environmental Protection Agency – Region VI, Dallas, TX W. Scott Mason, Regional Administrator	Consultation role to Louisiana Department of Environmental Quality on air emissions permitting Floodplain management and protection of wetlands (44 CFR 9) Review of wetlands impacts for U.S. Army Corps of Engineers Clean Water Act Section 404 permit	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025.
U.S. Army Corps of Engineers (USACE) – New Orleans District Martin Mayer, Chief, Regulatory Branch	Clean Water Act Section 404 Permit for impacts on waters of the United States, including wetlands (33 United States Code [USC] §1344) Rivers and Harbors Act Section 10 Permit for construction and operation of structures in and across federally navigable waterways (33 USC § 403) Section 408 authorization for work to alter USACE civil works (e.g., levees) (33 USC Section 408)	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Section 404/10 Permit amendment request to be submitted September 2025 Section 408 Permit Amendment request to be submitted in September 2025.
U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Marine Fisheries Service Andy Strelcheck, Deputy Regional Administrator	Endangered Species Act Section 7 Consultation (16 USC § 1856 et seq.) Magnuson-Stevens Fishery Conservation and Management Act Consultation Essential Fish Habitat Consultation (50 CFR Part 600) Fish and Wildlife Coordination Act Consultation (16 USC §§ 661 et seq.)	Informational Letter Consultation Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Consultation regarding essential fish habitat (EFH) initiated May 15, 2025. Response received June 9, 2025 stating no objection to the Project as proposed. Consultation regarding endangered species act sent June 27, 2025. Additional consultation regarding updated landward expansion on July 29,2025. Response received August 1, 2025 concurring that landward changes would not impact EFH.

Table 1.9-1

Plaquemines Expansion Project
Permits, Approvals, and Consultations

Agency / Contact Name	Permit/Approval/ Regulatory Scope	Correspondence Type	Status
U.S. Fish and Wildlife Service, Southeast Region 4 Dustin Garig, Deputy Field Supervisor Southeast Region	Endangered Species Act Section 7 Consultation (16 USC § 1536) Migratory Bird Treaty Act Consultation (16 USC §§ 703 et seq.) Fish and Wildlife Coordination Act Consultation (16 USC §§ 661 et seq.)	Informational Letter Consultation Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Consultation initiated May 14, 2025. Response received June 13, 2025 concurring that the Project is not likely to adversely affect federally listed species. Additional consultation regarding Project expansion, Response receive August 7, 2025 concurring expansion would not change previous determinations.
Federal Aviation Administration (FAA) Rob Lowe, Southwest Region Regional Administrator	FAA's regulations at 14 CFR Part 77.	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. FAA Notification to be determined by final design.
U.S. Department of Transportation Pipeline and Hazardous Materials Safety Administration Alan K. Mayberry Associate Administrator for Pipeline Safety	Letter of No Objection 49 CFR 193 Subpart B	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Application to be submitted September 2025.
State			
Louisiana Department of Environmental Quality – Water Permits Division Jenniffer Sheppard, Water Permits Administrator	Section 401 Water Quality Certification (33 USC § 1341) LPDES Industrial Hydrostatic Test Water Discharge General Permit (La. R.S. 30:2001 et seq.). Wastewater Discharge Permit, Section 402 (33 USC § 1342).	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Section 401 application will be initiated concurrent with U.S. Army Corps of Engineers' Section 404/10 Public Notice. Hydrostatic test water discharges permit applications to be submitted prior to construction. Wastewater Discharge Permit Amendment for operation of facilities pending final design.
Louisiana Department of Environmental Quality – Office of Environmental Quality Bryan Johnston, Air Permits – Administrator	Title V and Prevention of Deterioration of Significant (PSD) Air Permits (40 CFR Part 70)	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Application to be submitted September 2025.
Louisiana Department of Energy and Natural Resources (LDENR) – Office of Coastal Management Keith Lovell, Assistant Secretary	Coastal Use Permit (CUP), a Joint Permit Application with U.S. Army Corps of Engineers (R.S. 49:214.25)	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Terminal Site is located within fastlands and exempt from CUP. Application for No Direct and Significant CUP determination to be submitted for Marine Facilities in September 2025.

Table 1.9-1

Plaquemines Expansion Project
Permits, Approvals, and Consultations

Agency / Contact Name	Permit/Approval/ Regulatory Scope	Correspondence Type	Status
Louisiana Department of Wildlife and Fisheries Madison Sheahan – Secretary	Threatened and Endangered Species Consultation (16 USC §§ 460 et seq.)	Informational Letter	Informational letter sent: March 6, 2025 Response received April 8, 2025 indicating the Coastal Live Oak-Hackberry Forest near the Project, and no other impacts to rare, threatened, or endangered species or critical habitat are anticipated. Consultation to be initiated as part of the LDENR CUP application process. Consultation on July 29, 2025 requesting an in-stream work waiver to allow the Project to construct the marine berth in the Mississippi River year-round (as needed). Response received concurring on July 31, 2025.
Louisiana Office of Cultural Development, Division of Archaeology Dr. Charles “Chip” McGimsey, Director Carrie Broussard Assistant Secretary	National Historic Preservation Act Section 106 Consultation (36 CFR Part 800) and Review	Informational Letter Consultation Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Consultation letter sent July 1, 2025. Response received concurring with the APE and survey recommendations, and approving draft UDP.
Louisiana Office of State Lands Lawrence Rosso, Jr., Section Manager	Permit and Lease for State Water Bottoms (L.S.R. 41:1701-1714)	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Jurisdiction of state water bottoms at the location of the Marine facilities has been conveyed to Louisiana Gateway Port.
Louisiana Department of Transportation and Development Connie Betts, Transportation Planning Administrator	Various Project, Access Connection/Traffic Generator and Temporary Occupancy Permits	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Applications to be submitted prior to construction.
Coastal Protection and Restoration Authority	Letter of No Objection to support Section 408 Review		Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Letter of No Objection request to be submitted concurrent with Section 408 Permit application amendment to the U.S. Army Corps of Engineers.
Local			
Plaquemines Parish Port Charles Tillotson Executive Director	Lease agreement	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025.
Plaquemines Parish Police Jury Ametra Rose Planning & Zoning Superintendent	Site Development Permit	Informational Letter	Informational letter sent: March 6, 2025 Updated informational letter sent: July 18, 2025. Applications for Site Development Permits to be submitted in 2026.

Table 1.9-1

Plaquemines Expansion Project
Permits, Approvals, and Consultations

Agency / Contact Name	Permit/Approval/ Regulatory Scope	Correspondence Type	Status
Plaquemines Parish Levee District Ken Dugas, P.E. Chief Parish Engineer	Section 408 Letter of No Objection	Informational Letter	Informational letter sent: March 6, 2025 Letter of No Objection request to be submitted concurrent with Section 408 Permit application amendment to the U.S. Army Corps of Engineers.
Native American Tribes			
Alabama-Coushatta Tribe of Texas Tribal Historic Preservation Officer Bryant Celestine	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025.
Chitimacha Tribe of Louisiana Kimberly S. Walden Tribal Historic Preservation Officer	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025.
Coushatta Tribe of Louisiana Kristian Poncho Tribal Historic Preservation Officer	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025.
Choctaw Nation of Oklahoma Tribal Historic Preservation Officer Lindsey D. Bilyeau	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025. Response received May 23, 2025, requesting additional information. Additional information sent to Choctaw Nation on June 20, 2025. Response received July 31, 2025 with additional information requests. Additional information sent August 4, 2025.
Jena Band of Choctaw Indians Johnna Flynn Tribal Historic Preservation Officer	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025.

Table 1.9-1

Plaquemines Expansion Project
Permits, Approvals, and Consultations

Agency / Contact Name	Permit/Approval/ Regulatory Scope	Correspondence Type	Status
Mississippi Band of Choctaw Indians Tribal Historic Preservation Officer Kenneth Carleton	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025.
Seminole Tribe of Florida Tribal Historic Preservation Officer Tina Marie Osceola	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025.
Seminole Nation of Oklahoma Tribal Historic Preservation Officer Ben Yahola	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025.
Tunica-Biloxi Indians of Louisiana Early J. Barbry, Jr. Tribal Historic Preservation Officer	Consultation	Informational Letter	Informational letter sent: March 6, 2025 Letter to Tribe introducing the Project and requesting input archaeological sites, burials, and traditional cultural properties of concern sent on June 13, 2025. Updated informational letter sent: July 18, 2025.

TABLE 1.11-2

Plaquemines Expansion Project
Past, Present, and Reasonably Foreseeable Activities and Projects Considered in the Cumulative Impact Analysis [a]

Project Name and Project Proponent/Sponsor	Location	Distance from Project (miles)	Number on Figure 1.11-1	Description	Permits/Authorizations or Environmental Reviews	Current Status	Cumulative Resources Potentially Affected [b]
INDUSTRIAL DEVELOPMENTS							
NOLA Terminal NOLA Terminal, LLC	Plaquemines Parish, Louisiana	1.2 miles northwest	1	Multi-use terminal on the Mississippi River for transfer, storage, and export of bulk commodities including grain, concrete, and crude oil.	U.S. Army Corps of Engineers (“USACE”) Permit (MVN-2013-00550 EMM), Louisiana Department of Environmental Quality (“LDEQ”) Air permit issued in 2013 No known permits as of 3/3/2025	Phase 1 construction complete. Phase 2 construction not yet started.	Water resources, 0.1 ac of wetlands, socioeconomics, air - construction
Plaquemines LNG Venture Global Plaquemines LNG, LLC	Port Sulphur, Plaquemines Parish, Louisiana	Adjacent	2	632-acre LNG terminal with liquefaction facilities; includes Gator Express pipeline	FERC order issued: September 30, 2019 (Docket No. CP17-66-000) USACE Permit MVN-2015-2098-EPP Air Permit PSD-LA-808 (M-4) (pending 2023), 2240-00443-V4 (issued 2019)	Operational	Air, wetlands, water, noise
Louisiana Gateway Container Terminal	Plaquemines Parish, Louisiana	2.4 miles southeast	3	Container terminal including three berths with six ship-to-shore cranes, an intermodal rail yard, and an effective terminal capacity of up to 1.0 million twenty-foot equivalent units annually	USACE Public Notice MVN-2022-00523-EPP	Construction has not yet started, anticipated to begin late 2025	Water resources, socioeconomics, marine transportation
Plaquemines CCS Venture Global CCS Plaquemines, LLC	Within existing Terminal Site	Adjacent	4	Capture CO2 from combined cycle gas turbine exhaust and transport via pipeline into state-controlled subsurface saline aquifers beneath Barataria Bay	Louisiana Department of Natural Resources Operating Permit issued in 2022, Class VI well permit application pending	Construction not yet started	Socioeconomics, air
Alliance Refinery dba Belle Chasse Terminal Harvest Louisiana Terminals, LLC	Plaquemines Parish, Louisiana	6 miles northwest	5	3,200-acre terminal containing 1 million barrels of active storage crude oil capacity and two crude oil loading docks for transfer activities	Additional information requested for air permit no. 2513-V12 on 6/13/2025	Operational	Air, socioeconomics, noise
Gulfstream LNG Project	Plaquemines Parish, Louisiana	5.5 miles southeast	6	Construction of two feed gas processing trains, three LNG trains each with an average base LNG production capacity of approximately 1.4 MPTA, one LNG storage tank and tank protection system, two marine berths, and an on-site power generation plant.	Application filed with FERC in July 2025. Permits pending.	Construction has not started	Water resources, air quality, marine transportation
OTHER DEVELOPMENTS							
Mississippi River Ship Channel, Gulf to Baton Rouge, LA Dredging Project COE and Louisiana Department of Transportation and Development	Jefferson and Plaquemines Parish, Louisiana	24 miles northwest	7	Deepening the Mississippi River ship channel to allow ships a 50-foot draft for approximately 256 miles from the Gulf of Mexico to Baton Rouge, primarily occurring between mile 98.3 and 100.6 AHP, adjacent to New Orleans	COE Final EIS published April 2018	Construction on-going	Socioeconomics
Bayou Grande Cheniere Ridge Marsh Creation CPRA	Plaquemines Parish, Louisiana	7.3 miles southeast	8	500-acre marsh restoration west of the Mississippi River	USACE Permit MVN-2020-0024 issued 2021	Construction has not started	No resources affected within geographic scope

TABLE 1.11-2

Plaquemines Expansion Project
Past, Present, and Reasonably Foreseeable Activities and Projects Considered in the Cumulative Impact Analysis [a]

Project Name and Project Proponent/Sponsor	Location	Distance from Project (miles)	Number on Figure 1.11-1	Description	Permits/Authorizations or Environmental Reviews	Current Status	Cumulative Resources Potentially Affected [b]
Parish Water Line (Alliance Booster Station and new water line to Port Sulphur Water Treatment) Plaquemines Parish Water Department	Plaquemines Parish, Louisiana	6.5 miles northwest to Booster Site/ pipeline will cross Terminal Site property	9	Construction of greenfield booster station and 13 miles of 20-inch-diameter water line to be construction adjacent to SH23 in two phases. Phase 1 is located between the Alliance Booster Station and Hermitage Road. Phase 2 is located between Hermitage Road and Port Sulphur Water Treatment Plant.	Data not publicly available	Phase 1 complete. Phase 2 construction on-going	Water resources, soils and geology, noise – construction, air quality – construction
Cloud Connector Project	Richland, Franklin, Catahoula, Concordia, Avoyelles, Pointe Coupee, St. Landry, Iberville, Assumption, Terrebonne, Jefferson, and Plaquemines Parishes Louisiana	Ties into Project LNG Terminal. 293 miles NW to the existing Project LNG Terminal	10	Proposed intrastate natural gas pipeline to be constructed within an approximately 300-mile-long corridor, crossing thirteen parishes.	No permits issued yet – USACE is the lead agency	Construction has not started	Socioeconomics, water resources, biological resources
Port Ship Service, Inc.	Plaquemines Parish, Louisiana	Adjacent, north of SH 23	11	Marine transportation service that provides a docking location to embark and/or disembark river pilots that anchor within the Davant and Point Celeste Anchorages. Project will be relocated approximately 1 mile east as part of Louisiana Gateway Port development.	None associated with relocation	Not yet relocated	Water resources, vegetation, wildlife, socioeconomics, marine transportation, land use, visual, noise (operation and construction), air quality (operation and construction)
Belle Chasse Marine	Plaquemines Parish, Louisiana	Adjacent, north of SH 23	12	Marine transportation service. Project will be relocated approximately 1 mile east as part of Louisiana Gateway Port development.	None associated with relocation	Not yet relocated	Water resources, vegetation, wildlife, socioeconomics, marine transportation, land use, visual, noise (operation and construction), air quality (operation and construction)
Plaquemines Dirt & Clay Borrow Pit	Plaquemines Parish, Louisiana	2.2 mile southeast	13	Provides essential fill material to projects in the area.	Plaquemines Parish #2013-4372	Operational	Ground water, water resources,
Woodland Borrow Pit North and South	Plaquemines Parish, Louisiana	Adjacent to eastern Project area	14	Provides essential fill material to projects in the area.	Plaquemines Parish #2019-753 and #2013-4164, LAR10K093	Operational	Ground water, water resources,
Medium Diversion at Myrtle Grove with Dedicated Dredging Louisiana Coastal Area	Myrtle Grove, Plaquemines Parish, Louisiana	0.9 mile south	15	Establish geomorphic connection from the Mississippi River to the estuary to introduce sediments to build and sustain wetlands	N/A; Project previously suspended but funding is being redirected to revive this project after the cancellation of the Mid-Barataria Sediment Diversion	Construction not started	Water resources, socioeconomics
Walker Road – Peters Road extension and bridge projects Louisiana Department of Transportation and Development	Jefferson and Plaquemines Parishes, Louisiana	17.5 miles northwest	16	The Peters Road and relocation will streamline the transportation network by improving access for trucks and other vehicles transporting goods to and from the Louisiana Gateway Port.	Data not publicly available	Peters Road relocation construction ongoing. Gulf Intercoastal Waterway construction not started.	Socioeconomics - transportation
Port Support Boat Complex	Plaquemines Parish, Louisiana	1 miles east	17	A new facility for watercrafts and emergency response will be constructed at mile marker 52.	Data not publicly available	Construction not yet started	Water resources, marine traffic
On-Site Concrete, LLC	Plaquemines Parish, Louisiana	Adjacent to eastern Project area	18	Concrete manufacturing facilities batch plant	Louisiana Department of Environmental Quality Air Permit RP_242133_ PER20240001	Operational	Water resources

[a] This table lists those projects that are most likely to contribute to cumulative impacts within the vicinity of the proposed Plaquemines Expansion Project; it is not intended to provide an all-inclusive listing of all projects in the region.

[b] Cumulative resources potentially affected do not include impacts from cumulative air model. These potential sources will be evaluated in the final application.

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1
APPENDIX 1C

Upland Erosion Control, Revegetation and Maintenance Plan

UPLAND EROSION CONTROL, REVEGETATION, AND MAINTENANCE PLAN

MAY 2013 VERSION

UPLAND EROSION CONTROL, REVEGETATION, AND MAINTENANCE PLAN

TABLE OF CONTENTS

I. APPLICABILITY 1

II. SUPERVISION AND INSPECTION 2
- A. ENVIRONMENTAL INSPECTION 2
- B. RESPONSIBILITIES OF ENVIRONMENTAL INSPECTORS 2

III. PRECONSTRUCTION PLANNING 4
- A. CONSTRUCTION WORK AREAS 4
- B. DRAIN TILE AND IRRIGATION SYSTEMS 4
- C. GRAZING DEFERMENT 5
- D. ROAD CROSSINGS AND ACCESS POINTS 5
- E. DISPOSAL PLANNING 5
- F. AGENCY COORDINATION 5
- G. SPILL PREVENTION AND RESPONSE PROCEDURES 6
- H. RESIDENTIAL CONSTRUCTION 6
- I. WINTER CONSTRUCTION PLANS 6

IV. INSTALLATION 7
- A. APPROVED AREAS OF DISTURBANCE 7
- B. TOPSOIL SEGREGATION 8
- C. DRAIN TILES 9
- D. IRRIGATION 9
- E. ROAD CROSSINGS AND ACCESS POINTS 9
- F. TEMPORARY EROSION CONTROL 9
  - 1. Temporary Slope Breakers 9
  - 2. Temporary Trench Plugs 10
  - 3. Sediment Barriers 10
  - 4. Mulch 11

V. RESTORATION 12
- A. CLEANUP 12
- B. PERMANENT EROSION CONTROL DEVICES 13
  - 1. Trench Breakers 13
  - 2. Permanent Slope Breakers 14
- C. SOIL COMPACTION MITIGATION 14
- D. REVEGETATION 15
  - 1. General 15
  - 2. Soil Additives 15
  - 3. Seeding Requirements 15

VI. OFF-ROAD VEHICLE CONTROL 16

VII. POST-CONSTRUCTION ACTIVITIES AND REPORTING 17
- A. MONITORING AND MAINTENANCE 17
- B. REPORTING 18

UPLAND EROSION CONTROL, REVEGETATION, AND MAINTENANCE PLAN (PLAN)

I. APPLICABILITY

A. The intent of this Plan is to assist project sponsors by identifying baseline mitigation measures for minimizing erosion and enhancing revegetation. Project sponsors shall specify in their applications for a new FERC authorization and in prior notice and advance notice filings, any individual measures in this Plan they consider unnecessary, technically infeasible, or unsuitable due to local conditions and fully describe any alternative measures they would use. Project sponsors shall also explain how those alternative measures would achieve a comparable level of mitigation.

Once a project is authorized, project sponsors can request further changes as variances to the measures in this Plan (or the applicant's approved plan). The Director of the Office of Energy Projects (Director) will consider approval of variances upon the project sponsor's written request, if the Director agrees that a variance:

1. provides equal or better environmental protection;

2. is necessary because a portion of this Plan is infeasible or unworkable based on project-specific conditions; or

3. is specifically required in writing by another federal, state, or Native American land management agency for the portion of the project on its land or under its jurisdiction.

Sponsors of projects planned for construction under the automatic authorization provisions in the FERC's regulations must receive written approval for any variances in advance of construction.

Project-related impacts on wetland and waterbody systems are addressed in the staff's Wetland and Waterbody Construction and Mitigation Procedures (Procedures).

II. SUPERVISION AND INSPECTION

A. ENVIRONMENTAL INSPECTION

1. At least one Environmental Inspector is required for each construction spread during construction and restoration (as defined by section V). The number and experience of Environmental Inspectors assigned to each construction spread shall be appropriate for the length of the construction spread and the number/significance of resources affected.

2. Environmental Inspectors shall have peer status with all other activity inspectors.

3. Environmental Inspectors shall have the authority to stop activities that violate the environmental conditions of the FERC's Orders, stipulations of other environmental permits or approvals, or landowner easement agreements; and to order appropriate corrective action.

B. RESPONSIBILITIES OF ENVIRONMENTAL INSPECTORS

At a minimum, the Environmental Inspector(s) shall be responsible for:

1. Inspecting construction activities for compliance with the requirements of this Plan, the Procedures, the environmental conditions of the FERC's Orders, the mitigation measures proposed by the project sponsor (as approved and/or modified by the Order), other environmental permits and approvals, and environmental requirements in landowner easement agreements.

2. Identifying, documenting, and overseeing corrective actions, as necessary to bring an activity back into compliance;

3. Verifying that the limits of authorized construction work areas and locations of access roads are visibly marked before clearing, and maintained throughout construction;

4. Verifying the location of signs and highly visible flagging marking the boundaries of sensitive resource areas, waterbodies, wetlands, or areas with special requirements along the construction work area;

5. Identifying erosion/sediment control and soil stabilization needs in all areas;

6. Ensuring that the design of slope breakers will not cause erosion or direct water into sensitive environmental resource areas, including cultural resource sites, wetlands, waterbodies, and sensitive species habitats;

7. Verifying that dewatering activities are properly monitored and do not result in the deposition of sand, silt, and/or sediment into sensitive environmental resource areas, including wetlands, waterbodies, cultural resource sites, and sensitive species habitats; stopping dewatering activities if such deposition is occurring and ensuring the design of the discharge is changed to prevent reoccurrence; and verifying that dewatering structures are removed after completion of dewatering activities;

8. Ensuring that subsoil and topsoil are tested in agricultural and residential areas to measure compaction and determine the need for corrective action;

9. Advising the Chief Construction Inspector when environmental conditions (such as wet weather or frozen soils) make it advisable to restrict or delay construction activities to avoid topsoil mixing or excessive compaction;

10. Ensuring restoration of contours and topsoil;

11. Verifying that the soils imported for agricultural or residential use are certified as free of noxious weeds and soil pests, unless otherwise approved by the landowner;

12. Ensuring that erosion control devices are properly installed to prevent sediment flow into sensitive environmental resource areas (e.g., wetlands, waterbodies, cultural resource sites, and sensitive species habitats) and onto roads, and determining the need for additional erosion control devices;

13. Inspecting and ensuring the maintenance of temporary erosion control measures at least:

    a. on a daily basis in areas of active construction or equipment operation;

    b. on a weekly basis in areas with no construction or equipment operation; and

    c. within 24 hours of each 0.5 inch of rainfall;

14. Ensuring the repair of all ineffective temporary erosion control measures within 24 hours of identification, or as soon as conditions allow if compliance with this time frame would result in greater environmental impacts;

15. Keeping records of compliance with the environmental conditions of the FERC's Orders, and the mitigation measures proposed by the project sponsor in the application submitted to the FERC, and other federal or state environmental permits during active construction and restoration;

16. Identifying areas that should be given special attention to ensure stabilization and restoration after the construction phase; and

17. Verifying that locations for any disposal of excess construction materials for beneficial reuse comply with section III.E.

III. PRECONSTRUCTION PLANNING

The project sponsor shall do the following before construction:

A. CONSTRUCTION WORK AREAS

1. Identify all construction work areas (e.g., construction right-of-way, extra work space areas, pipe storage and contractor yards, borrow and disposal areas, access roads) that would be needed for safe construction. The project sponsor must ensure that appropriate cultural resources and biological surveys are conducted, as determined necessary by the appropriate federal and state agencies.

2. Project sponsors are encouraged to consider expanding any required cultural resources and endangered species surveys in anticipation of the need for activities outside of authorized work areas.

3. Plan construction sequencing to limit the amount and duration of open trench sections, as necessary, to prevent excessive erosion or sediment flow into sensitive environmental resource areas.

B. DRAIN TILE AND IRRIGATION SYSTEMS

1. Attempt to locate existing drain tiles and irrigation systems.

2. Contact landowners and local soil conservation authorities to determine the locations of future drain tiles that are likely to be installed within 3 years of the authorized construction.

3. Develop procedures for constructing through drain-tiled areas, maintaining irrigation systems during construction, and repairing drain tiles and irrigation systems after construction.

4. Engage qualified drain tile specialists, as needed to conduct or monitor repairs to drain tile systems affected by construction. Use drain tile specialists from the project area, if available.

C. GRAZING DEFERMENT

Develop grazing deferment plans with willing landowners, grazing permittees, and land management agencies to minimize grazing disturbance of revegetation efforts.

D. ROAD CROSSINGS AND ACCESS POINTS

Plan for safe and accessible conditions at all roadway crossings and access points during construction and restoration.

E. DISPOSAL PLANNING

Determine methods and locations for the regular collection, containment, and disposal of excess construction materials and debris (e.g., timber, slash, mats, garbage, drill cuttings and fluids, excess rock) throughout the construction process. Disposal of materials for beneficial reuse must not result in adverse environmental impact and is subject to compliance with all applicable survey, landowner or land management agency approval, and permit requirements.

F. AGENCY COORDINATION

The project sponsor must coordinate with the appropriate local, state, and federal agencies as outlined in this Plan and/or required by the FERC's Orders.

1. Obtain written recommendations from the local soil conservation authorities or land management agencies regarding permanent erosion control and revegetation specifications.

2. Develop specific procedures in coordination with the appropriate agencies to prevent the introduction or spread of invasive species, noxious weeds, and soil pests resulting from construction and restoration activities.

3. Develop specific procedures in coordination with the appropriate agencies and landowners, as necessary, to allow for livestock and wildlife movement and protection during construction.

4. Develop specific blasting procedures in coordination with the appropriate agencies that address pre- and post-blast inspections; advanced public notification; and mitigation measures for building foundations, groundwater wells, and springs. Use appropriate methods (e.g., blasting mats) to prevent damage to nearby structures and to prevent debris from entering sensitive environmental resource areas.

G. SPILL PREVENTION AND RESPONSE PROCEDURES

The project sponsor shall develop project-specific Spill Prevention and Response Procedures, as specified in section IV of the staff's Procedures. A copy must be filed with the Secretary of the FERC (Secretary) prior to construction and made available in the field on each construction spread. The filing requirement does not apply to projects constructed under the automatic authorization provisions in the FERC's regulations.

H. RESIDENTIAL CONSTRUCTION

For all properties with residences located within 50 feet of construction work areas, project sponsors shall: avoid removal of mature trees and landscaping within the construction work area unless necessary for safe operation of construction equipment, or as specified in landowner agreements; fence the edge of the construction work area for a distance of 100 feet on either side of the residence; and restore all lawn areas and landscaping immediately following clean up operations, or as specified in landowner agreements. If seasonal or other weather conditions prevent compliance with these time frames, maintain and monitor temporary erosion controls (sediment barriers and mulch) until conditions allow completion of restoration.

I. WINTER CONSTRUCTION PLANS

If construction is planned to occur during winter weather conditions, project sponsors shall develop and file a project-specific winter construction plan with the FERC application. This filing requirement does not apply to projects constructed under the automatic authorization provisions of the FERC's regulations.

The plan shall address:

1. winter construction procedures (e.g., snow handling and removal, access road construction and maintenance, soil handling under saturated or frozen conditions, topsoil stripping);

2. stabilization and monitoring procedures if ground conditions will delay restoration until the following spring (e.g., mulching and erosion controls, inspection and reporting, stormwater control during spring thaw conditions); and

3. final restoration procedures (e.g., subsidence and compaction repair, topsoil replacement, seeding).

IV. INSTALLATION

A. APPROVED AREAS OF DISTURBANCE

1. Project-related ground disturbance shall be limited to the construction right-of-way, extra work space areas, pipe storage yards, borrow and disposal areas, access roads, and other areas approved in the FERC's Orders. Any project-related ground disturbing activities outside these areas will require prior Director approval. This requirement does not apply to activities needed to comply with the Plan and Procedures (i.e., slope breakers, energy-dissipating devices, dewatering structures, drain tile system repairs) or minor field realignments and workspace shifts per landowner needs and requirements that do not affect other landowners or sensitive environmental resource areas. All construction or restoration activities outside of authorized areas are subject to all applicable survey and permit requirements, and landowner easement agreements.

2. The construction right-of-way width for a project shall not exceed 75 feet or that described in the FERC application unless otherwise modified by a FERC Order. However, in limited, non-wetland areas, this construction right-of-way width may be expanded by up to 25 feet without Director approval to accommodate full construction right-of-way topsoil segregation and to ensure safe construction where topographic conditions (e.g., side-slopes) or soil limitations require it. Twenty-five feet of extra construction right-of-way width may also be used in limited, non-wetland or non-forested areas for truck turn-arounds where no reasonable alternative access exists.

   Project use of these additional limited areas is subject to landowner or land management agency approval and compliance with all applicable survey and permit requirements. When additional areas are used, each one shall be identified and the need explained in the weekly or biweekly construction reports to the FERC, if required. The following material shall be included in the reports:

   a. the location of each additional area by station number and reference to previously filed alignment sheets, or updated alignment sheets showing the additional areas;

   b. identification of the filing at FERC containing evidence that the additional areas were previously surveyed; and

c. a statement that landowner approval has been obtained and is available in project files.

Prior written approval of the Director is required when the authorized construction right-of-way width would be expanded by more than 25 feet.

B. TOPSOIL SEGREGATION

1. Unless the landowner or land management agency specifically approves otherwise, prevent the mixing of topsoil with subsoil by stripping topsoil from either the full work area or from the trench and subsoil storage area (ditch plus spoil side method) in:

   a. cultivated or rotated croplands, and managed pastures;

   b. residential areas;

   c. hayfields; and

   d. other areas at the landowner's or land managing agency's request.

2. In residential areas, importation of topsoil is an acceptable alternative to topsoil segregation.

3. Where topsoil segregation is required, the project sponsor must:

   a. segregate at least 12 inches of topsoil in deep soils (more than 12 inches of topsoil); and

   b. make every effort to segregate the entire topsoil layer in soils with less than 12 inches of topsoil.

4. Maintain separation of salvaged topsoil and subsoil throughout all construction activities.

5. Segregated topsoil may not be used for padding the pipe, constructing temporary slope breakers or trench plugs, improving or maintaining roads, or as a fill material.

6. Stabilize topsoil piles and minimize loss due to wind and water erosion with use of sediment barriers, mulch, temporary seeding, tackifiers, or functional equivalents, where necessary.

C. DRAIN TILES

1. Mark locations of drain tiles damaged during construction.

2. Probe all drainage tile systems within the area of disturbance to check for damage.

3. Repair damaged drain tiles to their original or better condition. Do not use filter-covered drain tiles unless the local soil conservation authorities and the landowner agree. Use qualified specialists for testing and repairs.

4. For new pipelines in areas where drain tiles exist or are planned, ensure that the depth of cover over the pipeline is sufficient to avoid interference with drain tile systems. For adjacent pipeline loops in agricultural areas, install the new pipeline with at least the same depth of cover as the existing pipeline(s).

D. IRRIGATION

Maintain water flow in crop irrigation systems, unless shutoff is coordinated with affected parties.

E. ROAD CROSSINGS AND ACCESS POINTS

1. Maintain safe and accessible conditions at all road crossings and access points during construction.

2. If crushed stone access pads are used in residential or agricultural areas, place the stone on synthetic fabric to facilitate removal.

3. Minimize the use of tracked equipment on public roadways. Remove any soil or gravel spilled or tracked onto roadways daily or more frequent as necessary to maintain safe road conditions. Repair any damages to roadway surfaces, shoulders, and bar ditches.

F. TEMPORARY EROSION CONTROL

Install temporary erosion controls immediately after initial disturbance of the soil. Temporary erosion controls must be properly maintained throughout construction (on a daily basis) and reinstalled as necessary (such as after backfilling of the trench) until replaced by permanent erosion controls or restoration is complete.

1. Temporary Slope Breakers

   a. Temporary slope breakers are intended to reduce runoff velocity and divert water off the construction right-of-way. Temporary slope

breakers may be constructed of materials such as soil, silt fence, staked hay or straw bales, or sand bags.

b. Install temporary slope breakers on all disturbed areas, as necessary to avoid excessive erosion. Temporary slope breakers must be installed on slopes greater than 5 percent where the base of the slope is less than 50 feet from waterbody, wetland, and road crossings at the following spacing (closer spacing shall be used if necessary):

Slope (%)	Spacing (feet)
5 - 15	300
>15 - 30	200
>30	100

c. Direct the outfall of each temporary slope breaker to a stable, well vegetated area or construct an energy-dissipating device at the end of the slope breaker and off the construction right-of-way.

d. Position the outfall of each temporary slope breaker to prevent sediment discharge into wetlands, waterbodies, or other sensitive environmental resource areas.

2. Temporary Trench Plugs

Temporary trench plugs are intended to segment a continuous open trench prior to backfill.

a. Temporary trench plugs may consist of unexcavated portions of the trench, compacted subsoil, sandbags, or some functional equivalent.

b. Position temporary trench plugs, as necessary, to reduce trenchline erosion and minimize the volume and velocity of trench water flow at the base of slopes.

3. Sediment Barriers

Sediment barriers are intended to stop the flow of sediments and to prevent the deposition of sediments beyond approved workspaces or into sensitive resources.

a. Sediment barriers may be constructed of materials such as silt fence, staked hay or straw bales, compacted earth (e.g., driveable berms across travelways), sand bags, or other appropriate materials.

b. At a minimum, install and maintain temporary sediment barriers across the entire construction right-of-way at the base of slopes greater than 5 percent where the base of the slope is less than 50 feet from a waterbody, wetland, or road crossing until revegetation is successful as defined in this Plan. Leave adequate room between the base of the slope and the sediment barrier to accommodate ponding of water and sediment deposition.

c. Where wetlands or waterbodies are adjacent to and downslope of construction work areas, install sediment barriers along the edge of these areas, as necessary to prevent sediment flow into the wetland or waterbody.

4. Mulch

a. Apply mulch on all slopes (except in cultivated cropland) concurrent with or immediately after seeding, where necessary to stabilize the soil surface and to reduce wind and water erosion. Spread mulch uniformly over the area to cover at least 75 percent of the ground surface at a rate of 2 tons/acre of straw or its equivalent, unless the local soil conservation authority, landowner, or land managing agency approves otherwise in writing.

b. Mulch can consist of weed-free straw or hay, wood fiber hydromulch, erosion control fabric, or some functional equivalent.

c. Mulch all disturbed upland areas (except cultivated cropland) before seeding if:

(1) final grading and installation of permanent erosion control measures will not be completed in an area within 20 days after the trench in that area is backfilled (10 days in residential areas), as required in section V.A.1; or

(2) construction or restoration activity is interrupted for extended periods, such as when seeding cannot be completed due to seeding period restrictions.

d. If mulching before seeding, increase mulch application on all slopes within 100 feet of waterbodies and wetlands to a rate of 3 tons/acre of straw or equivalent.

e. If wood chips are used as mulch, do not use more than 1 ton/acre and add the equivalent of 11 lbs/acre available nitrogen (at least 50 percent of which is slow release).

f. Ensure that mulch is adequately anchored to minimize loss due to wind and water.

g. When anchoring with liquid mulch binders, use rates recommended by the manufacturer. Do not use liquid mulch binders within 100 feet of wetlands or waterbodies, except where the product is certified environmentally non-toxic by the appropriate state or federal agency or independent standards-setting organization.

h. Do not use synthetic monofilament mesh/netted erosion control materials in areas designated as sensitive wildlife habitat, unless the product is specifically designed to minimize harm to wildlife. Anchor erosion control fabric with staples or other appropriate devices.

V. RESTORATION

A. CLEANUP

1. Commence cleanup operations immediately following backfill operations. Complete final grading, topsoil replacement, and installation of permanent erosion control structures within 20 days after backfilling the trench (10 days in residential areas). If seasonal or other weather conditions prevent compliance with these time frames, maintain temporary erosion controls (i.e., temporary slope breakers, sediment barriers, and mulch) until conditions allow completion of cleanup.

   If construction or restoration unexpectedly continues into the winter season when conditions could delay successful decompaction, topsoil replacement, or seeding until the following spring, file with the Secretary for the review and written approval of the Director, a winter construction plan (as specified in section III.I). This filing requirement does not apply to projects constructed under the automatic authorization provisions of the FERC's regulations.

2. A travel lane may be left open temporarily to allow access by construction traffic if the temporary erosion control structures are installed as specified in section IV.F. and inspected and maintained as specified in sections II.B.12 through 14. When access is no longer required the travel lane must be removed and the right-of-way restored.

3. Rock excavated from the trench may be used to backfill the trench only to the top of the existing bedrock profile. Rock that is not returned to the trench shall be considered construction debris, unless approved for use as mulch or for some other use on the construction work areas by the landowner or land managing agency.

4. Remove excess rock from at least the top 12 inches of soil in all cultivated or rotated cropland, managed pastures, hayfields, and residential areas, as well as other areas at the landowner's request. The size, density, and distribution of rock on the construction work area shall be similar to adjacent areas not disturbed by construction. The landowner or land management agency may approve other provisions in writing.

5. Grade the construction right-of-way to restore pre-construction contours and leave the soil in the proper condition for planting.

6. Remove construction debris from all construction work areas unless the landowner or land managing agency approves leaving materials onsite for beneficial reuse, stabilization, or habitat restoration.

7. Remove temporary sediment barriers when replaced by permanent erosion control measures or when revegetation is successful.

B. PERMANENT EROSION CONTROL DEVICES

1. Trench Breakers

a. Trench breakers are intended to slow the flow of subsurface water along the trench. Trench breakers may be constructed of materials such as sand bags or polyurethane foam. Do not use topsoil in trench breakers.

b. An engineer or similarly qualified professional shall determine the need for and spacing of trench breakers. Otherwise, trench breakers shall be installed at the same spacing as and upslope of permanent slope breakers.

c. In agricultural fields and residential areas where slope breakers are not typically required, install trench breakers at the same spacing as if permanent slope breakers were required.

d. At a minimum, install a trench breaker at the base of slopes greater than 5 percent where the base of the slope is less than 50 feet from a waterbody or wetland and where needed to avoid draining a waterbody or wetland. Install trench breakers at wetland boundaries, as specified in the Procedures. Do not install trench breakers within a wetland.

2. Permanent Slope Breakers

a. Permanent slope breakers are intended to reduce runoff velocity, divert water off the construction right-of-way, and prevent sediment deposition into sensitive resources. Permanent slope breakers may be constructed of materials such as soil, stone, or some functional equivalent.

b. Construct and maintain permanent slope breakers in all areas, except cultivated areas and lawns, unless requested by the landowner, using spacing recommendations obtained from the local soil conservation authority or land managing agency.

In the absence of written recommendations, use the following spacing unless closer spacing is necessary to avoid excessive erosion on the construction right-of-way:

Slope (%)	Spacing (feet)
5 - 15	300
>15 - 30	200
>30	100

c. Construct slope breakers to divert surface flow to a stable area without causing water to pool or erode behind the breaker. In the absence of a stable area, construct appropriate energy-dissipating devices at the end of the breaker.

d. Slope breakers may extend slightly (about 4 feet) beyond the edge of the construction right-of-way to effectively drain water off the disturbed area. Where slope breakers extend beyond the edge of the construction right-of-way, they are subject to compliance with all applicable survey requirements.

C. SOIL COMPACTION MITIGATION

1. Test topsoil and subsoil for compaction at regular intervals in agricultural and residential areas disturbed by construction activities. Conduct tests on the same soil type under similar moisture conditions in undisturbed areas to approximate preconstruction conditions. Use penetrometers or other appropriate devices to conduct tests.

2. Plow severely compacted agricultural areas with a paraplow or other deep tillage implement. In areas where topsoil has been segregated, plow the subsoil before replacing the segregated topsoil.

If subsequent construction and cleanup activities result in further compaction, conduct additional tilling.

3. Perform appropriate soil compaction mitigation in severely compacted residential areas.

D. REVEGETATION

1. General

a. The project sponsor is responsible for ensuring successful revegetation of soils disturbed by project-related activities, except as noted in section V.D.1.b.

b. Restore all turf, ornamental shrubs, and specialized landscaping in accordance with the landowner's request, or compensate the landowner. Restoration work must be performed by personnel familiar with local horticultural and turf establishment practices.

2. Soil Additives

Fertilize and add soil pH modifiers in accordance with written recommendations obtained from the local soil conservation authority, land management agencies, or landowner. Incorporate recommended soil pH modifier and fertilizer into the top 2 inches of soil as soon as practicable after application.

3. Seeding Requirements

a. Prepare a seedbed in disturbed areas to a depth of 3 to 4 inches using appropriate equipment to provide a firm seedbed. When hydroseeding, scarify the seedbed to facilitate lodging and germination of seed.

b. Seed disturbed areas in accordance with written recommendations for seed mixes, rates, and dates obtained from the local soil conservation authority or the request of the landowner or land management agency. Seeding is not required in cultivated croplands unless requested by the landowner.

c. Perform seeding of permanent vegetation within the recommended seeding dates. If seeding cannot be done within those dates, use appropriate temporary erosion control measures discussed in section IV.F and perform seeding of permanent vegetation at the beginning of the next recommended seeding season. Dormant seeding or temporary

seeding of annual species may also be used, if necessary, to establish cover, as approved by the Environmental Inspector. Lawns may be seeded on a schedule established with the landowner.

d. In the absence of written recommendations from the local soil conservation authorities, seed all disturbed soils within 6 working days of final grading, weather and soil conditions permitting, subject to the specifications in section V.D.3.a through V.D.3.c.

e. Base seeding rates on Pure Live Seed. Use seed within 12 months of seed testing.

f. Treat legume seed with an inoculant specific to the species using the manufacturer's recommended rate of inoculant appropriate for the seeding method (broadcast, drill, or hydro).

g. In the absence of written recommendations from the local soil conservation authorities, landowner, or land managing agency to the contrary, a seed drill equipped with a cultipacker is preferred for seed application.

Broadcast or hydroseeding can be used in lieu of drilling at double the recommended seeding rates. Where seed is broadcast, firm the seedbed with a cultipacker or roller after seeding. In rocky soils or where site conditions may limit the effectiveness of this equipment, other alternatives may be appropriate (e.g., use of a chain drag) to lightly cover seed after application, as approved by the Environmental Inspector.

VI. OFF-ROAD VEHICLE CONTROL

To each owner or manager of forested lands, offer to install and maintain measures to control unauthorized vehicle access to the right-of-way. These measures may include:

A. signs;

B. fences with locking gates;

C. slash and timber barriers, pipe barriers, or a line of boulders across the right-of-way; and

D. conifers or other appropriate trees or shrubs across the right-of-way.

VII. POST-CONSTRUCTION ACTIVITIES AND REPORTING

A. MONITORING AND MAINTENANCE

1. Conduct follow-up inspections of all disturbed areas, as necessary, to determine the success of revegetation and address landowner concerns. At a minimum, conduct inspections after the first and second growing seasons.

2. Revegetation in non-agricultural areas shall be considered successful if upon visual survey the density and cover of non-nuisance vegetation are similar in density and cover to adjacent undisturbed lands. In agricultural areas, revegetation shall be considered successful when upon visual survey, crop growth and vigor are similar to adjacent undisturbed portions of the same field, unless the easement agreement specifies otherwise.

   Continue revegetation efforts until revegetation is successful.

3. Monitor and correct problems with drainage and irrigation systems resulting from pipeline construction in agricultural areas until restoration is successful.

4. Restoration shall be considered successful if the right-of-way surface condition is similar to adjacent undisturbed lands, construction debris is removed (unless otherwise approved by the landowner or land managing agency per section V.A.6), revegetation is successful, and proper drainage has been restored.

5. Routine vegetation mowing or clearing over the full width of the permanent right-of-way in uplands shall not be done more frequently than every 3 years. However, to facilitate periodic corrosion/leak surveys, a corridor not exceeding 10 feet in width centered on the pipeline may be cleared at a frequency necessary to maintain the 10-foot corridor in an herbaceous state. In no case shall routine vegetation mowing or clearing occur during the migratory bird nesting season between April 15 and August 1 of any year unless specifically approved in writing by the responsible land management agency or the U.S. Fish and Wildlife Service.

6. Efforts to control unauthorized off-road vehicle use, in cooperation with the landowner, shall continue throughout the life of the project. Maintain signs, gates, and permanent access roads as necessary.

B. REPORTING

1. The project sponsor shall maintain records that identify by milepost:

   a. method of application, application rate, and type of fertilizer, pH modifying agent, seed, and mulch used;

   b. acreage treated;

   c. dates of backfilling and seeding;

   d. names of landowners requesting special seeding treatment and a description of the follow-up actions;

   e. the location of any subsurface drainage repairs or improvements made during restoration; and

   f. any problem areas and how they were addressed.

2. The project sponsor shall file with the Secretary quarterly activity reports documenting the results of follow-up inspections required by section VII.A.1; any problem areas, including those identified by the landowner; and corrective actions taken for at least 2 years following construction.

   The requirement to file quarterly activity reports with the Secretary does not apply to projects constructed under the automatic authorization, prior notice, or advanced notice provisions in the FERC's regulations.

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1
APPENDIX 1D

Wetland and Waterbody Construction Mitigation Procedures

WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES

MAY 2013 VERSION

WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES

TABLE OF CONTENTS

I. APPLICABILITY 1

II. PRECONSTRUCTION FILING 2

III. ENVIRONMENTAL INSPECTORS 3

IV. PRECONSTRUCTION PLANNING 3

V. WATERBODY CROSSINGS 5
- A. NOTIFICATION PROCEDURES AND PERMITS 5
- B. INSTALLATION 5
  1. Time Window for Construction 5
  2. Extra Work Areas 5
  3. General Crossing Procedures 6
  4. Spoil Pile Placement and Control 7
  5. Equipment Bridges 7
  6. Dry-Ditch Crossing Methods 8
  7. Crossings of Minor Waterbodies 9
  8. Crossings of Intermediate Waterbodies 10
  9. Crossings of Major Waterbodies 10
  10. Temporary Erosion and Sediment Control 10
  11. Trench Dewatering 11
- C. RESTORATION 11
- D. POST-CONSTRUCTION MAINTENANCE 12

VI. WETLAND CROSSINGS 13
- A. GENERAL 13
- B. INSTALLATION 14
  1. Extra Work Areas and Access Roads 14
  2. Crossing Procedures 15
  3. Temporary Sediment Control 16
  4. Trench Dewatering 17
- C. RESTORATION 17
- D. POST-CONSTRUCTION MAINTENANCE AND REPORTING 18

VII. HYDROSTATIC TESTING 19
- A. NOTIFICATION PROCEDURES AND PERMITS 19
- B. GENERAL 19
- C. INTAKE SOURCE AND RATE 19
- D. DISCHARGE LOCATION, METHOD, AND RATE 20

WETLAND AND WATERBODY
CONSTRUCTION AND MITIGATION PROCEDURES (PROCEDURES)

I. APPLICABILITY

A. The intent of these Procedures is to assist project sponsors by identifying baseline mitigation measures for minimizing the extent and duration of project-related disturbance on wetlands and waterbodies. Project sponsors shall specify in their applications for a new FERC authorization, and in prior notice and advance notice filings, any individual measures in these Procedures they consider unnecessary, technically infeasible, or unsuitable due to local conditions and fully describe any alternative measures they would use. Project sponsors shall also explain how those alternative measures would achieve a comparable level of mitigation.

Once a project is authorized, project sponsors can request further changes as variances to the measures in these Procedures (or the applicant's approved procedures). The Director of the Office of Energy Projects (Director) will consider approval of variances upon the project sponsor's written request, if the Director agrees that a variance:

1. provides equal or better environmental protection;

2. is necessary because a portion of these Procedures is infeasible or unworkable based on project-specific conditions; or

3. is specifically required in writing by another federal, state, or Native American land management agency for the portion of the project on its land or under its jurisdiction.

Sponsors of projects planned for construction under the automatic authorization provisions in the FERC's regulations must receive written approval for any variances in advance of construction.

Project-related impacts on non-wetland areas are addressed in the staff's Upland Erosion Control, Revegetation, and Maintenance Plan (Plan).

B. DEFINITIONS

1. "Waterbody" includes any natural or artificial stream, river, or drainage with perceptible flow at the time of crossing, and other permanent waterbodies such as ponds and lakes:

   a. "minor waterbody" includes all waterbodies less than or equal to 10 feet wide at the water's edge at the time of crossing;

   b. "intermediate waterbody" includes all waterbodies greater than 10 feet wide but less than or equal to 100 feet wide at the water's edge at the time of crossing; and

   c. "major waterbody" includes all waterbodies greater than 100 feet wide at the water's edge at the time of crossing.

2. "Wetland" includes any area that is not in actively cultivated or rotated cropland and that satisfies the requirements of the current federal methodology for identifying and delineating wetlands.

II. PRECONSTRUCTION FILING

A. The following information must be filed with the Secretary of the FERC (Secretary) prior to the beginning of construction, for the review and written approval by the Director:

1. site-specific justifications for extra work areas that would be closer than 50 feet from a waterbody or wetland; and

2. site-specific justifications for the use of a construction right-of-way greater than 75-feet-wide in wetlands.

B. The following information must be filed with the Secretary prior to the beginning of construction. These filing requirements do not apply to projects constructed under the automatic authorization provisions in the FERC's regulations:

1. Spill Prevention and Response Procedures specified in section IV.A;

2. a schedule identifying when trenching or blasting will occur within each waterbody greater than 10 feet wide, within any designated coldwater fishery, and within any waterbody identified as habitat for federally-listed threatened or endangered species. The project sponsor will revise the schedule as necessary to provide FERC staff at least 14 days advance notice. Changes within this last 14-day period must provide for at least 48 hours advance notice;

3. plans for horizontal directional drills (HDD) under wetlands or waterbodies, specified in section V.B.6.d;

4. site-specific plans for major waterbody crossings, described in section V.B.9;

5. a wetland delineation report as described in section VI.A.1, if applicable; and

6. the hydrostatic testing information specified in section VII.B.3.

III. ENVIRONMENTAL INSPECTORS

A. At least one Environmental Inspector having knowledge of the wetland and waterbody conditions in the project area is required for each construction spread. The number and experience of Environmental Inspectors assigned to each construction spread shall be appropriate for the length of the construction spread and the number/significance of resources affected.

B. The Environmental Inspector's responsibilities are outlined in the Upland Erosion Control, Revegetation, and Maintenance Plan (Plan).

IV. PRECONSTRUCTION PLANNING

A. The project sponsor shall develop project-specific Spill Prevention and Response Procedures that meet applicable requirements of state and federal agencies. A copy must be filed with the Secretary prior to construction and made available in the field on each construction spread. This filing requirement does not apply to projects constructed under the automatic authorization provisions in the FERC's regulations.

1. It shall be the responsibility of the project sponsor and its contractors to structure their operations in a manner that reduces the risk of spills or the accidental exposure of fuels or hazardous materials to waterbodies or wetlands. The project sponsor and its contractors must, at a minimum, ensure that:

a. all employees handling fuels and other hazardous materials are properly trained;

b. all equipment is in good operating order and inspected on a regular basis;

c. fuel trucks transporting fuel to on-site equipment travel only on approved access roads;

d. all equipment is parked overnight and/or fueled at least 100 feet from a waterbody or in an upland area at least 100 feet from a wetland boundary. These activities can occur closer only if the Environmental Inspector determines that there is no reasonable alternative, and the

project sponsor and its contractors have taken appropriate steps (including secondary containment structures) to prevent spills and provide for prompt cleanup in the event of a spill;

e. hazardous materials, including chemicals, fuels, and lubricating oils, are not stored within 100 feet of a wetland, waterbody, or designated municipal watershed area, unless the location is designated for such use by an appropriate governmental authority. This applies to storage of these materials and does not apply to normal operation or use of equipment in these areas;

f. concrete coating activities are not performed within 100 feet of a wetland or waterbody boundary, unless the location is an existing industrial site designated for such use. These activities can occur closer only if the Environmental Inspector determines that there is no reasonable alternative, and the project sponsor and its contractors have taken appropriate steps (including secondary containment structures) to prevent spills and provide for prompt cleanup in the event of a spill;

g. pumps operating within 100 feet of a waterbody or wetland boundary utilize appropriate secondary containment systems to prevent spills; and

h. bulk storage of hazardous materials, including chemicals, fuels, and lubricating oils have appropriate secondary containment systems to prevent spills.

2. The project sponsor and its contractors must structure their operations in a manner that provides for the prompt and effective cleanup of spills of fuel and other hazardous materials. At a minimum, the project sponsor and its contractors must:

a. ensure that each construction crew (including cleanup crews) has on hand sufficient supplies of absorbent and barrier materials to allow the rapid containment and recovery of spilled materials and knows the procedure for reporting spills and unanticipated discoveries of contamination;

b. ensure that each construction crew has on hand sufficient tools and material to stop leaks;

c. know the contact names and telephone numbers for all local, state, and federal agencies (including, if necessary, the U. S. Coast Guard and the National Response Center) that must be notified of a spill; and

d. follow the requirements of those agencies in cleaning up the spill, in excavating and disposing of soils or other materials contaminated by a spill, and in collecting and disposing of waste generated during spill cleanup.

B. AGENCY COORDINATION

The project sponsor must coordinate with the appropriate local, state, and federal agencies as outlined in these Procedures and in the FERC's Orders.

V. WATERBODY CROSSINGS

A. NOTIFICATION PROCEDURES AND PERMITS

1. Apply to the U.S. Army Corps of Engineers (COE), or its delegated agency, for the appropriate wetland and waterbody crossing permits.

2. Provide written notification to authorities responsible for potable surface water supply intakes located within 3 miles downstream of the crossing at least 1 week before beginning work in the waterbody, or as otherwise specified by that authority.

3. Apply for state-issued waterbody crossing permits and obtain individual or generic section 401 water quality certification or waiver.

4. Notify appropriate federal and state authorities at least 48 hours before beginning trenching or blasting within the waterbody, or as specified in applicable permits.

B. INSTALLATION

1. Time Window for Construction

Unless expressly permitted or further restricted by the appropriate federal or state agency in writing on a site-specific basis, instream work, except that required to install or remove equipment bridges, must occur during the following time windows:

a. coldwater fisheries - June 1 through September 30; and

b. coolwater and warmwater fisheries - June 1 through November 30.

2. Extra Work Areas

a. Locate all extra work areas (such as staging areas and additional spoil storage areas) at least 50 feet away from water's edge, except where

the adjacent upland consists of cultivated or rotated cropland or other disturbed land.

b. The project sponsor shall file with the Secretary for review and written approval by the Director, site-specific justification for each extra work area with a less than 50-foot setback from the water's edge, except where the adjacent upland consists of cultivated or rotated cropland or other disturbed land. The justification must specify the conditions that will not permit a 50-foot setback and measures to ensure the waterbody is adequately protected.

c. Limit the size of extra work areas to the minimum needed to construct the waterbody crossing.

3. General Crossing Procedures

a. Comply with the COE, or its delegated agency, permit terms and conditions.

b. Construct crossings as close to perpendicular to the axis of the waterbody channel as engineering and routing conditions permit.

c. Where pipelines parallel a waterbody, maintain at least 15 feet of undisturbed vegetation between the waterbody (and any adjacent wetland) and the construction right-of-way, except where maintaining this offset will result in greater environmental impact.

d. Where waterbodies meander or have multiple channels, route the pipeline to minimize the number of waterbody crossings.

e. Maintain adequate waterbody flow rates to protect aquatic life, and prevent the interruption of existing downstream uses.

f. Waterbody buffers (e.g., extra work area setbacks, refueling restrictions) must be clearly marked in the field with signs and/or highly visible flagging until construction-related ground disturbing activities are complete.

g. Crossing of waterbodies when they are dry or frozen and not flowing may proceed using standard upland construction techniques in accordance with the Plan, provided that the Environmental Inspector verifies that water is unlikely to flow between initial disturbance and final stabilization of the feature. In the event of perceptible flow, the project sponsor must comply with all applicable Procedure requirements for "waterbodies" as defined in section I.B.1.

4. Spoil Pile Placement and Control

   a. All spoil from minor and intermediate waterbody crossings, and upland spoil from major waterbody crossings, must be placed in the construction right-of-way at least 10 feet from the water's edge or in additional extra work areas as described in section V.B.2.

   b. Use sediment barriers to prevent the flow of spoil or silt-laden water into any waterbody.

5. Equipment Bridges

   a. Only clearing equipment and equipment necessary for installation of equipment bridges may cross waterbodies prior to bridge installation. Limit the number of such crossings of each waterbody to one per piece of clearing equipment.

   b. Construct and maintain equipment bridges to allow unrestricted flow and to prevent soil from entering the waterbody. Examples of such bridges include:

      (1) equipment pads and culvert(s);
      (2) equipment pads or railroad car bridges without culverts;
      (3) clean rock fill and culvert(s); and
      (4) flexi-float or portable bridges.

      Additional options for equipment bridges may be utilized that achieve the performance objectives noted above. Do not use soil to construct or stabilize equipment bridges.

   c. Design and maintain each equipment bridge to withstand and pass the highest flow expected to occur while the bridge is in place. Align culverts to prevent bank erosion or streambed scour. If necessary, install energy dissipating devices downstream of the culverts.

   d. Design and maintain equipment bridges to prevent soil from entering the waterbody.

   e. Remove temporary equipment bridges as soon as practicable after permanent seeding.

   f. If there will be more than 1 month between final cleanup and the beginning of permanent seeding and reasonable alternative access to the right-of-way is available, remove temporary equipment bridges as soon as practicable after final cleanup.

g. Obtain any necessary approval from the COE, or the appropriate state agency for permanent bridges.

6. Dry-Ditch Crossing Methods

a. Unless approved otherwise by the appropriate federal or state agency, install the pipeline using one of the dry-ditch methods outlined below for crossings of waterbodies up to 30 feet wide (at the water's edge at the time of construction) that are state-designated as either coldwater or significant coolwater or warmwater fisheries, or federally-designated as critical habitat.

b. Dam and Pump

(1) The dam-and-pump method may be used without prior approval for crossings of waterbodies where pumps can adequately transfer streamflow volumes around the work area, and there are no concerns about sensitive species passage.

(2) Implementation of the dam-and-pump crossing method must meet the following performance criteria:

(i) use sufficient pumps, including on-site backup pumps, to maintain downstream flows;
(ii) construct dams with materials that prevent sediment and other pollutants from entering the waterbody (e.g., sandbags or clean gravel with plastic liner);
(iii) screen pump intakes to minimize entrainment of fish;
(iv) prevent streambed scour at pump discharge; and
(v) continuously monitor the dam and pumps to ensure proper operation throughout the waterbody crossing.

c. Flume Crossing

The flume crossing method requires implementation of the following steps:

(1) install flume pipe after blasting (if necessary), but before any trenching;

(2) use sand bag or sand bag and plastic sheeting diversion structure or equivalent to develop an effective seal and to divert stream flow through the flume pipe (some modifications to the stream bottom may be required to achieve an effective seal);

(3) properly align flume pipe(s) to prevent bank erosion and streambed scour;

(4) do not remove flume pipe during trenching, pipelaying, or backfilling activities, or initial streambed restoration efforts; and

(5) remove all flume pipes and dams that are not also part of the equipment bridge as soon as final cleanup of the stream bed and bank is complete.

d. Horizontal Directional Drill

For each waterbody or wetland that would be crossed using the HDD method, file with the Secretary for the review and written approval by the Director, a plan that includes:

(1) site-specific construction diagrams that show the location of mud pits, pipe assembly areas, and all areas to be disturbed or cleared for construction;

(2) justification that disturbed areas are limited to the minimum needed to construct the crossing;

(3) identification of any aboveground disturbance or clearing between the HDD entry and exit workspaces during construction;

(4) a description of how an inadvertent release of drilling mud would be contained and cleaned up; and

(5) a contingency plan for crossing the waterbody or wetland in the event the HDD is unsuccessful and how the abandoned drill hole would be sealed, if necessary.

The requirement to file HDD plans does not apply to projects constructed under the automatic authorization provisions in the FERC's regulations.

7. Crossings of Minor Waterbodies

Where a dry-ditch crossing is not required, minor waterbodies may be crossed using the open-cut crossing method, with the following restrictions:

a. except for blasting and other rock breaking measures, complete instream construction activities (including trenching, pipe installation, backfill, and restoration of the streambed contours) within 24 hours.

Streambanks and unconsolidated streambeds may require additional restoration after this period;

b. limit use of equipment operating in the waterbody to that needed to construct the crossing; and

c. equipment bridges are not required at minor waterbodies that do not have a state-designated fishery classification or protected status (e.g., agricultural or intermittent drainage ditches). However, if an equipment bridge is used it must be constructed as described in section V.B.5.

8. Crossings of Intermediate Waterbodies

Where a dry-ditch crossing is not required, intermediate waterbodies may be crossed using the open-cut crossing method, with the following restrictions:

a. complete instream construction activities (not including blasting and other rock breaking measures) within 48 hours, unless site-specific conditions make completion within 48 hours infeasible;

b. limit use of equipment operating in the waterbody to that needed to construct the crossing; and

c. all other construction equipment must cross on an equipment bridge as specified in section V.B.5.

9. Crossings of Major Waterbodies

Before construction, the project sponsor shall file with the Secretary for the review and written approval by the Director a detailed, site-specific construction plan and scaled drawings identifying all areas to be disturbed by construction for each major waterbody crossing (the scaled drawings are not required for any offshore portions of pipeline projects). This plan must be developed in consultation with the appropriate state and federal agencies and shall include extra work areas, spoil storage areas, sediment control structures, etc., as well as mitigation for navigational issues. The requirement to file major waterbody crossing plans does not apply to projects constructed under the automatic authorization provisions of the FERC's regulations.

The Environmental Inspector may adjust the final placement of the erosion and sediment control structures in the field to maximize effectiveness.

10. Temporary Erosion and Sediment Control

Install sediment barriers (as defined in section IV.F.3.a of the Plan) immediately after initial disturbance of the waterbody or adjacent upland.

Sediment barriers must be properly maintained throughout construction and reinstalled as necessary (such as after backfilling of the trench) until replaced by permanent erosion controls or restoration of adjacent upland areas is complete. Temporary erosion and sediment control measures are addressed in more detail in the Plan; however, the following specific measures must be implemented at stream crossings:

a. install sediment barriers across the entire construction right-of-way at all waterbody crossings, where necessary to prevent the flow of sediments into the waterbody. Removable sediment barriers (or driveable berms) must be installed across the travel lane. These removable sediment barriers can be removed during the construction day, but must be re-installed after construction has stopped for the day and/or when heavy precipitation is imminent;

b. where waterbodies are adjacent to the construction right-of-way and the right-of-way slopes toward the waterbody, install sediment barriers along the edge of the construction right-of-way as necessary to contain spoil within the construction right-of-way and prevent sediment flow into the waterbody; and

c. use temporary trench plugs at all waterbody crossings, as necessary, to prevent diversion of water into upland portions of the pipeline trench and to keep any accumulated trench water out of the waterbody.

11. Trench Dewatering

Dewater the trench (either on or off the construction right-of-way) in a manner that does not cause erosion and does not result in silt-laden water flowing into any waterbody. Remove the dewatering structures as soon as practicable after the completion of dewatering activities.

C. RESTORATION

1. Use clean gravel or native cobbles for the upper 1 foot of trench backfill in all waterbodies that contain coldwater fisheries.

2. For open-cut crossings, stabilize waterbody banks and install temporary sediment barriers within 24 hours of completing instream construction activities. For dry-ditch crossings, complete streambed and bank stabilization before returning flow to the waterbody channel.

3. Return all waterbody banks to preconstruction contours or to a stable angle of repose as approved by the Environmental Inspector.

4. Install erosion control fabric or a functional equivalent on waterbody banks at the time of final bank recontouring. Do not use synthetic monofilament

mesh/netted erosion control materials in areas designated as sensitive wildlife habitat unless the product is specifically designed to minimize harm to wildlife. Anchor erosion control fabric with staples or other appropriate devices.

5. Application of riprap for bank stabilization must comply with COE, or its delegated agency, permit terms and conditions.

6. Unless otherwise specified by state permit, limit the use of riprap to areas where flow conditions preclude effective vegetative stabilization techniques such as seeding and erosion control fabric.

7. Revegetate disturbed riparian areas with native species of conservation grasses, legumes, and woody species, similar in density to adjacent undisturbed lands.

8. Install a permanent slope breaker across the construction right-of-way at the base of slopes greater than 5 percent that are less than 50 feet from the waterbody, or as needed to prevent sediment transport into the waterbody. In addition, install sediment barriers as outlined in the Plan.

   In some areas, with the approval of the Environmental Inspector, an earthen berm may be suitable as a sediment barrier adjacent to the waterbody.

9. Sections V.C.3 through V.C.7 above also apply to those perennial or intermittent streams not flowing at the time of construction.

D. POST-CONSTRUCTION MAINTENANCE

1. Limit routine vegetation mowing or clearing adjacent to waterbodies to allow a riparian strip at least 25 feet wide, as measured from the waterbody's mean high water mark, to permanently revegetate with native plant species across the entire construction right-of-way. However, to facilitate periodic corrosion/leak surveys, a corridor centered on the pipeline and up to 10 feet wide may be cleared at a frequency necessary to maintain the 10-foot corridor in an herbaceous state. In addition, trees that are located within 15 feet of the pipeline that have roots that could compromise the integrity of the pipeline coating may be cut and removed from the permanent right-of-way. Do not conduct any routine vegetation mowing or clearing in riparian areas that are between HDD entry and exit points.

2. Do not use herbicides or pesticides in or within 100 feet of a waterbody except as allowed by the appropriate land management or state agency.

3. Time of year restrictions specified in section VII.A.5 of the Plan (April 15 – August 1 of any year) apply to routine mowing and clearing of riparian areas.

VI. WETLAND CROSSINGS

A. GENERAL

1. The project sponsor shall conduct a wetland delineation using the current federal methodology and file a wetland delineation report with the Secretary before construction. The requirement to file a wetland delineation report does not apply to projects constructed under the automatic authorization provisions in the FERC's regulations.

   This report shall identify:

   a. by milepost all wetlands that would be affected;

   b. the National Wetlands Inventory (NWI) classification for each wetland;

   c. the crossing length of each wetland in feet; and

   d. the area of permanent and temporary disturbance that would occur in each wetland by NWI classification type.

   The requirements outlined in this section do not apply to wetlands in actively cultivated or rotated cropland. Standard upland protective measures, including workspace and topsoiling requirements, apply to these agricultural wetlands.

2. Route the pipeline to avoid wetland areas to the maximum extent possible. If a wetland cannot be avoided or crossed by following an existing right-of-way, route the new pipeline in a manner that minimizes disturbance to wetlands. Where looping an existing pipeline, overlap the existing pipeline right-of-way with the new construction right-of-way. In addition, locate the loop line no more than 25 feet away from the existing pipeline unless site-specific constraints would adversely affect the stability of the existing pipeline.

3. Limit the width of the construction right-of-way to 75 feet or less. Prior written approval of the Director is required where topographic conditions or soil limitations require that the construction right-of-way width within the boundaries of a federally delineated wetland be expanded beyond 75 feet. Early in the planning process the project sponsor is encouraged to identify site-specific areas where excessively wide trenches could occur and/or where spoil piles could be difficult to maintain because existing soils lack adequate unconfined compressive strength.

4. Wetland boundaries and buffers must be clearly marked in the field with signs and/or highly visible flagging until construction-related ground disturbing activities are complete.

5. Implement the measures of sections V and VI in the event a waterbody crossing is located within or adjacent to a wetland crossing. If all measures of sections V and VI cannot be met, the project sponsor must file with the Secretary a site-specific crossing plan for review and written approval by the Director before construction. This crossing plan shall address at a minimum:

   a. spoil control;

   b. equipment bridges;

   c. restoration of waterbody banks and wetland hydrology;

   d. timing of the waterbody crossing;

   e. method of crossing; and

   f. size and location of all extra work areas.

6. Do not locate aboveground facilities in any wetland, except where the location of such facilities outside of wetlands would prohibit compliance with U.S. Department of Transportation regulations.

B. INSTALLATION

1. Extra Work Areas and Access Roads

   a. Locate all extra work areas (such as staging areas and additional spoil storage areas) at least 50 feet away from wetland boundaries, except where the adjacent upland consists of cultivated or rotated cropland or other disturbed land.

   b. The project sponsor shall file with the Secretary for review and written approval by the Director, site-specific justification for each extra work area with a less than 50-foot setback from wetland boundaries, except where adjacent upland consists of cultivated or rotated cropland or other disturbed land. The justification must specify the site-specific conditions that will not permit a 50-foot setback and measures to ensure the wetland is adequately protected.

   c. The construction right-of-way may be used for access when the wetland soil is firm enough to avoid rutting or the construction right-of-way has been appropriately stabilized to avoid rutting (e.g., with timber riprap, prefabricated equipment mats, or terra mats).

      In wetlands that cannot be appropriately stabilized, all construction equipment other than that needed to install the wetland crossing shall

use access roads located in upland areas. Where access roads in upland areas do not provide reasonable access, limit all other construction equipment to one pass through the wetland using the construction right-of-way.

d. The only access roads, other than the construction right-of-way, that can be used in wetlands are those existing roads that can be used with no modifications or improvements, other than routine repair, and no impact on the wetland.

2. Crossing Procedures

a. Comply with COE, or its delegated agency, permit terms and conditions.

b. Assemble the pipeline in an upland area unless the wetland is dry enough to adequately support skids and pipe.

c. Use “push-pull” or “float” techniques to place the pipe in the trench where water and other site conditions allow.

d. Minimize the length of time that topsoil is segregated and the trench is open. Do not trench the wetland until the pipeline is assembled and ready for lowering in.

e. Limit construction equipment operating in wetland areas to that needed to clear the construction right-of-way, dig the trench, fabricate and install the pipeline, backfill the trench, and restore the construction right-of-way.

f. Cut vegetation just above ground level, leaving existing root systems in place, and remove it from the wetland for disposal.

The project sponsor can burn woody debris in wetlands, if approved by the COE and in accordance with state and local regulations, ensuring that all remaining woody debris is removed for disposal.

g. Limit pulling of tree stumps and grading activities to directly over the trenchline. Do not grade or remove stumps or root systems from the rest of the construction right-of-way in wetlands unless the Chief Inspector and Environmental Inspector determine that safety-related construction constraints require grading or the removal of tree stumps from under the working side of the construction right-of-way.

h. Segregate the top 1 foot of topsoil from the area disturbed by trenching, except in areas where standing water is present or soils are

saturated. Immediately after backfilling is complete, restore the segregated topsoil to its original location.

i. Do not use rock, soil imported from outside the wetland, tree stumps, or brush riprap to support equipment on the construction right-of-way.

j. If standing water or saturated soils are present, or if construction equipment causes ruts or mixing of the topsoil and subsoil in wetlands, use low-ground-weight construction equipment, or operate normal equipment on timber riprap, prefabricated equipment mats, or terra mats.

k. Remove all project-related material used to support equipment on the construction right-of-way upon completion of construction.

3. Temporary Sediment Control

Install sediment barriers (as defined in section IV.F.3.a of the Plan) immediately after initial disturbance of the wetland or adjacent upland. Sediment barriers must be properly maintained throughout construction and reinstalled as necessary (such as after backfilling of the trench). Except as noted below in section VI.B.3.c, maintain sediment barriers until replaced by permanent erosion controls or restoration of adjacent upland areas is complete. Temporary erosion and sediment control measures are addressed in more detail in the Plan.

a. Install sediment barriers across the entire construction right-of-way immediately upslope of the wetland boundary at all wetland crossings where necessary to prevent sediment flow into the wetland.

b. Where wetlands are adjacent to the construction right-of-way and the right-of-way slopes toward the wetland, install sediment barriers along the edge of the construction right-of-way as necessary to contain spoil within the construction right-of-way and prevent sediment flow into the wetland.

c. Install sediment barriers along the edge of the construction right-of-way as necessary to contain spoil and sediment within the construction right-of-way through wetlands. Remove these sediment barriers during right-of-way cleanup.

4. Trench Dewatering

Dewater the trench (either on or off the construction right-of-way) in a manner that does not cause erosion and does not result in silt-laden water flowing into any wetland. Remove the dewatering structures as soon as practicable after the completion of dewatering activities.

C. RESTORATION

1. Where the pipeline trench may drain a wetland, construct trench breakers at the wetland boundaries and/or seal the trench bottom as necessary to maintain the original wetland hydrology.

2. Restore pre-construction wetland contours to maintain the original wetland hydrology.

3. For each wetland crossed, install a trench breaker at the base of slopes near the boundary between the wetland and adjacent upland areas. Install a permanent slope breaker across the construction right-of-way at the base of slopes greater than 5 percent where the base of the slope is less than 50 feet from the wetland, or as needed to prevent sediment transport into the wetland. In addition, install sediment barriers as outlined in the Plan. In some areas, with the approval of the Environmental Inspector, an earthen berm may be suitable as a sediment barrier adjacent to the wetland.

4. Do not use fertilizer, lime, or mulch unless required in writing by the appropriate federal or state agency.

5. Consult with the appropriate federal or state agencies to develop a project-specific wetland restoration plan. The restoration plan shall include measures for re-establishing herbaceous and/or woody species, controlling the invasion and spread of invasive species and noxious weeds (e.g., purple loosestrife and phragmites), and monitoring the success of the revegetation and weed control efforts. Provide this plan to the FERC staff upon request.

6. Until a project-specific wetland restoration plan is developed and/or implemented, temporarily revegetate the construction right-of-way with annual ryegrass at a rate of 40 pounds/acre (unless standing water is present).

7. Ensure that all disturbed areas successfully revegetate with wetland herbaceous and/or woody plant species.

8. Remove temporary sediment barriers located at the boundary between wetland and adjacent upland areas after revegetation and stabilization of adjacent upland areas are judged to be successful as specified in section VII.A.4 of the Plan.

D. POST-CONSTRUCTION MAINTENANCE AND REPORTING

1. Do not conduct routine vegetation mowing or clearing over the full width of the permanent right-of-way in wetlands. However, to facilitate periodic corrosion/leak surveys, a corridor centered on the pipeline and up to 10 feet wide may be cleared at a frequency necessary to maintain the 10-foot corridor in an herbaceous state. In addition, trees within 15 feet of the pipeline with roots that could compromise the integrity of pipeline coating may be selectively cut and removed from the permanent right-of-way. Do not conduct any routine vegetation mowing or clearing in wetlands that are between HDD entry and exit points.

2. Do not use herbicides or pesticides in or within 100 feet of a wetland, except as allowed by the appropriate federal or state agency.

3. Time of year restrictions specified in section VII.A.5 of the Plan (April 15 – August 1 of any year) apply to routine mowing and clearing of wetland areas.

4. Monitor and record the success of wetland revegetation annually until wetland revegetation is successful.

5. Wetland revegetation shall be considered successful if all of the following criteria are satisfied:

   a. the affected wetland satisfies the current federal definition for a wetland (i.e., soils, hydrology, and vegetation);

   b. vegetation is at least 80 percent of either the cover documented for the wetland prior to construction, or at least 80 percent of the cover in adjacent wetland areas that were not disturbed by construction;

   c. if natural rather than active revegetation was used, the plant species composition is consistent with early successional wetland plant communities in the affected ecoregion; and

   d. invasive species and noxious weeds are absent, unless they are abundant in adjacent areas that were not disturbed by construction.

6. Within 3 years after construction, file a report with the Secretary identifying the status of the wetland revegetation efforts and documenting success as defined in section VI.D.5, above. The requirement to file wetland restoration reports with the Secretary does not apply to projects constructed under the automatic authorization, prior notice, or advance notice provisions in the FERC's regulations.

   For any wetland where revegetation is not successful at the end of 3 years after construction, develop and implement (in consultation with a

professional wetland ecologist) a remedial revegetation plan to actively revegetate wetlands. Continue revegetation efforts and file a report annually documenting progress in these wetlands until wetland revegetation is successful.

VII. HYDROSTATIC TESTING

A. NOTIFICATION PROCEDURES AND PERMITS

1. Apply for state-issued water withdrawal permits, as required.

2. Apply for National Pollutant Discharge Elimination System (NPDES) or state-issued discharge permits, as required.

3. Notify appropriate state agencies of intent to use specific sources at least 48 hours before testing activities unless they waive this requirement in writing.

B. GENERAL

1. Perform 100 percent radiographic inspection of all pipeline section welds or hydrotest the pipeline sections, before installation under waterbodies or wetlands.

2. If pumps used for hydrostatic testing are within 100 feet of any waterbody or wetland, address secondary containment and refueling of these pumps in the project's Spill Prevention and Response Procedures.

3. The project sponsor shall file with the Secretary before construction a list identifying the location of all waterbodies proposed for use as a hydrostatic test water source or discharge location. This filing requirement does not apply to projects constructed under the automatic authorization provisions of the FERC's regulations.

C. INTAKE SOURCE AND RATE

1. Screen the intake hose to minimize the potential for entrainment of fish.

2. Do not use state-designated exceptional value waters, waterbodies which provide habitat for federally listed threatened or endangered species, or waterbodies designated as public water supplies, unless appropriate federal, state, and/or local permitting agencies grant written permission.

3. Maintain adequate flow rates to protect aquatic life, provide for all waterbody uses, and provide for downstream withdrawals of water by existing users.

4. Locate hydrostatic test manifolds outside wetlands and riparian areas to the maximum extent practicable.

D. DISCHARGE LOCATION, METHOD, AND RATE

1. Regulate discharge rate, use energy dissipation device(s), and install sediment barriers, as necessary, to prevent erosion, streambed scour, suspension of sediments, or excessive streamflow.

2. Do not discharge into state-designated exceptional value waters, waterbodies which provide habitat for federally listed threatened or endangered species, or waterbodies designated as public water supplies, unless appropriate federal, state, and local permitting agencies grant written permission.

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1
APPENDIX 1E

Project Correspondence to Landowners and Stakeholders (to-date)

PLAQUEMINES

1401 McKinney Street, Suite 2600
Houston, TX 77010

O 281.761.9800
www.ventureglobal.com

April 18, 2025

[Contact Name]
[Title]
[Agency Name]
[Address]

Re: Plaquemines Expansion Project

Dear Landowner:

Plaquemines Expansion, LLC ("Plaquemines Expansion"), a wholly owned subsidiary of Venture Global LNG, Inc. ("Venture Global LNG"), is writing to provide information to you regarding the Plaquemines LNG Expansion Project ("Project").

Plaquemines Expansion has contractually secured rights to an approximately 600-acre site immediately adjacent to the LNG terminal currently under construction by Plaquemines Expansion's affiliate—Venture Global Plaquemines LNG, LLC—in Plaquemines Parish, Louisiana, (the "Project Site"). The Project facilities will include construction of twelve liquefaction blocks capable of producing up to 18.6 million tonnes per annum ("MTPA") of liquefied natural gas ("LNG"), one marine loading berth for ocean-going vessels, and an on-site 930-megawatt natural gas-fired combined cycle electric generation facility. Plaquemines Expansion will liquefy, store, and deliver LNG as needed to LNG carriers for export overseas. A site layout for the Project is included in Attachment A.

On March 6, 2025, Plaquemines Expansion jointly filed a request with Venture Global Plaquemines LNG, LLC (jointly "the Applicants") to obtain approval from the Director of the Office of Energy Projects of the Federal Energy Regulatory Commission ("Commission") to initiate the Commission's National Environmental Policy Act ("NEPA") pre-filing review of the Project. The FERC officially accepted Plaquemines Expansion's request on April 4, 2025 (See FERC Docket No. PF25-7).

The pre-filing process is meant to increase stakeholder input early in the permitting process by (1) allowing proactive interaction between the prospective applicants, Commission staff, other agencies, landowners, and other stakeholders and (2) identifying and addressing issues during the planning phase before a formal application for authorization of the Project is submitted. At the close of the pre-filing review, the Applicants will file a formal application with the Commission pursuant to Section 3 of the Natural Gas Act.

Plaquemines Expansion expects to file the formal project application in October 2025. Following the receipt of Commission authorization and other necessary approvals, the Applicants plan to begin construction of the Project in early 2027.

Those landowners within one half mile of the Project are officially defined as “affected landowners” and, as such, are letter recipients. As an “affected landowner”, the following information is enclosed to inform you about the FERC review process and your rights.

- A copy of the FERC pamphlet for landowners entitled “An Interstate Natural Gas Facility on My Land? What do I Need to Know?”

Plaquemines Expansion intends to hold public open house meetings in May 2025 to discuss the Project and solicit feedback from impacted parties and the public about the proposed Project. A separate invitation to the open houses will follow in the coming weeks.

If you have any questions, please feel free to contact us at our toll-free line at 1-800-514-0833 or email us at landowner@VENTUREGLOBALLNG.COM. You can also visit our website at ventureglobalIng.com for more information on the Project.

If you have a grievance or other concern about the Plaquemines Expansion Project, you can submit an anonymous report though: https://ventureglobal.allvoices.co/ or by calling 1-888-483-9086. Please include as much information as possible including any photograph or attachment which you think is relevant.

We look forward to working with you on the Plaquemines Expansion Project and seeing you at the upcoming open houses.

Respectfully submitted,




AJ Walker
Vice President, Public Affairs & Development
Venture Global LNG, Inc.

Enclosures

cc: Fory Musser, Senior Vice President, Venture Global LNG, Inc.
Elizabeth Dolezal, Vice President, Venture Global LNG, Inc.
Jonathan Robillard, Director, Venture Global LNG, Inc.
Charlie Burt, Senior Manager, Venture Global LNG, Inc.

An Interstate Natural Gas Facility on My Land?


What Do I Need to Know?



Federal Energy Regulatory Commission








Washington, DC www.ferc.gov

An Interstate Natural Gas Facility on My Land?

What do I Need to know?




The Federal Energy Regulatory Commission is charged by Congress with evaluating whether interstate natural gas pipeline projects proposed by private companies should be approved. The Federal government does not propose, construct, operate, or own such projects. The Commission's determination whether to approve such a project may affect you if your land is where a natural gas pipeline, other facilities, or underground storage fields might be located.
We want you to know:

- *How the Commission's procedures work;*
- *What rights you have;*
- *How the location of a pipeline or other facilities is decided; and*
- *What safety and environmental issues might be involved.*

Federal Energy Regulatory Commission
Updated August 2015



PROCESS FOR NATURAL GAS CERTIFICATES



Contents

Background....4
How the Process Begins....5
Key Issues Involving Location of the Project....8
Pipeline Installation Sequence....11
Pipeline Construction....12
Abandonment....14
Storage Fields....15
LNG Facilities....20
Compressor Stations....20
The Responsibilities of Gas Companies....22
Important Safety Issues....25
Further Environmental Issues....26
Additional Information....27
Glossary of Terms....28

Background

The Commission approves the location, construction and operation of interstate pipelines, facilities and storage fields involved in moving natural gas across state boundaries. The Commission also approves the abandonment of these facilities.

Interstate pipelines crisscross the United States, moving nearly a quarter of the nation's energy long distances to markets in the 48 contiguous states, and are vital to the economy. Although pipelines generally are buried underground, they may have associated facilities that are above-ground such as taps, valves, metering stations, interconnection, pig launchers, pig receivers, or compressor stations. A natural gas storage field includes subsurface gas storage rights and there may be storage field pipelines and gas wells associated with the storage rights. A Pipeline Glossary is provided at the end of this brochure to help you understand some of the technical terms that are associated with pipeline construction and above-ground facilities.

If a proposed pipeline route is on, or abuts your land, you will probably first learn of this from the natural gas company as it plans and studies the route during either the Commission's voluntary Pre-filing Process or in the application development process. Once a company files an application requesting the Commission to issue a certificate authorizing the construction of a pipeline project, the company will mail you a copy of this brochure and other information within three days of the Commission issuing a Notice of Application. The Commission's staff will prepare an environmental study of the proposal; either an Environmental Impact Statement or an Environmental Assessment, depending on the scope of the project. For major construction projects, local media may be notified and public meetings may be held. You will have an opportunity to express your views and to have them considered. You will also have the opportunity to learn the views of other interested parties. The Commission may approve the project, with or without modifications, or reject it. If it is approved and you fail to reach an easement agreement with the company, access to and compensation for use of your land will be determined by a court.

Understandably, the location of pipelines and other facilities may be of concern to landowners. The Commission's process for assessing pipeline applications is open and public, and designed to keep all parties informed.

This brochure generally explains the Commission's certificate process and addresses some of the basic concerns of landowners. The Commission's Office of External Affairs at 1-866-208-3372 will be happy to answer any further questions about the procedures involved.

How the Process Begins

Q: How will I first hear about proposed facility construction?

A: If you are located in the vicinity of the project you may first learn of it through newspaper notices. If you are an owner of property that may be affected by the project, you will probably first hear of it from the natural gas company as it collects the environmental information or conducts surveys required for the Commission application. The company may ask you for permission to access your land to conduct civil and environmental surveys. It is also possible that the company will contact you to discuss obtaining an easement prior to filing the application. In the case of a compressor station or other above-ground facility, the company will often offer to purchase, or obtain an option to purchase, the property for the station or facility. This usually occurs prior to the filing of the application.

For a storage field, rights on certain parcels of land may only involve subsurface storage rights. The company will also notify you of the filing of the application with the Commission.

Q: How can I obtain more details about the company's application?

A: A copy of the company's application can be obtained from the company, although the company is not obligated to provide voluminous material or material that is difficult to reproduce. You may also obtain a copy for a nominal copying charge from the Commission's Public Reference Room. Call 202-502-8371 for details. The application may also be obtained through the Commission's Web site, **www.ferc.gov**, using the "**eLibrary**" link and the project's docket number. User assistance is available at 1-866-208-3676. Within three days of assignment of a docket number, the application will also be available in at least one location in each county in which the facility is located.

Note that in some cases you will not be able to view or print copies of large-scale maps or similar information about the location of the project from the

Commission's Web site. However, the Web site will provide instructions for obtaining the material.

Q: How do I make my views known?

A: You may contact the natural gas company through the contact person listed in the notification letter you receive from the company.

There are two ways to make your views known to the Commission: first, if you want the Commission to consider your views on the various environmental issues involved in the location of the facility, you can do so by simply writing a letter. When submitting a letter to the Secretary of the Commission, you should identify the project's docket number in order for the comment to be successfully entered into the record on the eLibrary system.

There are several steps in the Commission's environmental review process. The Commission affords you the opportunity to comment at various stages in this process. Details are available from the Commission's Office of External Affairs at 1-866-208-3372. Check the Commission's Web site for details on filing electronically. By filing comments, your views will be considered and addressed in the environmental documents or a final order. Additionally, you will be placed on a mailing list to receive environmental documents in the case. You can also use eRegistration and eSubscription (see **www.ferc.gov**) to keep track of individual proceedings at FERC. Users with an eRegistration account may subscribe to specific dockets and receive email notification when a document is added to eLibrary for the subscribed docket.

Q: What is an intervenor?

A: You may file to become what is known as an intervenor. You may obtain instructions on how to do this from the Office of External Affairs or on our Web site at *http://www.ferc.gov/resources/guides/how-to/intervene.asp*. Becoming an intervenor is not complicated and gives you official rights. As an intervenor, you will receive the applicant's filings and other Commission documents related to the case and materials filed by other interested parties. You will also be able to file briefs, appear at hearings and be heard by the courts if you choose to appeal the Commission's final ruling. ***However, along with these rights come responsibilities. As an intervenor, you will be obligated to provide copies of what you file with the Commission to all the other parties at the time of filing by electronic means (direct attachment of the document to an e-mail or by referencing a link to the filed document in eLibrary) or***

by mail. In major cases, there may be hundreds of parties. You may file to become an intervenor by sending a request to intervene by mail or overnight services to:

Secretary
Federal Energy Regulatory Commission
888 First Street, N.E.
Washington, DC 20426

We prefer that comments or requests for intervention be submitted electronically through the Commission's Web site (www.ferc.gov). If you submit comments or requests through eFiling or eComment, there is no need to send paper copies. However, if you submit a request for intervention through the mail, you should include 14 copies of your request.

You must normally file for intervenor status within 21 days of our notice of the application in the Federal Register, although the Commission may accept late intervention if good reasons are given. Visit the Federal Register at *http://www.gpoaccess.gov/fr/index.html*. You may also file for intervenor status for the purposes of addressing environmental issues during the comment period for a draft environmental impact statement.

Please note: "PF" dockets are assigned to projects that are in the pre-filing or planning stage. There is no provision for becoming an intervenor in PF dockets. However, once the pre-filing stage has been completed and an application has been filed, you may file for intervenor status.

CUSTOMER ASSISTANCE

For further assistance and public inquiries, please contact:
Office of External Affairs
1-202-502-8004 1-866-208-3372 (Toll-free)
customer@ferc.gov

For assistance with ferc.gov or eFiling, please contact:
FERC Online Technical Support
1-202-502-6652 1-866-208-3676 (Toll-free)
ferconlinesupport@ferc.gov

For materials and copying assistance, please contact:
Public Reference Room
1-202-502-8371 1-866-208-3676 (Toll-free)
public.referenceroom@ferc.gov

YOUR PROJECT'S DOCKET NUMBER PF25-7-000

Key Issues Involving Location of the Project

Q: How is the pipeline route, compressor station or storage field location selected?

A: The natural gas company proposes the route or location, which is then examined by the Commission. The company must study alternative routes or locations to avoid or minimize damage to the environment. The Commission, intervenors, or any commenter may also suggest alternatives and modifications to reduce the effects on buildings, fences, crops, water supplies, soil, vegetation, wildlife, air quality, noise, safety, landowner interests and more. The Commission staff's Alternatives analysis will consider whether the pipeline can be placed near or within an existing pipeline, power line, highway or railroad right-of-way. Storage fields are usually located in depleted oil or natural gas production fields or in salt deposits. Therefore, their location is fixed by geologic conditions. However, the facilities needed to develop and use a storage field can be moved to some extent.

Q: How do natural gas companies obtain a right-of-way?

A: The company negotiates a right-of-way easement and compensation for the easement with each landowner. Landowners may be paid for loss of certain uses of the land during and after construction, loss of any other resources, and any damage to property. If the Commission approves the project and no agreement with the landowner is reached, the company may acquire the easement under eminent domain (a right given to the company by statute to take private land for Commission-authorized use) with a court determining compensation.

Q: Who pays taxes on the right-of-way?

A: The landowner pays taxes on the right-of-way unless a local taxing authority grants relief. The company simply has an easement across a portion of the land.

Q: How large is the right-of-way and how is it maintained?

A: It is generally 75 to 100 feet wide during construction, although extra space is usually required at road or stream crossings or because of soil conditions.

The permanent right-of-way is usually about 50 feet wide. Routine mowing or cutting of vegetation is done no more than once every three years. A ten-foot-wide corridor, centered on the pipeline, may be mowed or cut more frequently to facilitate periodic surveys and inspections. In cropland and residential areas the right-of-way is maintained by the landowner consistent with the presence of a pipeline.

Q: How large is a compressor station or storage field?

A: Usually the natural gas company purchases ten to forty acres for a compressor station, of which about five acres are actually used for construction. A storage field could encompass many hundreds or even thousands of acres, depending on the geologic structure. Storage fields also frequently include a buffer zone or protection area forming a halo of some hundreds of acres surrounding the storage field itself.



Compressor Station

Q: Must the company comply with local, county and state laws and zoning ordinances?

A: Generally, yes. If there is a conflict, however, between these requirements and what the Commission requires; the Commission requirement prevails.

Q: How close can I build to the facilities?

A: For a pipeline this depends on the terms of the easement agreement. But build is usually allowed up to the edge of the right-of-way.

For a compressor station, the site is usually owned by the company. If you own property adjacent to the site, you may build on it.

For storage fields, unless there are surface facilities or pipelines, you may build anywhere on the surface. If you or someone else wishes to drill wells which would penetrate the storage formation, you must coordinate that activity with the company, and usually the state authority regulating well drilling.

Q: What about bushes, trees, fences, driveways and so forth?

A: Trees with roots that may damage the pipeline or its coating and other obstructions that prevent observation from aircraft during maintenance are usually not allowed. Driveways and other improvements without foundations are normally allowed. All improvements are subject to the terms of the easement and are subject to negotiation as long as the pipeline maintenance and safety are not affected.

Q. How long will the right-of-way be there?

A: Part of it is temporary and will be restored immediately after construction. The permanent right-of-way will remain until the Commission determines it can be abandoned by the pipeline company. This can be 20 to 50 years or more.

Q. In general, will I still be able to use the right-of-way?

A: The easement agreement will specify restricted uses on or across the right-of-way and any types of uses for which the company's permission must be sought. The continuation of past agricultural uses and practices on or across the right-of-way would be permitted. Buildings and large trees are usually not allowed. Special uses or activities that might have an impact on pipeline design (such as planned logging roads or drain tiles) should be negotiated with the pipeline company to minimize future conflicts.

Q: To what depth would the pipeline be buried underground?

A: The depth of cover for natural gas pipelines is regulated by the Pipeline and Hazardous Materials Safety Administration, within the U.S. Department of Transportation. In normal soil conditions, the minimum required is 30-36 inches between the top of the pipeline and the land surface. Additional cover is provided at road and waterbody crossings, while less cover (a minimum of 18 inches) is required in consolidated rock. In special cases, the pipeline could be buried deeper (48 – 60 inches) where agricultural practices or other issues warrant additional cover.



Pipeline

Q: What if I have problems with erosion or other issues during restoration and/or maintenance of the right-of-way?

A: The landowner should first contact the natural gas company to address and resolve the issue. If the landowner is not satisfied that the problem has been adequately addressed, he or she can contact the Commission's Landowner Helpline at (877) 337-2237 or send an email to *landownerhelp@ferc.gov*.

Pipeline Installation Sequence

After a company has received authorization from FERC as well as all necessary permits, and has an easement on a property, construction would proceed as follows:

1) The civil survey (and any uncompleted environmental surveys) would be completed and the construction right-of-way would be marked/staked for the clearing crew.

2) The clearing crew would remove any trees or brush within the right-of-way that would interfere with construction.

3) Temporary erosion control devices would be installed as required.

4) Next, the right-of-way would be graded.

5) Topsoil would be separated from subsoil in agricultural/residential areas (or in other areas requested during the easement negotiations).

6) Heavy equipment, such as backhoes or trenching machines, would then dig the trench. In areas where bedrock is near the surface, blasting may be required.

7) The pipe would be delivered to the right-of-way in segments (called joints).

8) The pipe would be bent to fit the trench and welded together. All welds would be tested prior to placing the pipe in the trench.

9) The trench would be back filled and if topsoil was removed it would be returned.

10) Construction debris would be removed.

11) The right-of-way would be regraded, seeded, and temporary and permanent erosion control devices would be installed.

12) After the right-of-way has revegetated the temporary erosion control devices would be removed.

13) Prior to gas flowing, the pipeline would be pressure tested (normally with water) to ensure it does not leak.

Pipeline Construction

A graphic representation of the pipeline installation sequence.



Moving assembly line (graphic not to scale)



Clearing and grading

Ditching (rock-free)

Ditching (rock)

Padding ditch bottom





Bending

Welding

X-ray and weld repair

Coating welds





Cleanup




Restoring residential area



Reseeding the right-of-way







Stringing

continued below







Inspection and repair of coating

Lowering in

Backfill

Pressure testing for leaks









Restored right-of-way

Abandonment

Q: What is abandonment in place?

A: A pipeline company may request authorization for a pipeline to be "abandoned in place." In this case, the pipeline is physically separated from its source of gas and is no longer maintained. The pipeline is sealed at both ends and left in the ground. A company may revert the easement back to the affected property owners; in certain cases where multiple pipelines exist in the same corridor, the company may continue to hold the easements and maintain the right-of-way according to its vegetation maintenance practices.

Q: Can the pipeline be used after abandonment?

A: In some cases a pipeline company may ask to abandon a pipeline for use as a natural gas transportation line, but reserve the right to convert that line to another use, such as the transportation of crude oil or other petroleum products. Easements agreements affected by conversion transactions may transfer to the new operator.

Q: If the pipeline is being abandoned will it be removed from my property?

A: The Commission may decide there are environmental or other conditions that should determine the disposition of the pipeline. If not, the easement agreement that you or previous owners of the land signed may stipulate whether the pipeline is to be removed. You may also come to some agreement with the company on what they will do with the pipeline. Usually, above-ground facilities are removed.

Q: If a company abandons a pipeline, can it keep an easement on my property?

A: It depends on the terms of the easement agreement and may be subject to negotiation between the landowner and the pipeline company. If there is more than one pipeline, the pipeline company will keep the easement.

Q: Will I be notified if abandonment is proposed?

A: You will probably be notified by the company if it proposes to relinquish the easement as part of the abandonment and the easement is not being transferred to another company. Otherwise, you may be notified by the Commission as part of the environmental analysis of the project.

Storage Fields

Q: What will happen to my property if a storage field is located beneath it?



Well drilling rig

A: Possibly nothing, since the storage field itself is usually thousands of feet beneath the ground surface. Wells are needed to inject and withdraw the stored natural gas or to monitor field conditions (observation wells). The wells require a surface site of roughly one acre for drilling and less than one tenth of an acre for the surface wellhead piping and other facilities.

If there are no facilities to be constructed on your property, the company will only need the storage rights to the geologic formation in which the natural gas would be stored. This is also the case for any property within any designated "buffer zone" or "protective area" around the actual storage field.

Q: Why is storage important?

A: Underground natural gas storage can be used to balance the load requirements of gas users. Storage fields are the warehouses that provide a ready supply of natural gas to serve the market during periods of high demand. For example, in the Midwest and the Mid-Atlantic regions, natural gas is primarily used during the winter because many homes are heated by natural gas. To accommodate this load profile, natural gas is injected into storage fields

during the warmer months (April - October), and withdrawn in the colder months (November - March). However, since the 1980s, most new power generation equipment has been fired by natural gas, which has created summer peaking requirements for natural gas to accommodate air conditioning loads in many areas of the country. Storage helps to meet peak demand requirements both in winter and in summer.

Q: What types of facilities are associated with storage?

A: Most natural gas storage facilities in the U.S. consist of underground formations, combined with above-ground equipment. These facilities include wells (injection/withdrawal and observation, water supply, water disposal), wellhead valve assemblies, gathering lines (field lines, headers), metering and compression facilities, dehydration units, generators or transformers, associated electric equipment, roads, sheds/buildings and pipeline pigging facilities. A list of natural gas facilities that fall under FERC jurisdiction is available on the agency's Web site at *http://www.ferc.gov/industries/gas/indus-act/storage/fields-by-owner.pdf* . Natural gas storage facilities that are owned and operated by natural gas distribution systems and used to deliver gas to their customers fall under the authority of state regulatory agencies.

Q: Are there different types of underground storage fields?

A: Most storage of natural gas takes advantage of natural geologic formations (reservoirs). There are three types of underground storage fields: (1) depleted oil and/or gas fields, (2) aquifers, and (3) salt caverns.

Depleted Oil and/or Gas Fields: Most of the natural gas storage in the United States consists of naturally-occurring oil or gas reservoirs that have been depleted through production. These consist of porous and permeable underground rock formations (usually 1,000 to 5,000 feet thick) that are confined by impermeable rock barriers and identified by a single natural pressure. Typically, this type of field has one injection/withdrawal cycle each year – gas is injected in summer and withdrawn in winter. This type of storage facility is normally used for long term or seasonal system supply, although in some instances it is used for peak day deliveries. These formations contain volumes of gas that are permanently stored in the field (called cushion or base gas) that help to maintain the underground pressure required to operate the field. Storage gas is then added to the field. In field storage the base gas is generally about 50% of the total reservoir capacity.

Aquifer Storage Fields: This type of storage field uses a permeable rock formation containing water, called an "aquifer." The nature of the water in the aquifer may vary from fresh water to saturated brine. An aquifer would have a high cushion gas requirement, generally between 50% and 80%, as the water in the portion of the reservoir being used for storage must be displaced constantly. They also have high deliverability rates but are limited to one injection/withdrawal cycle each year.

Salt Cavern Storage: This type of storage field uses caverns that are leached or mined out of underground salt deposits (salt domes or bedded salt formations). Salt caverns usually operate with about 20% to 30% cushion gas and the remaining capacity as working gas. Working gas can be recycled more than once per year (some up to 10 – 12 times per year), the injection and withdrawal rates being limited only by the capability of the surface facilities. Salt cavern storage has high deliverability and injection capabilities and is usually used for peak deliverability purposes, daily or even hourly. Most of the naturally-occurring salt caverns in the United States lie closer to the producer region—in Louisiana, Texas, and the Gulf Coast.

For more detailed information about natural gas storage, visit these Web sites:

- FERC Staff Report on Underground Natural Gas Storage
  http://www.ferc.gov/EventCalendar/Files/20041020081349-final-gs-report.pdf
- EIA: Basics of Underground Natural Gas Storage
  http://www.eia.doe.gov/pub/oil_gas/natural_gas/analysis_publications/storagebasics/storagebasics.html
- NaturalGas.org: Storage of Natural Gas
  http://www.naturalgas.org/naturalgas/storage.asp
- The Energy Information Administration (EIA)
  http://www.eia.doe.gov/oil_gas/natural_gas/info_glance/natural_gas.html

Q: How are storage field boundaries determined?

A: Boundaries are determined by the geologic characteristics of the formation in which the gas will be stored. Most also have buffer zones surrounding the portion of the reservoir to limit migration of the stored gas and to protect the integrity of the field.

Q: Can companies use the ground under my property without paying for it? Am I required to sign an easement?

A: A company that owns/operates a storage field cannot use the underground portion of storage facilities without either owning mineral rights or having some form of agreement with the owner of the mineral rights. Compensation for that use will come as a result of the property/mineral rights conveyed to the company by the current owner or attached to the deed from a previous property owner. Those property/mineral rights, depending on the facts of the particular situation, will most likely be in the form of a storage lease or an easement agreement.

A FERC certificate is not required in order for a company to negotiate the acquisition of a storage lease or easement. However, if FERC has issued a certificate approving the creation of a new storage field (or expansion of an existing field), that indicates that the agency has concluded that the storage field is needed and is in the public interest. In accordance with the Natural Gas Act (a law passed by the United States Congress in 1938), the FERC certificate gives the company the right to ask a state or federal court to award the needed property rights to the company where voluntary good faith negotiation has failed.

If the owner of the property/mineral rights and the company do not reach an agreement, the company can go to court to obtain the necessary rights through eminent domain. In such cases, the court will determine the amount that the company must pay to the owner of these rights. Similarly, if the storage field operations affect the surface property through construction of facilities or by reserving access rights, the company must also reach an agreement with the owner of the surface rights or go to court to obtain any necessary property rights through eminent domain. The court will determine the amount that the company must pay the owner of the surface rights. The state or federal court procedure is known as condemnation (or the exercise of eminent domain).

Q: How far from my home can a storage facility be located? If the company is just using the area under my land, do they require access to my land?

A: The storage reservoir itself is underground and does not require surface facilities on every property within the storage field boundaries. However,



Underground storage

the company may need to construct and operate facilities on the surface, including injection and withdrawal wells to get the gas into and out of the subsurface rock formations, well lines that connect those wells to other pipelines in the storage field, compressor stations to pump the gas, and facilities that are used to clean and monitor the interior of certain underground pipelines. Where surface facilities are needed, the storage lease or easement agreements developed between the landowner and the storage facility operator usually indicate minimum spacing of the facilities with respect to existing structures, like your home.

In most cases, if the company does not have any surface facilities on your property, the company would not need access to your property. However, the company may need access to your land to check the integrity of a pipeline crossing your property or to monitor the effects of previously abandoned facilities (such as an old gas well) or facilities owned by another company to insure that those facilities do not interfere with the company's storage operations. Because the need for access cannot be predicted, the storage lease or easement agreement typically references the right of the company to enter your property when needed. The company should inform the property owner when its employees plan to enter the property.

Q: Is all storage in the U.S. under the jurisdiction of the Federal Energy Regulatory Commission?

A: No. Only natural gas storage that is used in interstate commerce is under FERC jurisdiction. There are approximately 500 existing underground natural gas storage facilities in the United States. Of those facilities, approximately 50% are under FERC jurisdiction, and the remaining are under state and/or local jurisdiction or are privately owned and unregulated.

LNG Facilities

Natural gas can also be converted to liquefied natural gas (LNG) and stored in above-ground tanks. Facilities for making LNG are used by many gas distribution companies for short-term peaking requirements, and are regulated under state authority. However, The Commission regulates a small number of similar facilities that are connected to interstate natural gas pipelines.

The United States also has several large LNG terminals, which include large LNG storage tanks as part of their operations. Traditionally, imported LNG is regasified before it enters the system of interstate natural gas pipelines for delivery to consumers. The Gulf Coast area has the country's highest concentration of existing and planned LNG terminals. In this region, salt caverns and depleted reservoirs also may be used as gas storage.

The growing production of natural gas in the United States from shale deposits has led to rising interest in developing liquefaction facilities for the export of natural gas to other countries. In this case, some LNG terminals would be used to export gas. Domestic natural gas would arrive at an LNG terminal via pipeline in a gaseous state, then liquefied and placed on LNG vessels for delivery to international consumers. While the Commission has the responsibility to evaluate and authorize LNG facilities, any company that exports natural gas also must receive an export license from the U.S. Department of Energy.

Compressor Stations

Q: What is a compressor station?

A: Compressor stations house natural gas fired engines, turbines or electric motors that drive compressors to compress, or pump, natural gas to move it through the system. They are located strategically along a pipeline route. Compressor stations associated with interstate natural gas pipeline systems are regulated by FERC. Compressors also are used by producers in gathering facilities that are not regulated by FERC.

Electric motor-driven compressors are very clean, and emit no particulate matter or pollutants. Natural gas-fired engines and turbines burn a portion of

the natural gas in the pipeline and would emit pollutants. Air emissions are regulated by the U.S. Environmental Protection Agency and state permitting authorities. These regulations are applicable to any source that emits or has the potential to emit any air contaminants, as defined in the Clean Air Act. Companies are required to obtain these federal permits, as applicable.

Q: How noisy is a compressor station?

A: The noise attributable to a new compressor station, compression added to an existing station, or any modification, upgrade or update of an existing station, must not exceed a day-night average noise level of 55 decibels at any pre-existing noise-sensitive areas such as schools, hospitals or residences. Companies perform noise surveys during initial operation of the approved facilities and report the results to FERC to document compliance.

Q: Can compressor stations cause vibration at my home?

A: Vibration is caused by direct vibration or by low-frequency noise emitted from a compressor station. This is similar to what happens when noise from a speaker causes the floor to shake or when a helicopter flying overhead causes a window to rattle.



Compressor station

Companies are required to comply with FERC's rule at 18CFR 380.12(k)(4)(v)(B) to ensure that there is no increase in perceptible vibration from the operation of the compressor station.

Q: How much noise is permitted from drilling activities?

A: Directional drilling is sometimes used to install underground pipeline through sensitive areas. Drilling is also used to install vertical wells at storage facilities. Drilling should be conducted with the goal of keeping noise impacts at noise-sensitive areas below a day-night level of 55 decibels. States may have their own noise level requirements for construction sites.

Q; Will the compressor station affect my air quality?

A: Numerous federal and state air quality rules and permits may apply to each compressor station. FERC will identify the required permits and regulations for each compressor station. We also identify the impacts on local and regional air quality from construction and operation of each compressor station.

Q: Are there special safety or fire issues associated with compressor stations?

A: All interstate natural gas facilities, including compressor stations, are required to comply with the U.S. Department of Transportation's Minimum Safety Standards. Compressor stations are constructed with many safety systems, such as gas and fire detection systems and emergency shutdown equipment. These systems are designed to ensure that in the event of an accident, the compressor station would be safely shut down with minimal risk to the public.

The Responsibilities of Gas Companies

Q: Must companies post bonds to guarantee performance?

A: No, but the Commission inspects the right-of-way during and after construction to ensure that the terms of its certificate have been met.

Q: Can the pipeline company come on my land without my permission?

A: State or local trespass laws prevail until a certificate is issued by the Commission. Some states have laws that allow a company to get access to property for survey purposes. Procedures vary by state. Once a certificate is issued or an easement/survey agreement or court order is obtained, the company may come onto your land. Usually the company will notify you in advance.

Q: When can they start to build?

A: Construction cannot commence until the Commission issues a certificate, the company accepts it, the company receives all other relevant permits and

authorizations, and the company complies with environmental conditions attached to the certificate. For most large pipelines, the time from filing an application to approval ranges from one year to two years. Once a certificate is issued, construction may start within a few weeks of the company having completed any outstanding studies or having met other preconditions set by the Commission.

Q: Why would the company approach me about an easement before the project is approved?

A: Because of planning and lead time, the company may try to obtain easement agreements in advance. Also, a company must conduct environmental studies before it files an application with the Commission. For these studies to be as complete as possible, the company will try to obtain access to all of the proposed right-of-way. If Commission approval is ultimately denied, or the route changes, the initial easement agreement with the landowner is usually void (depending on the wording of the right-of-way or access contract). Further, disputes over the wording of an easement agreement are subject to state law.



Valve

Q: Can the company place more than one pipeline on my property? Can the pipeline and the easement be used for anything other than natural gas?

A: The Commission grants a certificate and states that eminent domain may only be used for the proposed pipeline and related facilities in the exact location described and only for the transportation of natural gas. If the company wishes to install another natural gas pipeline under Commission jurisdiction, it must obtain additional approval from the Commission. Other utilities may wish to use an adjacent or overlapping easement, but they would have to obtain approval from you or from another permitting authority that can grant eminent domain (usually the state). Of course, you may agree to other uses.

Q: Can the company construct above-ground facilities on the right-of-way?

A: Yes, if they have been approved by the Commission. Above-ground facilities, such as valves, pig launchers and pig receivers, are commonly placed in the right-of-way and are strategically placed along the pipeline system for operation and safety purposes.

Q: How close can the pipeline be to other pipelines or utility facilities?

A: Pipelines must be at least a foot from any underground structure and two to three feet below ground. Companies usually want their pipelines to be 25 feet from another pipeline. If space permits, pipelines can be placed in another utility's right-of-way.

Q: Can I receive service from the pipeline?

A: No, not in most cases. Generally speaking, interstate pipelines are operating at pressures incompatible with direct residential use, which is provided by local distribution companies.

Q: Can a pipeline be placed in a river or the ocean?

A: A pipeline can be placed in the ocean or across a river; however, it is usually not acceptable to place one longitudinally down a river or other stream. There are different environmental, cost, design and safety issues associated with construction in a water body.

Q: How soon after construction will the company restore the land?

A: Commission rules require restoration as soon as the trench is backfilled and weather permits.

Q. What authorization allows the pipeline company to use eminent domain?

A: If the Commission authorizes the project and the necessary easements cannot be negotiated, an applicant is granted the right of eminent domain

under section 7(h) of the Natural Gas Act and the procedures set forth under the Federal Rules of Civil Procedure (Rule 71A). Under these conditions, the landowner could receive compensation as determined by the courts.

Important Safety Issues

Q: Who is responsible for safety?

A: While the Commission has oversight in ensuring that pipeline and above-ground facilities are safely constructed and installed, once the natural gas is flowing in the new system, the U.S. Department of Transportation's Pipeline and Hazardous Pipeline Materials Safety Administration takes over the responsibility during the operation for the lifetime of the pipeline. The U.S. Department of Transportation is also responsible for setting the federal safety standards for natural gas (and other) pipelines and related facilities. The *Pipeline and Hazardous Materials Safety Administration* can be contacted at 202-366-4595 or at *http://www.phmsa.dot.gov*.

Q: Are pipelines safe?





Safety Inspectors

A: Accidents are rare and usually result from outside forces or unauthorized action by someone other than the pipeline company. The U.S. Department of Transportation enforces strict safety standards and requires safety checks.


Q: Does natural gas smell?

A: Natural gas is odorless. An odorant, which smells like rotten eggs, is generally added for quick leak detection in more populated areas on interstate transmission pipelines and in local distribution pipelines in accordance with U.S. Department of Transportation safety regulations.

Further Environmental Issues

Q: What if my property contains endangered species, wetlands, or archeological sites?

A: Endangered species must be protected from the effects of construction and this could affect the location of the pipeline or other facilities. In the case of wetlands, if proper crossing procedures are used and no alternatives are available, they may be used for a pipeline right-of-way. If an archeological or historic site is eligible for listing in the National Register of Historic Places, impact to it must be minimized. It either will be excavated and studied, or the pipeline will be rerouted to avoid it. Landowners who want them usually are permitted to keep any artifacts after they are properly studied, subject to state law.



Wetlands

Q: Environmental studies were mentioned earlier. How do they work?

A: A Notice of Intent (NOI) to prepare an environmental assessment (EA) or an environmental impact statement (EIS) is issued for most major proposals. It is sent to federal, state and local agencies, local media and libraries, environmental groups, and the affected owners of any land that would be crossed. For some major projects the NOI may announce a schedule of public meetings along the proposed route. The NOI seeks comments from interested parties on the scope of the environmental document, and the comments must be submitted to the Commission, normally within 30 days. After the comment period, the Commission staff will prepare an EA or a Draft EIS outlining its findings and recommendations. For major proposals, further comments are sought during 45 days allotted for review of a Draft EIS or 30 days in the case of an EA. These comments are addressed in the Final EIS or the final order granting or denying the application.

Additional Information

FOR ADDITIONAL INFORMATION, CONTACT:

Federal Energy Regulatory Commission
Office of External Affairs
888 First Street NE, Washington, DC 20426
Toll Free: 1-866-208-3372
E-mail: *customer@ferc.gov*
www.ferc.gov

Landowner Helpline
Toll Free: 1-877-337-2237
E-mail: *landownerhelp@ferc.gov*

Other related FERC documents you may find helpful are listed below. These are available on our web site.

The following can be found at:
http://www.ferc.gov/industries/gas/enviro/guidelines.asp

- Guidelines for Reporting On Cultural Resources Investigations
- Handbook for Using Third-party Contractors to Prepare Environmental Assessments & Environmental Impact Statements (EIS)
- Upland Erosion Control, Revegetation and Maintenance Plan
- Wetland and Waterbody Construction and Mitigation Procedures

http://www.ferc.gov/resources/guides.asp

- Your Guide to Electronic Information at FERC
- An Interstate Natural Gas Facility on my Land
- Blanket Certificate Program: Notice to landowners

Glossary of Terms

Glossary of Terms supplied courtesy of the Pipeline and Hazardous Materials Safety Administration and FERC staff. For further information, please consult the PHMSA web site at *http://www.phmsa.dot.gov.*

COMPRESSOR STATIONS

Compressor Stations are facilities located along a natural gas pipeline that house and protect compressors. Compressors are used to compress (or pump) the gas to move it through the system. Compressor stations are strategically placed along the pipeline to boost the system pressure to maintain required flow rates.

EASEMENT

An easement is an acquired privilege or right, such as a right-of-way, afforded a person or company to make limited use of another person's or company's real property. For example, the municipal water company may have an easement across your property for the purpose of installing and maintaining a water line. Similarly, oil and natural gas pipeline companies acquire easements from property owners to establish rights-of-way for construction and operation of their pipelines.

GATHERING LINE

Pipelines, generally small in diameter, used to transport oil or gas from the well to a processing facility or a mainline pipeline. Gathering facilities, which can include the gathering lines and compressor stations associated with gathering, are not regulated by the Federal Energy Regulatory Commission.

HYDRAULIC FRACTURING

Also called "fracking," this refers to a process of fracturing rock using a pressurized liquid. This is usually water mixed with sand and chemicals, injected deep within the ground through a piped well bore. This technique is commonly used to produce natural gas or oil from shale, tight or coal seam formations.



Fracking rig

LATERAL

A lateral is a segment of a pipeline that branches off the main or transmission line to transport the product to a termination point, such as a tank farm or a metering station.

LAUNCHER

A launcher is a pipeline component that is used for inserting an inline inspection tool, cleaning pig, or other device into a pressurized pipeline. After performing its task, the tool or pig is removed via receiver.

LIQUEFACTION

Liquefaction refers to the process of converting natural gas (methane) to a liquid to facilitate transportation or storage. This process requires removing impurities and cooling the methane to -260°F.

LOOP

A loop is a segment of pipeline installed adjacent to an existing pipeline and connected to it at both ends. A loop allows more gas to be moved through the system.

METERING AND REGULATING (M&R) STATIONS

Metering and regulating stations are installations containing equipment to measure the amount of gas entering or leaving a pipeline system and, sometimes, to regulate gas pressure.



Metering and Regulating Station

PIG

A pig, also known as a "smart" pig, is a generic term signifying any independent, self-contained device, tool, or vehicle that is inserted into and moves through the interior of a pipeline for inspecting, dimensioning, or cleaning. These tools are commonly referred to as "pigs" because of the occasional squealing noises that can be heard as they travel through the pipe.

RECEIVERS

A pipeline component used for removing an inline inspection tool, cleaning pig, or other device from a pressurized pipeline. The device is inserted into the pipeline via a launcher.

RIGHTS-OF-WAY (ROW)

A right-of-way is a defined strip of land on which an operator has the rights to construct, operate, and/or maintain a pipeline. A ROW may be owned outright by the operator or an easement may be acquired for specific use of the ROW.

TRENCH

A trench is a long narrow ditch dug into the ground and embanked with its own soil. They are used for concealment and protection of pipeline. Trenches are usually dug by a backhoe or by a specialized digging machine.

VALVE

A valve is a mechanical device installed in a pipeline and used to control the flow of gas or liquid.



Pipeline in trench

See *http://www.phmsa.dot.gov* for additional pipeline-related terminology definitions.

Your project's docket number

PF25-7-000



Federal Energy Regulatory Commission
Office of Energy Projects

888 First Street, NE
Washington, DC 20426
202–502–6088
1–866–208–3372 (toll free)
202–502–8659 (TTY)

www.ferc.gov/industries/gas.asp

ATTACHMENT A

Plaquemines Expansion Facility Layout

Service Layer Credits: USA_Topo_Maps: Copyright:© 2013 National Geographic Society, i-cubed




Figure 1
Project Location
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 3/5/2025

PLAQUEMINES

1401 McKinney Street, Suite 2600
Houston, TX 77010

O 281.761.9800
www.ventureglobal.com

July 18, 2025

[Contact Name]
[Title]
[Agency Name]
[Address]

Re: Plaquemines Expansion Project

Dear Landowner:

Plaquemines Expansion, LLC ("Plaquemines Expansion"), a wholly owned subsidiary of Venture Global, Inc. ("Venture Global"), is writing to provide information to you regarding the Plaquemines LNG Expansion Project ("Project").

Plaquemines Expansion has contractually secured rights to an approximately 600-acre site immediately adjacent to the LNG terminal currently under construction by Plaquemines Expansion's affiliate—Venture Global Plaquemines LNG, LLC—in Plaquemines Parish, Louisiana, (the "Project Site"). On March 6, 2025, Plaquemines Expansion jointly filed a request with Venture Global Plaquemines LNG, LLC (jointly "the Applicants") to obtain approval from the Director of the Office of Energy Projects of the Federal Energy Regulatory Commission ("FERC" or "Commission") to initiate the Commission's National Environmental Policy Act ("NEPA") pre-filing review of the Project. The FERC officially accepted Plaquemines Expansion's request on April 4, 2025 (See FERC Docket No. PF25-7).

Since you were notified of the Project in April, Plaquemines Expansion made the following modifications to the Project:

- Increased the number of liquefaction blocks from 12 to 16;
- Increased the production capacity from 18.6 million tonnes per annum ("MPTA") to 24.8 MTPA;
- Added an additional 586 acres to be used as a laydown area to support construction.

An updated site layout for the proposed Project is included in Attachment A. Plaquemines Expansion expects to file the formal project application in October 2025. Following the receipt of Commission authorization and other necessary approvals, the Applicants plan to begin construction of the Project in early 2027.

If you have any questions, please feel free to contact us at our toll-free line at 1-800-514-0833 or email us at landowner@VENTUREGLOBALLNG.COM. You can also visit our website at ventureglobalLNG.com for more information on the Project.

If you have a grievance or other concern about the Plaquemines Expansion Project, you can submit an anonymous report though: https://ventureglobal.allvoices.co/ or by calling 1-888-483-9086. Please include as much information as possible including any photograph or attachment which you think is relevant.

We look forward to working with you on the Plaquemines Expansion Project.

Respectfully submitted,



AJ Walker
Vice President, Public Affairs & Development
Venture Global, Inc.

Enclosures

cc: Fory Musser, Senior Vice President, Venture Global, Inc.
Elizabeth Dolezal, Vice President, Venture Global, Inc.
Jonathan Robillard, Director, Venture Global, Inc.
Charlie Burt, Senior Manager, Venture Global, Inc.

ATTACHMENT A

Plaquemines Expansion Facility Layout

Service Layer Credits: USA NAIP Imagery: Natural Color: Esri, USDA Farm Service Agency




Figure 1.1-1
Regional Location of Proposed Project
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 7/14/2025

PLAQUEMINES

1401 McKinney Street, Suite 2600
Houston, TX 77010

O 281.761.9800
www.ventureglobal.com

July 18, 2025

[Contact Name]
[Title]
[Agency Name]
[Address]

Re: Plaquemines Expansion Project

Dear Landowner:

Plaquemines Expansion, LLC ("Plaquemines Expansion"), a wholly owned subsidiary of Venture Global LNG, Inc. ("Venture Global LNG"), is writing to provide information to you regarding the Plaquemines LNG Expansion Project ("Project").

Plaquemines Expansion has contractually secured rights to an approximately 600-acre site immediately adjacent to the LNG terminal currently under construction by Plaquemines Expansion's affiliate—Venture Global Plaquemines LNG, LLC—in Plaquemines Parish, Louisiana, (the "Project Site"). The Project facilities will include construction of sixteen liquefaction blocks capable of producing up to 24.8 million tonnes per annum ("MTPA") of liquefied natural gas ("LNG"), one marine loading berth for ocean-going vessels, and an on-site 950-megawatt natural gas-fired combined cycle electric generation facility. Plaquemines Expansion will liquefy, store, and deliver LNG as needed to LNG carriers for export overseas. A site layout for the Project is included in Attachment A.

On March 6, 2025, Plaquemines Expansion jointly filed a request with Venture Global Plaquemines LNG, LLC (jointly "the Applicants") to obtain approval from the Director of the Office of Energy Projects of the Federal Energy Regulatory Commission ("Commission") to initiate the Commission's National Environmental Policy Act ("NEPA") pre-filing review of the Project. The FERC officially accepted Plaquemines Expansion's request on April 4, 2025 (See FERC Docket No. PF25-7).

The pre-filing process is meant to increase stakeholder input early in the permitting process by (1) allowing proactive interaction between the prospective applicants, Commission staff, other agencies, landowners, and other stakeholders and (2) identifying and addressing issues during the planning phase before a formal application for authorization of the Project is submitted. At the close of the pre-filing review, the Applicants will file a formal application with the Commission pursuant to Section 3 of the Natural Gas Act.

Plaquemines Expansion expects to file the formal project application in October 2025. Following the receipt of Commission authorization and other necessary approvals, the Applicants plan to begin construction of the Project in early 2027.

Since prefiling was initiated in March, Plaquemines Expansion has added an additional 586 acres to be used as laydown for the Project. Those landowners within one half mile of the Project are officially defined as

"affected landowners" and, as such, are letter recipients. As an "affected landowner", the following information is enclosed to inform you about the FERC review process and your rights.

- A copy of the FERC pamphlet for landowners entitled "An Interstate Natural Gas Facility on My Land? What do I Need to Know?"

If you have any questions, please feel free to contact us at our toll-free line at 1-800-514-0833 or email us at landowner@VENTUREGLOBALLNG.COM. You can also visit our website at ventureglobalIng.com for more information on the Project.

If you have a grievance or other concern about the Plaquemines Expansion Project, you can submit an anonymous report though: https://ventureglobal.allvoices.co/ or by calling 1-888-483-9086. Please include as much information as possible including any photograph or attachment which you think is relevant.

We look forward to working with you on the Plaquemines Expansion Project.

Respectfully submitted,



AJ Walker
Vice President, Public Affairs & Development
Venture Global, Inc.

Enclosures

cc: Fory Musser, Senior Vice President, Venture Global, Inc.
Elizabeth Dolezal, Vice President, Venture Global, Inc.
Jonathan Robillard, Director, Venture Global, Inc.
Charlie Burt, Senior Manager, Venture Global, Inc.

ATTACHMENT A

Plaquemines Expansion Facility Layout

Service Layer Credits: USA NAIP Imagery: Natural Color: Esri, USDA Farm Service Agency




Figure 1.1-1
Regional Location of Proposed Project
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 7/14/2025

PLAQUEMINES

1401 McKinney Street, Suite 2600
Houston, TX 77010

O 281.761.9800
www.ventureglobal.com

April 18, 2025

[Contact Name]
[Title]
[Agency Name]
[Address]

Re: Plaquemines Expansion Project

Dear Stakeholder:

Plaquemines Expansion, LLC ("Plaquemines Expansion"), a wholly owned subsidiary of Venture Global LNG, Inc. ("Venture Global LNG"), is writing to provide information to you regarding the Plaquemines LNG Expansion Project ("Project").

Plaquemines Expansion has contractually secured rights to an approximately 600-acre site immediately adjacent to the LNG terminal currently under construction by Plaquemines Expansion's affiliate—Venture Global Plaquemines LNG, LLC—in Plaquemines Parish, Louisiana, (the "Project Site"). The Project facilities will include construction of twelve liquefaction blocks capable of producing up to 18.6 million tonnes per annum ("MTPA") of liquefied natural gas ("LNG"), one marine loading berth for ocean-going vessels, and an on-site 930-megawatt natural gas-fired combined cycle electric generation facility. Plaquemines Expansion will liquefy, store, and deliver LNG as needed to LNG carriers for export overseas. A site layout for the Project is included in Attachment A.

On March 6, 2025, Plaquemines Expansion jointly filed a request with Venture Global Plaquemines LNG, LLC (jointly "the Applicants") to obtain approval from the Director of the Office of Energy Projects of the Federal Energy Regulatory Commission ("Commission") to initiate the Commission's National Environmental Policy Act ("NEPA") pre-filing review of the Project. The FERC officially accepted Plaquemines Expansion's request on April 4, 2025 (See FERC Docket No. PF25-7).

The pre-filing process is meant to increase stakeholder input early in the permitting process by (1) allowing proactive interaction between the prospective applicants, Commission staff, other agencies, landowners, and other stakeholders and (2) identifying and addressing issues during the planning phase before a formal application for authorization of the Project is submitted. At the close of the pre-filing review, the Applicants will file a formal application with the Commission pursuant to Section 3 of the Natural Gas Act.

Plaquemines Expansion expects to file the formal project application in October 2025. Following the receipt of Commission authorization and other necessary approvals, the Applicants plan to begin construction of the Project in early 2027.

Plaquemines Expansion intends to hold public open house meetings in May 2025 to discuss the Project and solicit feedback from impacted parties and the public about the proposed Project. A separate invitation to the open houses will follow in the coming weeks.

If you have any questions, please feel free to contact us at our toll-free line at 1-800-514-0833 or email us at PL3.questions@VENTUREGLOBALLNG.com. You can also visit our website at ventureglobalIng.com for more information on the Project.

If you have a grievance or other concern about the Plaquemines Expansion Project, you can submit an anonymous report though: https://ventureglobal.allvoices.co/ or by calling 1-888-483-9086. Please include as much information as possible including any photograph or attachment which you think is relevant.

We look forward to working with you on the Plaquemines Expansion Project and seeing you at the upcoming open houses. If you have comments or would like to request further information regarding the Project, please contact me at the email address or telephone number listed below.

Respectfully submitted,



AJ Walker
Vice President, Public Affairs & Development
Venture Global LNG, Inc.
AJWalker@ventureglobalIng.com

Enclosure

cc: Fory Musser, Senior Vice President, Venture Global LNG, Inc.
Elizabeth Dolezal, Vice President, Venture Global LNG, Inc.
Jonathan Robillard, Director, Venture Global LNG, Inc.
Charlie Burt, Senior Manager, Venture Global LNG, Inc.

ATTACHMENT A

Plaquemines Expansion Facility Layout

Service Layer Credits: USA_Topo_Maps: Copyright:© 2013 National Geographic Society, i-cubed




Figure 1
Project Location
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 3/5/2025

PLAQUEMINES

1401 McKinney Street, Suite 2600
Houston, TX 77010

O 281.761.9800
www.ventureglobal.com

July 18, 2025

[Contact Name]
[Title]
[Agency Name]
[Address]

Re: Plaquemines Expansion Project

Dear Stakeholder:

Plaquemines Expansion, LLC ("Plaquemines Expansion"), a wholly owned subsidiary of Venture Global, Inc. ("Venture Global"), is writing to provide information to you regarding the Plaquemines LNG Expansion Project ("Project").

Plaquemines Expansion has contractually secured rights to an approximately 600-acre site immediately adjacent to the LNG terminal currently under construction by Plaquemines Expansion's affiliate—Venture Global Plaquemines LNG, LLC—in Plaquemines Parish, Louisiana, (the "Project Site"). On March 6, 2025, Plaquemines Expansion jointly filed a request with Venture Global Plaquemines LNG, LLC (jointly "the Applicants") to obtain approval from the Director of the Office of Energy Projects of the Federal Energy Regulatory Commission ("FERC" or "Commission") to initiate the Commission's National Environmental Policy Act ("NEPA") pre-filing review of the Project. The FERC officially accepted Plaquemines Expansion's request on April 4, 2025 (See FERC Docket No. PF25-7).

Since you were notified of the Project in April, Plaquemines Expansion made the following modifications to the Project:

- Increased the number of liquefaction blocks from 12 to 16;
- Increased the production capacity from 18.6 million tonnes per annum ("MPTA") to 24.8 MTPA;
- Added an additional 586 acres to be used as a laydown area to support construction.

An updated site layout for the proposed Project is included in Attachment A. Plaquemines Expansion expects to file the formal project application in October 2025. Following the receipt of Commission authorization and other necessary approvals, the Applicants plan to begin construction of the Project in early 2027.

If you have any questions, please feel free to contact us at our toll-free line at 1-800-514-0833 or email us at PL3.questions@VENTUREGLOBALLNG.com. You can also visit our website at ventureglobalIng.com for more information on the Project.

If you have a grievance or other concern about the Plaquemines Expansion Project, you can submit an anonymous report though: https://ventureglobal.allvoices.co/ or by calling 1-888-483-9086. Please include as much information as possible including any photograph or attachment which you think is relevant.

We look forward to working with you on the Plaquemines Expansion Project and seeing you at the upcoming open houses. If you have comments or would like to request further information regarding the Project, please contact me at the email address or telephone number listed below.

Respectfully submitted,



AJ Walker
Vice President, Public Affairs & Development
Venture Global, Inc.
AJWalker@ventureglobalIng.com

Enclosure

cc: Fory Musser, Senior Vice President, Venture Global, Inc.
Elizabeth Dolezal, Vice President, Venture Global, Inc.
Jonathan Robillard, Director, Venture Global, Inc.
Charlie Burt, Senior Manager, Venture Global, Inc.

ATTACHMENT A

Plaquemines Expansion Facility Layout

Service Layer Credits: USA NAIP Imagery: Natural Color: Esri, USDA Farm Service Agency




Figure 1.1-1
Regional Location of Proposed Project
Plaquemines Expansion
Plaquemines Parish, Louisiana

Source: Burns & McDonnell

Issued: 7/14/2025

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1
APPENDIX 1F

Landowner List

(Filed Under Separate Cover as Controlled Unclassified Information/Privileged [CUI/PRIV])

PLAQUEMINES EXPANSION PROJECT
RESOURCE REPORT 1
APPENDIX 1G

Stakeholder Lists

(Filed Under Separate Cover as Controlled Unclassified Information/Privileged [CUI/PRIV])